

# SUMMARY OF QUANTITIES

F.A.I. RATE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
.80	37-UHR-J	HENRY	133	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CODE NUMBER	ITEM	UNITS	90%-FED 10%-STATE NHS			80%-FED 20%-STATE BR		
			URBAN TOTAL	1000 ROADWAY	X771-2A BRIDGE	URBAN TOTAL	1000 ROADWAY	X771-2A BRIDGE
542A4021	PIPE CULVERTS, CLASS A, TYPE 6 36"	FOOT	362	362				
542C1075	PIPE CULVERTS, CLASS C, TYPE 2 30"	FOOT	85	85				
542D1060	PIPE CULVERTS, CLASS D, TYPE 2 15"	FOOT	199	199				
54205890	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL, EQUIVALENT ROUND-SIZE 15"	FOOT	56	56				
54213447	END SECTIONS 12"	EACH	4	4				
54213450	END SECTIONS 15"	EACH	4	4				
54213465	END SECTIONS 30"	EACH	2	2				
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	4	4				
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	4	4				
54214290	END SECTIONS, EQUIVELANT ROUND-SIZE 15"	EACH	2	2				
54247170	GRATING FOR CONCRETE FLARED END SECTION 36"	EACH	2	2				
* 56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	1	1				
59100100	GEOCOMPOSITE WALL DRAIN	SQ. YD.	112.5		112.5			
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	6	2	4			
60100070	SHOULDER REMOVAL AND REPLACEMENT	FOOT	100	100				
60100945	PIPE DRAINS 12"	FOOT	291	291				
60107600	PIPE UNDERDRAINS 4"	FOOT	79		79			
60107700	PIPE UNDERDRAINS 6"	FOOT	200	200				
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	163		163			
* 60255500	MANHOLES TO BE ADJUSTED	EACH	4	4				
* 60265700	VALVE VAULTS TO BE ADJUSTED	EACH	2	2				
60600095	CLASS SI CONCRETE (OUTLET)	CU. YD.	20.1	20.1				
60602500	CONCRETE GUTTER, TYPE A	FOOT	98	98				
60611815	COMBINATION CONCRETE CURB AND GUTTER, TYPE M (SPECIAL)	FOOT	79	79				
60900140	TYPE B INLET BOX, STANDARD 609006	EACH	4	4				
60900515	CONCRETE THRUST BLOCKS	EACH	4	4				
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	4	4				
61140000	STORM SEWERS, SPECIAL 8"	FOOT	100	100				
61140100	STORM SEWERS, SPECIAL 10"	FOOT	100	100				
61140200	STORM SEWERS, SPECIAL 12"	FOOT	100	100				

\*SPECIALTY ITEM

CODE NUMBER	ITEM	UNITS	90%-FED 10%-STATE NHS			80%-FED 20%-STATE BR		
			URBAN TOTAL	1000 ROADWAY	X771-2A BRIDGE	URBAN TOTAL	1000 ROADWAY	X771-2A BRIDGE
63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	762.5	762.5				
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4				
63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	4				
63200310	GUARD RAIL REMOVAL	FOOT	2850	2850				
63500105	DELINEATORS	EACH	10	10				
64200105	SHOULDER RUMBLE STRIP	FOOT	200	200				
66500105	WOVEN WIRE FENCE, 4"	FOOT	1,612	1,612				
66502000	WOVEN WIRE GATES, 4' X 24' DOUBLE	EACH	1	1				
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	33	33				
66700305	PERMANENT SURVEY MARKERS, TYPE 2	EACH	3	3				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL. MO.	9	9				
67100100	MOBILIZATION	L. SUM	1	1				
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	2	2				
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L. SUM	1	1				
70100460	TRAFFIC CONTROL & PROTECTION, STANDARD 701306	L. SUM	1	1				
70100700	TRAFFIC CONTROL & PROTECTION, STANDARD 701406	L. SUM	1	1				
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L. SUM	1	1				
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L. SUM	1	1				
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL. DA.	30	30				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	42	42				
70300220	TEMPORARY PAVEMENT MARKING LINE 4"	FOOT	8056	8056				
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	3550	3550				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ. FT.	3,657	3,657				
70400100	TEMPORARY CONCRETE BARRIER	FOOT	800	800				
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	800	800				
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	16888	16888				
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	24	24				
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	3		3			
78200410	GUARDRAIL MARKERS, TYPE A	EACH	19	19				
78200520	BARRIER WALL MARKERS, TYPE B	EACH	12		12			

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_  
 DATE \_\_\_\_\_

DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_

PLOT DATE = Tue Sep 12 13:32:19 2006  
 FILE NAME = c:\p\proj\p213180\4131026\p213180.dgn  
 PLOT SCALE = 50.0000 / IN.  
 USER NAME = rntesal

## SUMMARY OF QUANTITIES