

F.A. I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	37-UHBR-1	HENRY	133	8
STA.	TO STA.			
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNITS	URBAN		90%-FED 10%-STATE NHS	80%-FED 20%-STATE BR
			TOTAL	1000 ROADWAY	X771-2A BRIDGE	
78201000	TERMINAL MARKER-DIRECT APPLIED	EACH	4	4		
78200530	BARRIER WALL MARKERS, Type C	EACH	52	52		
Z0002600	BAR SPLICERS	EACH	66			66
Z0013798	CONSTRUCTION LAYOUT	L. SUM	1	1		
Z0020900	ESTABLISHING AND REFERENCING LAND SECTION MARKERS	EACH	1	1		
Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	28	28		
Z0030030	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2			2
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2			2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2			2
Z0049800	RELOCATE EXISTING SURVEY MARKERS	EACH	23	23		
Z0069400	STONE WELLS, SPECIAL	EACH	4	4		
Z0047300	PROTECTIVE SHIELD	SQ. YD.	455.7			455.7
A2006714	TREE, QUERCUS MACROCARPA (BUR OAK), 1 3/4" CALIPER, BALLED AND BURLAPPED	EACH	20	20		
B2000116	TREE, ACER CAMPESTRE (HEDGE MAPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	10	10		
B2003714	TREE, MALUS INDIAN SUMMER (INDIAN SUMMER CRABAPPLE), 1 3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	8	8		
B2005014	TREE, MALUS SNOWDRIFT (SNOWDRIFT CRABAPPLE), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	8	8		
XX004900	TURF REINFORCEMENT MAT	SQ. YD.	87	87		
X0325278	DRIVING PILES	FOOT	1627			1627
X0325519	DRAIN FOR AGGREGATE BASE COURSE	SQ. YD.	14	14		
X0712400	TEMPORARY PAVEMENT	SQ. YD.	893.5	893.5		
X0919000	TEMPORARY PAVEMENT REMOVAL	SQ. YD.	893.5	893.5		
X4021000	TEMPORARY ACCESS - PRIVATE ENTRANCE	EACH	4	4		
X4024000	TEMPORARY ACCESS - FIELD ENTRANCE	EACH	3	3		
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	77.4	77.4		
X4073051	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 8-1/2"	SQ. YD.	7422.85	7422.85		
X7013015	TRAFFIC CONTROL FOR ROAD CLOSURE	L. SUM	1	1		

* SPECIALTY ITEMS

PLOT DATE = Tue Sep 12 10:35:31 2006
 FILE NAME = c:\p\projects\213180\213180.dgn
 PLOT SCALE = 50.0000' / IN.
 USER NAME = renkwalj

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. _____
 HORIZ. _____

DATE _____

DRAWN BY _____
 CHECKED BY _____

SUMMARY OF QUANTITIES