

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	37-IHBR-1	HENRY	133	14
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

EARTHWORK SCHEDULE

EARTH WORK SCHEDULE					
20200100 - EARTH EXCAVATION					
20400800 - FURNISHED EXCAVATION					
LOCATION	EARTH EXC (CUT) CU YD	EARTH EXC ADJ SHRINK 25% CU YD	EMBANK (FILL) CU YD	EARTH WORK BALANCE	
				WASTE (+)	SHORTAGE (-)
				CU YD	CU YD
34 + 50 - 41 + 00	1778	1334	28	1306	
41 + 00 - 47 + 00	2047	1536	3028	-1492	
47 + 00 - 53 + 00	1285	964	10300	-9336	
53 + 00 - 59 + 00	188	141	16136	-15996	
59 + 00 - 64 + 00	3054	2290	3981	-1691	
TOTAL	8352	6264	33473	-27209	
SIDEROADS					
CARROLL STREET STAGE I					
100 + 13 - 102 + 00	373	280	74	205	
CARROLL STREET STAGE II					
100 + 13 - 102 + 00	111	83	270	-187	
CARROLL STREET STAGE III					
100 + 13 - 102 + 00	171	128	0	128	
TOTAL - CARROLL STREET	654	491	344	147	

PLOT DATE = Fri Sep 01 10:52:57 2006
 FILE NAME = c:\pcc\meta\213108\213108.dgn
 PLOT SCALE = 5/8"=1'-0"
 USER NAME = rwhal

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. DRAWN BY HORIZ. CHECKED BY DATE