

SCHEDULE OF QUANTITIES

| | | | | |
|---------------------|-----------|---------------------------|--------------|-----------|
| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 180 | 37-14BR-1 | HENRY | 133 | 18 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | | ILLINOIS FED. AID PROJECT | | |

542D1060 PIPE CULVERTS, CLASS D, TYPE 2 15"

| FOOT | LOCATION | |
|------|------------|--------------|
| 81 | STA. 60+00 | FE-RT |
| 62 | STA. 60+00 | FE-LT |
| 56 | STA. 63+00 | FE-RT (TEMP) |
| 199 | TOTAL | |

54205890 PIPE CULVERTS, TYPE 1, CORRUGATED STEEL, EQUIVALENT ROUND-SIZE 15"

| FOOT | LOCATION | |
|------|------------|-------|
| 56 | STA. 41+64 | FE-LT |
| 56 | TOTAL | |

54213447 END SECTIONS 12"

| EACH | LOCATION | |
|------|--------------|----|
| 1 | STA. 50+56.9 | LT |
| 1 | STA. 50+56.9 | RT |
| 1 | STA. 52+90.9 | LT |
| 1 | STA. 52+90.9 | RT |
| 4 | TOTAL | |

54213450 END SECTIONS 15"

| EACH | LOCATION | |
|------|------------|-------|
| 2 | STA. 60+00 | FE-LT |
| 2 | STA. 60+00 | FE-RT |
| 4 | TOTAL | |

54213465 END SECTIONS 30"

| EACH | LOCATION | |
|------|----------------|-------------|
| 2 | STA. 100+41.28 | CARROLL ST. |
| 2 | TOTAL | |

54213675 PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"

| EACH | LOCATION | |
|------|---------------|------------|
| 2 | STA. 46+00 | AR CULVERT |
| 2 | STA. 60+58.59 | AR CULVERT |
| 4 | TOTAL | |

54213681 PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"

| EACH | LOCATION | |
|------|-------------|---------|
| 1 | STA. 460+75 | I-80 LT |
| 1 | STA. 461+00 | I-80-RT |
| 1 | STA. 462+75 | I-80-LT |
| 1 | STA. 463+00 | I-80-RT |
| 4 | TOTAL | |

54214290 END SECTIONS, EQUIVALENT ROUND-SIZE 15"

| EACH | LOCATION | |
|------|------------|-------|
| 2 | STA. 41+64 | FE-LT |
| 2 | TOTAL | |

54247170 GRATING FOR CONCRETE FLARED END SECTION 36"

| EACH | LOCATION | |
|------|-------------|---------|
| 1 | STA. 462+75 | I-80 LT |
| 1 | STA. 461+00 | I-80 RT |
| 2 | TOTAL | |

56400300 FIRE HYDRANTS TO BE ADJUSTED

| EACH | LOCATION | |
|------|-------------|--------|
| 1 | STA. 101+80 | 30' LT |
| 1 | TOTAL | |

60100060 CONCRETE HEADWALL FOR PIPE DRAIN

| EACH | LOCATION | |
|------|--------------|---------------------------|
| 2 | STA. 50+68.9 | RT & LT - ABUTMENT DRAINS |
| 2 | STA. 52+78.9 | RT & LT - ABUTMENT DRAINS |
| 1 | STA. 460+69 | I-80 LT (CONTINGENCY) |
| 1 | STA. 463+04 | I-80 RT (CONTINGENCY) |
| 6 | TOTAL | |

60100070 SHOULDER REMOVAL AND REPLACEMENT

| FOOT | LOCATION | |
|------|---------------------------|--------------|
| 100 | STA. 461+50.0 TO 462+00.0 | I-80 LT & RT |
| 100 | TOTAL | |

60100945 PIPE DRAINS 12"

| FOOT | LOCATION | |
|------|--------------|----|
| 46 | STA. 50+56.9 | LT |
| 103 | STA. 50+56.9 | RT |
| 78 | STA. 52+90.9 | LT |
| 64 | STA. 52+90.9 | RT |
| 291 | TOTAL | |

PLOT DATE = Mon Oct 02 09:34:30 2006
 FILE NAME = C:\p\2006\213182\103182.dgn
 PLOT SCALE = 50.0000 / IN.
 USER NAME = reakea

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. / HORIZ.
DATE

DRAWN BY
CHECKED BY

SCHEDULE OF QUANTITIES