

# SCHEDULE OF QUANTITIES

F.A.L. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
..80	..37-LHRR-J	..HENRY	..133	..19
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

**60107600 PIPE UNDERDRAINS 4"**

FOOT	LOCATION	
10	STA. 50+68.9	LT
25	STA. 50+68.9	RT
27	STA. 52+78.9	LT
17	STA. 52+78.9	RT
<u>79</u>	TOTAL	

**60107700 PIPE UNDERDRAINS 6"**

FOOT	LOCATION	
200	STA. 460+50 TO 463+00	I-80 RT & LT (CONTINGENCY)
<u>200</u>	TOTAL	

**60255500 MANHOLES TO BE ADJUSTED**

EACH	LOCATION	
1	STA. 37+84.76	18.35' RT
1	STA. 41+51.84	15.88' RT
1	STA. 43+95.64	26.60' RT
1	STA. 101+10.36	11.83' RT
<u>4</u>	TOTAL	

**60265700 VALVE VAULTS TO BE ADJUSTED**

EACH	LOCATION	
1	STA. 100+35.76	33' RT
1	STA. 101+77.29	26.70' LT
<u>2</u>	TOTAL	

**60600095 CLASS SI CONCRETE (OUTLET)**

CU. YD.	LOCATION	
1.67	STA. 38+30 TO 38+53	OUTLET-LT
3.75	STA. 40+05 TO 40+50	OUTLET-LT
0.92	STA. 461+92 TO 462+04	I-80 GUTTER INLET LT
5.67	STA. 460+51 TO 461+15	I-80 OUTLET LT
0.92	STA. 461+43 TO 461+55	I-80 GUTTER INLET RT
7.13	STA. 462+44 TO 463+24	I-80 OUTLET RT
<u>20.1</u>	TOTAL	

**60602500 CONCRETE GUTTER, TYPE A**

FOOT	LOCATION	
55	STA. 461+90 TO 462+45	I-80 RT
43	STA. 461+15 TO 461+58	I-80 LT
<u>98</u>	TOTAL	

**60611815 COMBINATION CONCRETE CURB AND GUTTER, TYPE M (SPECIAL)**

FOOT	LOCATION	
32	STA. 38+53 TO 38+85	LT
47	STA. 39+53 TO 40+00	LT
<u>79</u>	TOTAL	

**60900140 TYPE B INLET BOX, STANDARD 609006**

EACH	LOCATION	
2	STA. 50+56.9	LT & RT
2	STA. 52+90.9	LT & RT
<u>4</u>	TOTAL	

**60900515 CONCRETE THRUST BLOCKS**

EACH	LOCATION	
1	STA. 50+56.9	LT
1	STA. 50+56.9	RT
1	STA. 52+90.9	LT
1	STA. 52+90.9	RT
<u>4</u>	TOTAL	

**61133100 FIELD TILE JUNCTION VAULTS, 2' DIA.**

EACH	LOCATION	
2	STA. 35+90 TO 50+70.90	(CONTINGENCY)
2	STA. 52+76.90 TO 63+70	(CONTINGENCY)
<u>4</u>	TOTAL	

**61140000 STORM SEWERS, SPECIAL 8"**

FOOT	LOCATION	
100	STA. 35+90 TO 63+70	(CONTINGENCY)
<u>100</u>	TOTAL	

**61140100 STORM SEWERS, SPECIAL 10"**

FOOT	LOCATION	
100	STA. 35+90 TO 63+70	(CONTINGENCY)
<u>100</u>	TOTAL	

**61140200 STORM SEWERS, SPECIAL 12"**

FOOT	LOCATION	
100	STA. 35+90 TO 63+70	(CONTINGENCY)
<u>100</u>	TOTAL	

**63000000 STEEL PLATE BEAM GUARD RAIL, TYPE A**

FOOT	LOCATION	
437.5	STA. 46+03.40 TO 50+40.9	LT
112.5	STA. 49+28.4 TO 50+40.9	RT
112.5	STA. 53+06.9 TO 54+19.4	LT
100.0	STA. 53+06.9 TO 54+06.9	RT
<u>762.5</u>	TOTAL	

PLOT DATE = Mon, Oct 02, 09:24:41, 2006  
 FILE NAME = C:\213100\213100.dgn  
 PLOT SCALE = 50.0000 / IN.  
 USER NAME = rnkswlj

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_

DATE \_\_\_\_\_

DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_