

SUMMARY OF QUANTITIES

CODE NO	SUMMARY OF QUANTITIES ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE
			100% STATE	ROADWAY 1000-2A
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	20	20
20200100	EARTH EXCAVATION	CU YD	2,094	2,094
20400800	FURNISHED EXCAVATION	CU YD	411	411
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	1,078	1,078
* 25000210	SEEDING, CLASS 2A	ACRE	1.00	1.00
* 25000310	SEEDING, CLASS 4	ACRE	1.25	1.25
* 25000750	MOWING	ACRE	2.25	2.25
* 25100115	MULCH, METHOD 2	ACRE	2.25	2.25
25100630	EROSION CONTROL BLANKET	SQ YD	1,255	1,255
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	900	900
28000300	TEMPORARY DITCH CHECKS	EACH	59	59
28000400	PERIMETER EROSION BARRIER	FOOT	172	172
28000500	INLET AND PIPE PROTECTION	EACH	5	5
28100207	STONE RIPRAP, CLASS A4	TON	697	697
28200200	FILTER FABRIC	SQ YD	1,047	1,047
35101100	AGGREGATE BASE COURSE, TYPE A 12"	SQ YD	1,521	1,521
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	65	65
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	168	168
40600990	TEMPORARY RAMP	SQ YD	28	28
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	253	253
44000100	PAVEMENT REMOVAL	SQ YD	108	108
44001430	BITUMINOUS SHOULDER REMOVAL	SQ YD	395	395
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	24	24
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	38	38
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	2,458	2,458
48101200	AGGREGATE SHOULDERS, TYPE B	TON	228	228
48202410	BITUMINOUS SHOULDERS SUPERPAVE 6 1/2"	SQ YD	708	708
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	1
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1	1
542A1093	PIPE CULVERTS, CLASS A, TYPE 2 48"	FOOT	96	96
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	30	30
542D0235	PIPE CULVERTS, CLASS D, TYPE 1 30"	FOOT	232	232
54213450	END SECTIONS 15"	EACH	2	2
54213465	END SECTIONS 30"	EACH	2	2

CODE NO	SUMMARY OF QUANTITIES ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE
			100% STATE	ROADWAY 1000-2A
5422D042	PIPE CULVERTS, CLASS D, TYPE 2 42" (TEMPORARY)	FOOT	16	16
61100500	EXPLORATION TRENCH 52" DEPTH	FOOT	200	200
61100605	MISCELLANEOUS CONCRETE	CU YD	3	3
61101013	STORM SEWERS PROTECTED, CLASS A, 12"	FOOT	220	220
61101017	STORM SEWERS PROTECTED, CLASS A, 15"	FOOT	100	100
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA	EACH	4	4
61133200	FIELD TILE JUNCTION VAULTS, 3' DIA	EACH	1	1
63500105	DELINEATORS	EACH	17	17
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	33	33
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2	2
67100100	MOBILIZATION	L SUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	246	246
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	41	41
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	7,720	7,720
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	16	16
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	16	16
* A2007814	TREE, TILIA AMERICANA (AMERICAN LINDEN/BASSWOOD), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	2	2
X0322263	CULVERT DROP BOX	EACH	1	1
X0950100	PIPE CULVERT REMOVAL 15"	FOOT	10	10
X3560130	BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 9 INCH	SQ YD	859	859
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	362	362
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	715	715
X4420500	TEMPORARY PAVEMENT PATCH	SQ YD	62	62
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
Z0020900	ESTABLISHING AND REFERENCING LAND SECTION MARKERS	EACH	1	1
Z0023600	FILLING EXISTING CULVERTS	EACH	2	2
Z0029001	GRATED CULVERT EXTENSION, NO 1	EACH	1	1
X0325587	CORRUGATED STEEL PIPE MULTIPLE END SECTIONS DOUBLE 30"	EACH	2	2

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**FAP ROUTE 17
SUMMARY OF QUANTITIES**

DRAWN BY TJD
CHECKED BY AWM
DATE 8/22/2006