

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2247	13X-BR-1	BUREAU	51	8
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

63000000

STEEL PLATE BEAM GUARD RAIL, TYPE A		FOOT
LOCATION		
STA 1507+74.28, 16' TO STA 1509+61.25, 16' RT		187.5
STA 1511+50.47, 16' TO STA 1512+12.97, 16' RT		62.5
STA 1511+69.42, 16' TO STA 1513+31.92, 16' LT		162.5
STA 1509+81.43, 18.4' TO STA 100+60.54, 27.9' RT		43.75
TOTAL		456

63500105

DELINEATORS		EACH
LOCATION		
STA 101+05.00, LT.		1
STA 101+09.62, RT.		1
STA 1507+24.58, RT.		1
STA 1512+62.97, RT.		1
STA 1513+81.92, LT.		1
TOTAL		5

78200520

BARRIER WALL MARKERS, TYPE B *		EACH
LOCATION		
BRIDGE		4
TOTAL		4

\* MARKERS SHALL BE BIDIRECTIONAL SILVER/ SILVER

63100085

TRAFFIC BARRIER TERMINAL TYPE 6		EACH
LOCATION		
STA 1509+91.86, RT		1
STA 1510+11.78, LT		1
STA 1511+19.82, RT		1
STA 1511+38.78, LT		1
TOTAL		4

THERMOPLASTIC PAVEMENT MARKING			
LOCATION	78000200	78000200	78000650
	4" WHITE	4" YELLOW	24" WHITE
	FOOT	FOOT	FOOT
STA 100+68.49			11
STA 100+70.50 TO STA 101+46.43		152	
STA 101+46.43 TO STA 1513+62.50, LT.	520		
STA 1506+80.00 TO STA 101+46.43, LT.	342		
STA 1506+80.00 TO STA 1513+62.50	683	1365	
TOTAL	1545	1517	11

78201000

TERMINAL MARKER - DIRECT APPLIED		EACH
LOCATION		
1 AT EACH TYPE 1 TERMINAL		4
TOTAL		4

63100167

TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)		EACH
LOCATION		
STA 100+60.54, RT.		1
STA 1507+74.28, RT.		1
TOTAL		2

78100100

RAISED REFLECTIVE PAVEMENT MARKER		EACH
LOCATION		
STA 1506+80.00 TO STA 1513+62.50		7
TOTAL		7

78300200

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL		EACH
LOCATION		
STA 1506+80.00 TO STA 1513+62.50		7
TOTAL		7

63100169

TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)		EACH
LOCATION		
STA 1512+12.97, RT.		1
STA 1513+31.92, LT.		1
TOTAL		2

78100105

RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)		EACH
LOCATION		
STA 1510+02.30 TO STA 1511+29.30		2
TOTAL		2

X0324043

GRATING FOR CONCRETE HEADWALL		EACH
LOCATION		
STA 101+00.00, LT.		1
TOTAL		1

78200410

GUARDRAIL MARKERS, TYPE A		EACH
LOCATION		
STA 1507+24.58 TO STA 1513+81.30		8
TOTAL		8

63200310

GUARDRAIL REMOVAL		FOOT
LOCATION		
STA 1507+52.08 (20' O/S) TO STA 1509+77.19 (17' O/S)		292
STA 1509+61.18 (43' O/S) TO STA 1513+83.37 (18' O/S)		365
TOTAL		657

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF QUANTITIES  
 FAS 2247 (U.S. 6)  
 OVER BRUSH CREEK  
 SECTION 13X-BR-1  
 BUREAU COUNTY

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_  
 DATE: 03/06  
 DRAWN BY KKP  
 CHECKED BY JKC