

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
627	(I-1) BR & I	LA SALLE	106	4
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOI	FED. AID PROJECT		

← 80% FEDERAL 20% STATE →

← 80% FEDERAL 20% STATE →

CODE NUMBER	ITEM	UNIT	TOTAL	ROADWAY 1000	CULVERT @ STA 393+00 Y007	STRUCTURE NO. 050-C804 Y007	STRUCTURE NO. 050-W004 Y007	STRUCTURE NO. 050-0239 X081-2A
50700215	FURNISHING SOLDIER PILES (W SECTION)	FOOT	1168				1168	
50800105	REINFORCEMENT BARS	POUND	15,470		3130	12,340		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	51,550		700	1800	21,220	27,830
51201610	FURNISHING STEEL PILES HP12X63	FOOT	150					150
51202700	DRIVING STEEL PILES	FOOT	150					150
51203610	TEST PILE STEEL HP12X63	EACH	2					2
51500100	NAME PLATES	EACH	3			1	1	1
54011008	PRECAST CONCRETE BOX CULVERT 10'X8'	FOOT	70		70			
54213447	END SECTIONS 12"	EACH	3	3				
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	42	42				
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	26	26				
55100700	STORM SEWER REMOVAL 15"	FOOT	70	70				
59100100	GEOCOMPOSITE WALL DRAIN	SQ. YD.	416			68	259	89
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	3	3				
60100945	PIPE DRAINS 12"	FOOT	63	63				
60100955	PIPE DRAINS 15"	FOOT	32	32				
60107700	PIPE UNDERDRAINS 6"	FOOT	1040	1040				
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	369				265	104
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1				
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	1	1				
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	1	1				
60500060	REMOVING INLETS	EACH	3	3				

* SPECIALTY ITEM

CODE NUMBER	ITEM	UNIT	TOTAL	ROADWAY 1000	CULVERT @ STA 393+00 Y007	STRUCTURE NO. 050-C804 Y007	STRUCTURE NO. 050-W004 Y007	STRUCTURE NO. 050-0239 X081-2A
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	454	454				
60900140	TYPE B INLET BOX, STANDARD 609006	EACH	1	1				
60900150	TYPE B INLET BOX, STANDARD 609006 (SPECIAL)	EACH	1	1				
60900515	CONCRETE THRUST BLOCKS	EACH	3	3				
63000005	STEEL PLATE BEAM GUARD RAIL, TYPE B	FOOT	1200	1200				
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4				
63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	3	3				
63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	1523	1523				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	22	22				
67100100	MOBILIZATION	L SUM	1	1				
70103700	TRAFFIC CONTROL COMPLETE	L SUM	1	1				
72000100	SIGN PANEL - TYPE 1	SQ. FT.	93	93				
78001110	PAINT PAVEMENT MARKING-LINE 4"	FOOT	3076	3076				
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	24	24				
78200400	GUARDRAIL REFLECTORS	EACH	48	48				
78200530	BARRIER WALL MARKERS, TYPE C	EACH	6	6				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	24	24				
Z0002600	BAR SPLICERS	EACH	72					72
Z0005215	BITUMINOUS STABILIZATION 6" AT STEEL PLATE BEAM GUARD RAIL	SQ. YD.	345	345				
Z0017900	DRAINAGE SCUPPERS, DS-12	EACH	2					2
Z0020800	EROSION CONTROL CURB	FOOT	131	131				
Z0040530	PIPE UNDERDRAIN REMOVAL	FOOT	591	591				

* SPECIALTY ITEM

DESIGNED BY MSW	 Farnsworth GROUP 2709 McGraw Drive Bloomington, Illinois 61704 308/832-0436, 308/889-1871 fax	FILE NO. 24-6772
DRAWN BY DJM		DATE 05/12/06
CHECKED BY MSW		SHEET NO. 4 OF 106

SUMMARY OF QUANTITIES	
IL ROUTE 71 OVER TRIBUTARY TO ILLINOIS RIVER F.A.P. ROUTE 627 - SEC. (I-1 BR & I LA SALLE COUNTY	