

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
627	(I-1) BR & I	LA SALLE	106	10
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

STORM SEWERS									
LOCATION	REMOVAL 15"	CLASS A, TY 1, 12"	CLASS A, TY 1, 15"	PIPE DRAIN 12"	PIPE DRAIN 15"	END SECTIONS 12"	PIPE ELBOW 12"	PIPE ELBOW 15"	MH. TY A, 4' DIA TY 1 FRAME, CLOSED LID
	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH
STRUCTURE NO. 050-C804									
STA. 416+26 LT								1	
STA. 416+26 RT								1	
STA. 416+26 LT TO STA. 416+52 LT			26						
STA 416+26 12.58' LT TO STA 416+26 41' LT					32				
STA. 416+28 LT	35								
STA. 416+62 LT	35								
STRUCTURE NO. 050-0239									
STA. 464+61 RT				20		1			
STA. 464+81 LT TO RT		42							
STA. 464+81 RT				16		1	2		1
STA. 465+85 LT							2		
STA 465+89 LT				27		1			
TOTAL	70	42	26	63	32	3	4	2	1

INLETS					
LOCATION	REMOVAL	INLETS TY. A TY. 3 FR & GR	INLETS TY. B TY. 3 FR & GR	TY. B INLET BOX STANDARD 609006	TY. B INLET BOX STANDARD (SPECIAL) 609006
	EACH	EACH	EACH	EACH	EACH
STRUCTURE NO. 050-C804					
STA. 416+52.55 LT		1			
STA. 416+26 LT			1		
STA. 416+28 LT	1				
STA. 416+69 LT	1				
STRUCTURE NO. 050-0239					
STA. 464+81 LT					1
STA. 465+27 LT	1				
STA. 465+89 LT				1	
TOTAL	3	1	1	1	1


RIPRAP			
LOCATION	CLASS A5	CLASS A4	FILTER FABRIC
	TON	SQ. YD.	SQ. YD.
CULVERT @ STA. 437+31			
STA. 437+31 LT (DOWNSTREAM)	261		64
STA. 437+31 RT (UPSTREAM)	31		25
STRUCTURE NO. 050-0239			
STA. 463+00 TO STA. 464+81 RT		108	108
STA. 464+70 RT		3	3
STA. 464+81 RT		45	45
STA. 465+89 LT		8	8
TOTAL	292	164	253

BRIDGE APPROACH PAVEMENT				
LOCATION	BRIDGE APP. PAVEMENT	BRIDGE APP. CONNECT. (PCC)	PROTECTIVE COAT	BRIDGE DECK GROOVING
	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.
STRUCTURE NO. 050-0239				
STA. 464+62.82 TO STA. 464+68.80		25		
STA. 464+68.80 TO STA. 464+98.80	122		125	114
STA. 465+71.96 TO STA. 466+01.96	122		125	114
STA. 466+01.96 TO STA. 466+07.96		25		
TOTAL	244	50	250	228

PAVEMENT REMOVAL	
LOCATION	SQ. YD.
CULVERT @ STA. 393+00	
STA. 392+65 TO STA. 393+35	205
STRUCTURE NO. 050-C804	
STA. 416+08 TO STA. 416+83	185
STRUCTURE NO. 050-0239	
STA. 463+00 TO STA. 463+50	133
STA. 464+65.8 TO STA. 466+05	371
STA. 467+00 TO STA. 467+55	147
TOTAL	1041

SCHEDULE OF QUANTITIES

IL ROUTE 71
OVER TRIBUTARY TO ILLINOIS RIVER
F.A.P. ROUTE 627 - SEC. (I-1) BR & I
LA SALLE COUNTY

DESIGNED BY MSW	 <p>2708 McDrew Drive Bloomington, Illinois 61704 309/983-8635, 309/983-1871 fax</p>	FILE NO. 24-6772
DRAWN BY DJM		DATE 05/12/06
CHECKED BY MSW		SHEET NO. 10 OF 106