

|                     |         |                           |              |           |
|---------------------|---------|---------------------------|--------------|-----------|
| F.A.P. RTE.         | SECTION | COUNTY                    | TOTAL SHEETS | SHEET NO. |
| 67                  | U-BR    | LA SALLE                  | 38           | 3         |
| STA.                |         | TO STA.                   |              |           |
| FED. ROAD DIST. NO. |         | ILLINOIS FED. AID PROJECT |              |           |

ACF ACBRF

← 80% FED 20% STATE →

ROADWAY SN 050-0243 EX SN 050-0030

| SUMMARY OF QUANTITIES |   |       |            | CONSTRUCTION TYPE CODE |         |  |
|-----------------------|---|-------|------------|------------------------|---------|--|
| CODE NO               | ITEM  | UNIT  | TOTAL QNTY | 1000                   | X080-2A |  |
| 20100110              | TREE REMOVAL (6 TO 15 UNITS DIAMETER)         | UNIT  | 33         | 33                     | 0       |  |
| 20100210              | TREE REMOVAL (OVER 15 UNITS DIAMETER)         | UNIT  | 18         | 18                     | 0       |  |
| 20101000              | TEMPORARY FENCE                               | FOOT  | 350        | 350                    | 0       |  |
| 20200100              | EARTH EXCAVATION                              | CU YD | 268        | 268                    | 0       |  |
| 20300100              | CHANNEL EXCAVATION                            | CU YD | 162        | 162                    | 0       |  |
| 20400800              | FURNISHED EXCAVATION                          | CU YD | 84         | 84                     | 0       |  |
| 20700400              | POROUS GRANULAR EMBANKMENT, SPECIAL           | CU YD | 78         | 0                      | 78      |  |
| * 25000200            | SEEDING, CLASS 2                              | ACRE  | 0.5        | 0.5                    | 0       |  |
| * 25000400            | NITROGEN FERTILIZER NUTRIENT                  | POUND | 31         | 31                     | 0       |  |
| * 25000500            | PHOSPHORUS FERTILIZER NUTRIENT                | POUND | 31         | 31                     | 0       |  |
| * 25000600            | POTASSIUM FERTILIZER NUTRIENT                 | POUND | 31         | 31                     | 0       |  |
| * 25100115            | MULCH, METHOD 2                               | ACRE  | 0.2        | 0.2                    | 0       |  |
| * 25100630            | EROSION CONTROL BLANKET                       | SQ YD | 947        | 947                    | 0       |  |
| 28000300              | TEMPORARY DITCH CHECKS                        | EACH  | 8          | 8                      | 0       |  |
| 28000250              | TEMPORARY EROSION CONTROL SEEDING             | POUND | 34         | 34                     | 0       |  |
| 28000400              | PERIMETER EROSION BARRIER                     | FOOT  | 550        | 550                    | 0       |  |
| 28100107              | STONE RIPRAP, CLASS A4                        | SQ YD | 234        | 0                      | 234     |  |
| 40600100              | BITUMINOUS MATERIALS (PRIME COAT)             | GAL   | 156.1      | 156.1                  | 0       |  |
| 40600300              | AGGREGATE (PRIME COAT)                        | TON   | 3.9        | 3.9                    | 0       |  |
| 40600980              | BITUMINOUS SURFACE REMOVAL - BUTT JOINT       | SQ YD | 189        | 189                    | 0       |  |
| 40600990              | TEMPORARY RAMP                                | SQ YD | 204        | 204                    | 0       |  |
| 42001165              | BRIDGE APPROACH PAVEMENT                      | SQ YD | 213        | 213                    | 0       |  |
| 42001300              | PROTECTIVE COAT                               | SQ YD | 365        | 0                      | 365     |  |
| 42001430              | BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE) | SQ YD | 43         | 43                     | 0       |  |
| 44000100              | PAVEMENT REMOVAL                              | SQ YD | 249        | 249                    | 0       |  |
| 44000710              | BITUMINOUS BASE COURSE REMOVAL                | SQ YD | 353        | 353                    | 0       |  |
| 44001430              | BITUMINOUS SHOULDER REMOVAL                   | SQ YD | 126        | 126                    | 0       |  |
| 44000030              | BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)   | SQ YD | 564        | 564                    | 0       |  |
| 48101200              | AGGREGATE SHOULDERS, TYPE B                   | TON   | 18         | 18                     | 0       |  |
| 48202000              | BITUMINOUS SHOULDERS SUPERPAVE                | TON   | 15         | 15                     | 0       |  |
| 48202600              | BITUMINOUS SHOULDERS SUPERPAVE 8"             | SQ YD | 577        | 577                    | 0       |  |
| 50100100              | REMOVAL OF EXISTING STRUCTURES                | EACH  | 1          | 0                      | 1       |  |
| 50200100              | STRUCTURE EXCAVATION                          | CU YD | 140        | 0                      | 140     |  |
| 50300100              | FLOOR DRAINS                                  | EACH  | 12         | 0                      | 12      |  |
| 50300225              | CONCRETE STRUCTURES                           | CU YD | 56.9       | 0                      | 56.9    |  |
| 50300255              | CONCRETE SUPERSTRUCTURE                       | CU YD | 202.5      | 0                      | 202.5   |  |
| 50300260              | BRIDGE DECK GROOVING                          | SQ YD | 273        | 0                      | 273     |  |
| 50800205              | REINFORCEMENT BARS, EPOXY COATED              | POUND | 48800      | 0                      | 48800   |  |
| 51201400              | FURNISHING STEEL PILES HP10X42                | FOOT  | 198        | 0                      | 198     |  |

\* SPECIALTY ITEM

| REVISIONS |      |
|-----------|------|
| NAME      | DATE |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
IL ROUTE 71 OVER UNNAMED STREAM  
FAP RT 67, SECTION U-BR  
LA SALLE COUNTY

**COOMBE-BLOXDORF P.C.**  
Engineers / Land Surveyors  
Springfield, Illinois  
Design Firm License No. 184-002703

SCALE:  
DATE: 01/13/06

DRAWN BY  
CHECKED BY

DATE = 05/30/2006  
PLOT SCALE = 1/8" = 1'-0"  
USER NAME = DFC