

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	*	KANKAKEE	24	4

(11X-2)RS-1 & (11,1)RS-4

SUMMARY OF QUANTITIES

CONSTRUCTION CODE TYPE: I000

URBAN
100% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	569
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3514
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1098
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1332
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	915
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	296
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	137
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	137
81306200	DRILL EXISTING JUNCTION BOX	EACH	1
* 88600100	DETECTOR LOOP, TYPE I	FOOT	950
XX004763	BITUMINOUS PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	50
X4063000	PRELIMINARY TEST STRIP (STONE MATRIX ASPHALT)	EACH	1
X7013010	TRAFFIC CONTROL AND PROTECTION FOR RAMP CLOSURE	L SUM	1
* X8860100	LOOP DETECTOR TESTING	EACH	2
X0325601	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, STONE MATRIX ASPHALT, SUPERPAVE, N50	TON	1314
X0325602	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE, STONE MATRIX ASPHALT, SUPERPAVE, N50	TON	1691

* SPECIALITY ITEMS

SHEET 2 OF 2

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
F.A.P. ROUTE 330 (IL ROUTE 17)
SECTION (11X-2)RS-1 & (11,1)RS-4
KANKAKEE COUNTY

DATE: 06/27/2006
c:/projects/cmain07/cm305/details.dgn