

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	*	KANKAKEE	24	9

* (11X-2)RS-1 & (11,1)RS-4

RAISED REFLECTIVE PAVEMENT MARKER SCHEDULE				
LOCATION	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER		
		MONODIRECTIONAL CRYSTAL	BIDIRECTIONAL AMBER	
	EACH	EACH	EACH	
LOCATION 1				
STA. 127+06 - STA. 133+00	28	28		
LOCATION 2				
STA. 225+00 - STA. 228+00	18	10	8	
STA. 228+00 - STA. 234+00	41	25	16	
STA. 234+00 - STA. 239+00	12	10	2	
I-57 RAMPS STA. 236+50 LT.				
SB RAMP TO IL 17				
RAMP TO SB I-57				
STA. 239+00 - STA. 244+00	16	15	1	
I-57 RAMPS STA. 236+50 LT.				
RAMP TO NB I-57				
NB RAMP TO IL 17				
STA. 244+00 - 249+19.06 BK	22	16	6	
STA. EQU. 249+19.06 BK=STA. 3+83.36 AH				
SUBTOTAL	137	104	33	
PROJECT TOTAL	137	137		

WORK ZONE PAVEMENT MARKING SCHEDULE			
LOCATION	SHORT-TERM PVMT MK	WORK ZONE PVMT MK REM	
		FEET	SO FT
LOCATION 1			
STA. 127+06 - STA. 133+00	97	32	
LOCATION 2			
STA. 225+00 - STA. 228+00	48	16	
STA. 228+00 - STA. 234+00	113	37	
STA. 234+00 - STA. 239+00	182	60	
I-57 RAMPS STA. 236+50 LT.			
SB RAMP TO IL 17	32	10	
RAMP TO SB I-57	31	10	
STA. 239+00 - STA. 244+00	59	19	
I-57 RAMPS STA. 236+50 LT.			
RAMP TO NB I-57	57	19	
NB RAMP TO IL 17	60	20	
STA. 244+00 - 249+19.06 BK	105	35	
STA. EQU. 249+19.06 BK=STA. 3+83.36 AH			
SUBTOTALS	783	258	
PROJECT TOTAL	783	258	

TEMPORARY PAVEMENT MARKING SCHEDULE									
LOCATION	4" LINE		6" LINE		8" LINE	12" LINE	24" LINE	LETTERS & SYMBOLS	
	WHITE	YELLOW	WHITE	YELLOW	WHITE	WHITE	WHITE	SQ FT	
	FEET	FEET	FEET	FEET	FEET	FEET	FEET		
LOCATION 1									
STA. 127+06 - STA. 133+00		102			519	91	55	150	
LOCATION 2									
STA. 225+00 - STA. 228+00		208	75	52	50		32	78	
STA. 228+00 - STA. 234+00		735	150	150				94	
STA. 234+00 - STA. 239+00		642	200		340	392	72	151	
I-57 RAMPS STA. 236+50 LT.									
SB RAMP TO IL 17	133	185							
RAMP TO SB I-57	122	185							
STA. 239+00 - STA. 244+00		314	125		78		35	23	
I-57 RAMPS STA. 242+14.71 RT.									
RAMP TO NB I-57	71	193	92		30	166	22		
NB RAMP TO IL 17	111	193	74		38	146	33		
STA. 244+00 - 249+19.06 BK		320	180		277	120	47	73	
STA. EQU. 249+19.06 BK=STA. 3+83.36 AH									
SUBTOTALS	437	3077	896	202	1332	915	296	569	
PROJECT TOTAL	3514		1098		1332	915	296	569	

DETECTOR LOOP SCHEDULE			
LOCATION	DETECTOR LOOP	LOOP DETECTOR	DRILL EXISTING
	TYPE I	TESTING	JUNCTION BOX
	FEET	EACH	EACH
FAIRMONT AVE.	450	1	1
EASTRIDGE ROAD	500	1	
PROJECT TOTAL	950	2	1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULES
 F.A.P. ROUTE 330 (IL ROUTE 17)
 SECTION (11X-2)RS-1 & (11,1)RS-4
 KANKAKEE COUNTY

DATE: 06/27/2006 c:/projects/main07/cm305/details.dgn