

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6769	(8B)BR-4	TAZEWELL	102	6
STA. 308+58		TO STA. 329+41		
FED. ROAD DIST. NO. 4		ILLINOIS	FED. AID PROJECT	

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO.	ITEM	UNITS	TOTAL QUANTITY (80% Fed. - 20% St.)	ROADWAY 1000-2A Tazewell Co.	S.N. 090-0173 <b>X071-2A</b> Tazewell Co.
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	48	48	
44000003	BITUMINOUS SURFACE REMOVAL 3/4"	SQ YD	4,538	4,538	
44000100	PAVEMENT REMOVAL	SQ YD	755	755	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	5.3	5.3	
44000400	GUTTER REMOVAL	FOOT	929	929	
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	537	537	
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	1,092	1,092	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50102400	CONCRETE REMOVAL	CU YD	2.4	2.4	
50104400	CONCRETE HEADWALL REMOVAL	EACH	5	5	
50200100	STRUCTURE EXCAVATION	CU YD	100		100
50300225	CONCRETE STRUCTURES	CU YD	39.9		39.9
50300255	CONCRETE SUPERSTRUCTURE	CU YD	143.3		143.3
50300260	BRIDGE DECK GROOVING	SQ YD	332		332
50300300	PROTECTIVE COAT	SQ YD	427		427

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO.	ITEM	UNITS	TOTAL QUANTITY (80% Fed. - 20% St.)	ROADWAY 1000-2A Tazewell Co.	S.N. 090-0173 <b>X071-2A</b> Tazewell Co.
50401105	FURNISHING AND ERECT. PREC. PRESTRESSED CONC. I-BEAMS, 54 IN.	FOOT	519		519
50500505	STUD SHEAR CONNECTORS	EACH	120		120
50800105	REINFORCEMENT BARS	POUND	2,036	2,036	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	<b>34,610</b>		<b>34,610</b>
51100300	SLOPE WALL 6 INCH	SQ YD	123		123
51201700	FURNISHING STEEL PILES HP 12 X 74	FOOT	515		515
<del>X0325278</del>	DRIVING PILES	FOOT	515		515
51203700	TEST PILE STEEL HP 12 X 74	EACH	2		2
51500100	NAME PLATES	EACH	1		1
54002020	EXPANSION BOLTS 3/4 INCH	EACH	20	20	
54003000	CONCRETE BOX CULVERTS	CU YD	16	16	
54213447	END SECTIONS 12"	EACH	2	2	
54215550	METAL END SECTIONS 15"	EACH	10	10	
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	184	184	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	92		92