

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6769	(8B)BR-4	TAZEWELL	102	7
STA. 308+58		TO STA. 329+41		
FED. ROAD DIST. NO. 4		ILLINOIS	FED. AID PROJECT	

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO.	ITEM	UNITS	TOTAL QUANTITY (80% Fed. - 20% St.)	ROADWAY 1000-2A Tazewell Co.	S.N. 090-0173 <b>X071</b> -2A Tazewell Co.
60100945	PIPE DRAINS 12"	FOOT	91	91	
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	153		153
60244240	GRATED INLET, SPECIAL	EACH	1	1	
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	65.1	65.1	
60602600	CONCRETE GUTTER, TYPE A (MODIFIED)	FOOT	911	911	
60900240	TYPE C INLET BOX, STANDARD 609006	EACH	2	2	
60900515	CONCRETE THRUST BLOCKS	EACH	2	2	
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	525	525	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	473	473	
63301210	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	25	25	
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	25	25	
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	1		1
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	3	3	

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO.	ITEM	UNITS	TOTAL QUANTITY (80% Fed. - 20% St.)	ROADWAY 1000-2A Tazewell Co.	S.N. 090-0173 <b>X071</b> -2A Tazewell Co.
66700605	PERMANENT SURVEY TIES	EACH	4	4	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8	
67100100	MOBILIZATION	L SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	60	60	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	188	188	
70300200	TEMPORARY PAVEMENT MARKING	FOOT	4,407	4,407	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,454	1,454	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	630	630	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	590	590	
* 70500100	TEMPORARY STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	75	75	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	6,453	6,453	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	26	26	
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	1		1

\* SPECIALTY ITEM