

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6769	(8B) BR-4	TAZEWELL	102	16
STA. 308+58		TO STA. 329+41		
FED. ROAD DIST. NO. 4		ILLINOIS	FED. AID PROJECT	

SCHEDULE OF QUANTITIES

CODE NO. 42001165

BRIDGE APPROACH PAVEMENT	
LOCATION	UNIT SQ YD
Sta. 318+98 to Sta. 319+27	120
Sta. 320+15 to Sta. 320+45	120
TOTAL = 240	

CODE NO. 42001430

BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	
LOCATION	UNIT SQ YD
Sta. 319+27	24
Sta. 320+45	24
TOTAL = 48	

CODE NO. 60600095

CLASS SI CONCRETE (OUTLET)	
LOCATION	UNIT CU YD
(Inlets)	
Lt. Sta. 313+08 to Sta. 313+20	1.2
Rt. Sta. 312+88 to Sta. 313+00	1.2
Rt. Sta. 325+42.9 to Sta. 325+54.9	1.2
Lt. Sta. 324+96.6 to Sta. 325+08.06	1.2
(Outlets)	
Lt. Sta. 315+50 to Sta. 315+86	8.4
Rt. Sta. 315+50 to Sta. 315+86	8.0
Rt. Sta. 322+22.2 to Sta. 322+58.2	7.4
Lt. Sta. 321+43.8 to Sta. 321+79.8	9.0
(Entrances & Mailbox Turnouts)	
Lt. Sta. 314+49.43	7.2
Rt. Sta. 315+19.20	6.6
Lt. Sta. 323+67.7 to Sta. 324+53.6	13.7
TOTAL = 65.1	

CODE NO. 60602600

CONCRETE GUTTER, TYPE A (MODIFIED)	
LOCATION	UNIT FOOT
Lt. Sta. 313+20 to Sta. 314+27	107.00
Lt. Sta. 314+70.30 to Sta. 315+50	79.70
Rt. Sta. 313+00 to Sta. 314+98.81	198.81
Rt. Sta. 315+39.81 to Sta. 315+50	10.19
Rt. Sta. 322+58.21 to Sta. 325+42.75	284.54
Lt. Sta. 321+79.84 to Sta. 323+67.69	187.85
Lt. Sta. 324+53.63 to Sta. 324+96.61	42.98
TOTAL = 911.07	

CODE NO. 63200310

GUARDRAIL REMOVAL	
LOCATION	UNIT FOOT
Rt. Sta. 311+66.68 to Sta. 312+30.10	63.42
Lt. Sta. 318+55 to Sta. 319+58	103.00
Rt. Sta. 319+78 to Sta. 320+79	101.00
Lt. Sta. 318+54 to Sta. 319+58	104.00
Rt. Sta. 319+78 to Sta. 320+79	101.00
TOTAL = 472.42	

CODE NO. 63100085

TRAFFIC BARRIER TERMINAL, TYPE 6	
LOCATION	UNIT EACH
Lt. Sta. 318+96.35 to Sta. 319+27	1
Rt. Sta. 318+96.35 to Sta. 319+27	1
Lt. Sta. 320+15 to Sta. 320+45.65	1
Rt. Sta. 320+15 to Sta. 320+45.65	1
TOTAL = 4	

CODE NO. 63301210

REMOVE & RE-ERECT STEEL PLATE BEAM GUARD RAIL, TYPE A	
LOCATION	UNIT FOOT
Lt. Sta. 319+04.8 to 319+29.8	25
TOTAL = 25	

CODE NO. 70500100

TEMPORARY STEEL PLATE BEAM GUARD RAIL, TYPE A	
LOCATION	UNIT FOOT
Lt. Sta. 318+54.8 to Sta. 319+04.8	50
Lt. Sta. 320+53.9 to Sta. 320+78.9	25
TOTAL = 75	

CODE NO. 63100167

TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	
LOCATION	UNIT EACH
Lt. Sta. 317+58.85 to Sta. 318+08.85	1
Rt. Sta. 316+71.35 to Sta. 317+21.35	1
Lt. Sta. 322+20.65 to Sta. 322+70.65	1
Rt. Sta. 321+33.15 to Sta. 321+83.15	1
TOTAL = 4	

CODE NO. 63000000

STEEL PLATE BEAM GUARD RAIL, TYPE A	
LOCATION	UNIT FOOT
Lt. Sta. 318.08.85 to Sta. 318+96.35	87.5
Rt. Sta. 317+21.35 to Sta. 318+96.35	175.0
Lt. Sta. 320+45.65 to Sta. 322+20.65	175.0
Rt. Sta. 320+45.65 to Sta. 321+33.15	87.5
TOTAL = 525	

CODE NO. 78200410

GUARDRAIL MARKERS, TYPE A	
LOCATION	UNIT EACH
Rt. Sta. 317+21.35 to Sta. 319+27	3
Lt. Sta. 318+08.85 to Sta. 319+27	2
Lt. Sta. 320+15 to Sta. 322+70.65	3
Rt. Sta. 320+15 to Sta. 321+83.15	2
TOTAL = 10	

CODE NO. 78200420

GUARDRAIL MARKERS, TYPE B	
LOCATION	UNIT EACH
Lt. Sta. 319+27 to Sta. 320+15	2
Rt. Sta. 319+27 to Sta. 320+15	2
TOTAL = 4	

CODE NO. 78201000

TERMINAL MARKER - DIRECT APPLIED	
LOCATION	UNIT EACH
Rt. Sta. 316+71.35	1
Lt. Sta. 317+58.85	1
Rt. Sta. 321+83.15	1
Lt. Sta. 322+70.65	1
TOTAL = 4	

CODE NO. X0301512

GUARDRAIL AGGREGATE EROSION CONTROL	
LOCATION	UNIT TON
Lt. Sta. 317+24.85 to Sta. 319+27	34.91
Rt. Sta. 316+37.42 to Sta. 319+27	50.39
Lt. Sta. 320+15 to Sta. 323+04.65	50.51
Rt. Sta. 320+15 to Sta. 322+17.15	34.91
TOTAL = 170.72	

CODE NO.	50800105	54003000	54002020	60244240
	REINFORCEMENT BARS	CONCRETE BOX CULVERTS	EXPANSION BOLTS 3/4 INCH	GRATED INLET, SPECIAL
	LBS	CU YD	EACH	EACH
LOCATION				
Lt. Sta. 312+12.73	815.15	6.62	10	
Rt. Sta. 312+12.73	1,221.10	9.45	10	1
TOTAL =	2,036.25	16.09	20	1

CODE NO.	54213447	60100945	60900240	60900515	X0321475
	END SECTIONS 12"	PIPE DRAINS 12"	TYPE C INLET BOX, STANDARD 609006	CONCRETE THRUST BLOCKS	PIPE ELBOW, 12"
	EACH	FOOT	EACH	EACH	EACH
LOCATION					
Lt. Sta. 319+02	1	45	1	1	2
Rt. Sta. 319+02	1	46	1	1	2
TOTAL =	2	91	2	2	4