

SCHEDULE OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6769	(8B) BR-4	TAZEWELL	102	17
STA. 308+58 TO STA. 329+41				
FED. ROAD DIST. NO. 4		ILLINOIS	FED. AID PROJECT	

CODE NO. Z0030250

IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	
LOCATION - STAGE I	UNIT EACH
Sta. 316+17	1
Sta. 322+43	1
Lt. Sta. 318+55	1
Lt. Sta. 320+79	1
TOTAL = 4	

CODE NO. Z0030350

IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	
LOCATION - STAGE II	UNIT EACH
Sta. 316+34	1
Sta. 322+23	1
TOTAL = 2	

CODE NO. 70100405

TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	
LOCATION	UNIT EACH
Sta. 314+00 to Sta. 325+00	1
TOTAL = 1.0	

CODE NO. 70100460

TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	
LOCATION	UNIT L. SUM
Jobsite	1
TOTAL = 1.0	

CODE NO. 70300100

SHORT-TERM PAVEMENT MARKING	
LOCATION	UNIT FOOT
Sta. 308+58 to Sta. 329+21	188
TOTAL = 188	

CODE NO. 70400100

TEMPORARY CONCRETE BARRIER	
LOCATION	UNIT FOOT
Sta. 316+17 to Sta. 316+94	80
Sta. 316+94 to Sta. 321+64	470
Sta. 321+64 to Sta. 322+43	80
TOTAL = 630	

CODE NO. 70400200

RELOCATE TEMPORARY CONCRETE BARRIER	
LOCATION	UNIT FOOT
Sta. 316+34 to Sta. 316+93	60
Sta. 316+93 to Sta. 321+63	470
Sta. 321+63 to Sta. 322+23	60
TOTAL = 590	

CODE NO. X7016500

TEMPORARY BRIDGE TRAFFIC SIGNALS (SPECIAL)	
LOCATION	UNIT EACH
Jobsite	1
TOTAL = 1	

CODE NO. 70103815

TRAFFIC CONTROL SURVEILLANCE	
LOCATION	UNIT CAL. DA
Jobsite	60
TOTAL = 60	

CODE NO. 70300200

TEMPORARY PAVEMENT MARKING				
LOCATION	Stop Bar	Inside Edge	Outside Edge	Center Line
Stage I	FOOT	FOOT	FOOT	FOOT
Sta. 314+35.7	78			
Sta. 314+35.7 to Sta. 324+23		986.5	984.2	
Sta. 324+23	78			
Stage II				
Sta. 314+58.9	78			
Sta. 314+58.9 to Sta. 324+27		969.2	967.3	
Sta. 324+27	78			
Resurfacing				
Sta. 308+58 to Sta. 329+21				188
SUB-TOTAL=	312	1,955.7	1,951.5	188
TOTAL= 4,407.2				

CODE NO. 70301000

WORK ZONE PAVEMENT MARKING REMOVAL				
LOCATION	Stop Bar	Inside Edge	Outside Edge	Center Line
Stage I	SQ FT	SQ FT	SQ FT	SQ FT
Sta. 314+35.7	25.7			
Sta. 314+35.7 to Sta. 324+23		325.5	324.8	
Sta. 324+23	25.7			
Stage II				
Sta. 314+58.9	25.7			
Sta. 314+58.9 to Sta. 324+27		319.8	319.2	
Sta. 324+27	25.7			
Resurfacing				
Sta. 308+58 to Sta. 329+21				62.0
SUB-TOTAL=	102.8	645.3	644.0	62.0
TOTAL= 1,454.1				

CODE NO. 78001110

PAINT PAVEMENT MARKING - LINE 4"							
LOCATION	Skip Dash	No Passing Zone (W.B.)		Double Yellow		Edge Line	
		Skip Dash	Center Line	Lt.	Rt.	Lt.	Rt.
	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
Sta. 305+58 to Sta. 315+50	170					692	692
Sta. 315+50 to Sta. 323+25		190	775			775	775
Sta. 323+25 to Sta. 329+21				596	596	596	596
SUB-TOTAL=	170	190	775	596	596	2,063	2,063
TOTAL= 6,453							