

SUMMARY OF QUANTITIES

FAP ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
622	(128BR)I	FULTON	19	3
STA.		TO STA.		
EXISTING CONDITIONS:				
CONTRACT NO. 68483				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		1000 FED 80% STATE 20%	X080-2A				
20200500	EARTH EXCAVATION (WIDENING)	CU YD	107		107				
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	57		57				
40600300	AGGREGATE (PRIME COAT)	TON	1.2		1.2				
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	266		266				
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1				
50300260	BRIDGE DECK GROOVING	SQ YD	144		144				
50300300	PROTECTIVE COAT	SQ YD	151		151				
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	1355		1355				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2050		2050				
50901005	STEEL BRIDGE RAIL, TYPE SM	FOOT	75		75				
51500100	NAME PLATES	EACH	1		1				
59000100	EPOXY CRACK SEALING	FOOT	14		14				
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4		4				
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECTAL (TANGENT)	EACH	2		2				
63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	175		175				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4		4				
67100100	MOBILIZATION	L SUM	1		1				
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1		1				
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1		1				
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1		1				
70106700	TEMPORARY RUMBLE STRIP	EACH	6		6				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	168		168				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3208		3208				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1174		1174				
70400100	TEMPORARY CONCRETE BARRIER	FOOT	452		452				
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	452		452				
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	3208		3208				
78200410	GUARDRAIL MARKERS, TYPE A	EACH	4		4				
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2		2				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		1000 FED 80% STATE 20%	X080-2A				SFTY-3N
X0301512	GUARDRAIL AGGREGATE EROSION CONTROL	TON	9		9				
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5")	SQ FT	20		20				
X3560100	BITUMINOUS CONCRETE BASE COURSE WIDENING, 6"	SQ YD	645		645				
X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	TON	70		70				
X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50	TON	30		30				
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	151		151				
* X7200200	WIDE LOAD SIGNING	L SUM	1		1				
Z0002600	BAR SPLICERS	EACH	36		36				
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2						2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2						2

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 F.A.P. RTE. 622
 SECTION (128BR)I
 FULTON COUNTY

SCALE: NONE
 DATE: 06/24/2006

DRAWN BY: KBF
 CHECKED BY: BWP