

CONTRACT NO. T0387

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
717	011B1BR	DEWITT	53	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

SUMMARY OF QUANTITIES

SHEET 1 OF 2

LOCATION OF WORK:

DEWITT COUNTY
RURAL
ROADWAY / STRUCTURE
IMPROVEMENTS
FAP 717 (IL 10)
STA. 1068+18.00
STA. 1070+90.00
80% FEDERAL
20% STATE
X071-2A

CONSTRUCTION TYPE CODE:

CODE NO	ITEM	UNIT	TOTAL QUANTITY	QUANTITY
20200100	EARTH EXCAVATION	CU YD	1455.0	1455.0
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	140.0	140.0
25000300	SEEDING, CLASS 3	ACRE	0.6	0.6
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	50.0	50.0
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	50.0	50.0
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	50.0	50.0
25100115	MULCH, METHOD 2	ACRE	0.6	0.6
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	60.0	60.0
28000400	PERIMETER EROSION BARRIER	FOOT	546.0	546.0
28100107	STONE RIPRAP, CLASS A4	SQ YD	855.0	855.0
28200200	FILTER FABRIC	SQ YD	855.0	855.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	14.0	14.0
40600300	AGGREGATE (PRIME COAT)	TON	1.0	1.0
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	219.0	219.0
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	50.0	50.0
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	136.0	136.0
44000100	PAVEMENT REMOVAL	SQ YD	461.0	461.0
44004250	PAVED SHOULDER REMOVAL	SQ YD	14.0	14.0
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	14.0	14.0
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1.0	1.0
50200100	STRUCTURE EXCAVATION	CU YD	382.0	382.0
50300100	FLOOR DRAINS	EACH	20.0	20.0
50300225	CONCRETE STRUCTURES	CU YD	70.5	70.5
50300255	CONCRETE SUPERSTRUCTURE	CU YD	190.8	190.8
50300260	BRIDGE DECK GROOVING	SQ YD	633.0	633.0
50300300	PROTECTIVE COAT	SQ YD	703.0	703.0
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1.0	1.0
50500505	STUD SHEAR CONNECTORS	EACH	3084.0	3084.0
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	53,040.0	53,040.0
51201600	FURNISHING STEEL PILES HP12X53	FOOT	715.0	715.0
51201700	FURNISHING STEEL PILES HP12X74	FOOT	552.0	552.0

PLOT DATE = 8/24/2006
 FILE NAME = c:\proje\bois\0603004 (v8)\T0387\text.dgn
 PLOT SCALE = 43.2354 / 1" IN.
 USER NAME = pierstonb

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. ROUTE 717 (IL 10)
 SECTION 011B1BR
 DEWITT COUNTY
 Sheet 1 of 2

SCALE: NOT TO SCALE
 DATE: 08/04/06

DRAWN BY: B.B.P.
 CHECKED BY: R.M.N.