

F.A.P. RY.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
717	(111B)BR	DEWITT	53	
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

SHEET 2 OF 2

LOCATION OF WORK:

DEWITT COUNTY
RURAL
ROADWAY / STRUCTURE
IMPROVEMENTS
FAP 717 (IL 10)
STA. 1068+18.00
STA. 1070+90.00
80% FEDERAL
20% STATE
X071-2A

CONSTRUCTION TYPE CODE:

CODE NO	ITEM	UNIT	TOTAL QUANTITY	QUANTITY
51203600	TEST PILE STEEL HP12x53	EACH	2.0	2.0
51203700	TEST PILE STEEL HP12X74	EACH	1.0	1.0
51500100	NAME PLATES	EACH	1.0	1.0
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	76.4	76.4
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	110.0	110.0
*63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4.0	4.0
*63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4.0	4.0
63200310	GUARDRAIL REMOVAL	FOOT	515.0	515.0
*63300900	VERTICAL ADJUSTMENT OF GUARD RAIL	FOOT	1086.0	1086.0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6.0	6.0
67100100	MOBILIZATION	L SUM	1.0	1.0
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1.0	1.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	25.0	25.0
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	828.0	828.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	9.0	9.0
*78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	828.0	828.0
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2.0	2.0
*78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	2.0	2.0
*78200405	GUARDRAIL MARKERS	EACH	23.0	23.0
*78200500	BARRIER WALL MARKERS	EACH	8.0	8.0
*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4.0	4.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	2.0	2.0
X0324865	DIAMOND GRINDING (BRIDGE SECTION)	SQ YD	722.0	722.0
X0325278	DRIVING PILES	FOOT	1,267.0	1,267.0
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	12.0	12.0
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1.0	1.0
Z0002600	BAR SPLICERS	EACH	64.0	64.0
Z0038700	PERMANENT BENCH MARKS	EACH	1.0	1.0
*SPECIALITY ITEM				

PLOT DATE = 8/23/2006
FILE NAME = c:\p\projects\4503004 (v8)\70387.txt.dgn
PLOT SCALE = 43.2355 / IN.
USER NAME = piersebr

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
F.A.P. ROUTE 717 (IL 10)
SECTION (111B)BR
DEWITT COUNTY
Sheet 2 of 2
SCALE: NOT TO SCALE
DATE: 08/04/06
DRAWN BY: B.B.P.
CHECKED BY: R.M.N.