

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
717	(111B)BR	DEWITT	53	10
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SCHEDULE OF QUANTITIES

SHEET 2 OF 2

PAINT PAVEMENT MARKING - LINE 4"

ROUTE	STATION	TO	STATION	LENGTH	4" WHITE (FOOT)	4" SKIP DASH YELLOW (FOOT)	4" NO PASSING YELLOW (FOOT)
IL 10	1068+18.00		1070+90.00	272.0	544.0	68.0	216.0
TOTAL					828.0 FOOT		

TEMPORARY PAINT PAVEMENT MARKING - LINE 4"

ROUTE	STATION	TO	STATION	LENGTH	4" WHITE (FOOT)	4" SKIP DASH YELLOW (FOOT)	4" NO PASSING YELLOW (FOOT)
IL 10	1068+18.00		1070+90.00	272.0	544.0	68.0	216.0
TOTAL					828.0 FOOT		

DIAMOND GRINDING (BRIDGE SECTION)

STATION	TO	STATION	WIDTH	AREA
			FT.	SQ. YD.
1067+94.00		1068+44.0	32.00	178.00
1070+64.00		1071+14.0	32.00	178.00
TOTAL FROM BRIDGE PLANS				722.00
TOTAL				1078.00

EARTHWORK

LOCATION			EARTH EXCAVATION	EARTH EXCAVATION EMBANKMENT ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
STATION	TO	STATION	CU YD	CU YD	CU YD	CU YD
IL 10	1068+18.00	1070+90.00	1454.0	1090.5	0.00	+1090.5
IL 10	TYPE 1 SPECIAL	1064+08.00 LT	0.00	0.00	24.0	-24.0
IL 10	TYPE 1 SPECIAL	1065+95.50 RT	0.00	0.00	24.0	-24.0
IL 10	TYPE 1 SPECIAL	1073+34.43 RT	0.00	0.00	20.0	-20.0
IL 10	TYPE 1 SPECIAL	1073+96.93 LT	0.00	0.00	56.0	-56.0
SUB-TOTALS			1454.0	1090.5	124.0	+966.5

EARTH EXCAVATION = 1455.00 CU. YD.

PLOT DATE = 8/24/2006
 FILE NAME = G:\projects\0503004 (w8)\70387\text.dgn
 USER NAME = pier_sonbr

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

F.A.P. ROUTE 717 (IL 10)
SECTION (111B)BR
DEWITT COUNTY
Sheet 2 of 2

SCALE: NOT TO SCALE DRAWN BY: B.B.P.
DATE: 07/21/06 CHECKED BY: R.M.N.