

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
685	113B-2	HANCOCK	45	9
STA. 69+70		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SIDE ROADS AND ENTRANCE IMPROVEMENT SCHEDULE														
LOCATION	TYPE OF ENTRANCE	EX MATERIAL TYPE	WIDTH	RT OFFSET	LT OFFSET	LENGTH (FROM EDGE OF PVT/ HMA SHLD TO LIMITS OF IMPROVEMENT)	PR HMA. CONC. THICKNESS	HMA. SURF. REM. - BUTT JOINT	PREP OF BASE	AGG. BASE REPAIR	AGGREGATE BASE COURSE TY - B	AGGREGATE BASE COURSE TY - B 6"	BIT. (P.C.)	INCIDENTAL HMA. SURF.
(LT / RT) STA) (+)	(FE / PE / CE / MB) (RURAL / URBAN)	(EARTH / AGG. / HMA. / P.C.C.)	FOOT	FOOT	FOOT	FOOT	INCH	SO. YD.	SO. YD.	TON	TON	SO. YD.	TON	TON
ENTRANCES														
RT 251+70	FE	AGG	24			20	-		-	-	19	-	-	-
LT 252+00	PE	AGG	24			20	-		-	-	18	-	-	-
TOTAL ENTRANCES:											37			
SIDE ROADS														
RT 246+39.38	SR	OIL/CHIP	35			59	2		266	55	1	-	0.5	51
LT 246+44.32	SR	OIL/CHIP	34.5			49	2		218	67	1	-	0.5	42
TOTAL SIDE ROADS:									484	122	39		1	93

44000100

PAVEMENT REMOVAL

STATION	TO	STATION	AREA (SQ YD)
248+13		249+04	148
248+25 RT		249+14 RT	55
TOTAL :			203

70300230

TEMPORARY PAVEMENT MARKING LINE 5"

STATION	TO	STATION	COLOR	LENGTH (FEET)
245+20		252+50	YELLOW	910
245+20 LT		252+50 LT	WHITE	630
245+20 RT		252+50 RT	WHITE	630
TOTAL LENGTH:				2170

PAVING SCHEDULE

LOCATION	HMA BASE COURSE WIDENING 10"	LEVELING BINDER (MACHINE METHOD)	HMA BASE COURSE 10"	HMA SURFACE COURSE	HMA SHOULDERS
246+62 RT TO 251+98 RT	100 SY		432 SY		61 TON
246+80 LT TO 252+26 LT			485 SY		61 TON
248+13 TO 249+04			223 SY		
245+62 TO 252+08		67 TON			
245+20 TO 252+50				150 TON	
TOTAL:	100 SY	67 TON	1140 SY	150 TON	122 TON

78001120

PAINT PAVEMENT MARKING-LINE 5"

STATION	TO	STATION	COLOR	LENGTH (FEET)
245+20		252+50	YELLOW	910
245+20 LT		252+50 LT	WHITE	630
245+20 RT		252+50 RT	WHITE	630
TOTAL LENGTH:				2170

70300100

SHORT TERM PAVEMENT MARKING

STATION	TO	STATION	COLOR	LENGTH (FEET)
245+20		252+50	YELLOW	133
TOTAL FOR 2 APPLICATIONS:				133

70301000

WORK ZONE PAVEMENT MARKING REMOVAL

STATION	TO	STATION	COLOR	AREA (SQ FT)
245+20		252+50	YELLOW	45
TOTAL AREA:				45

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE OF QUANTITIES
IL 9/96 OVER OPPOSUM CREEK
FAP 685 SECTION 113B-2
HANCOCK COUNTY**

SCALE VERT. HORIZ. DATE DATE DRAWN BY SJF CHECKED BY MJS

The Upchurch Group
HILLSIDE, IL. (708) 449-2821
MATTOON, IL. (217) 285-8177