TOTAL SHEET SHEET NO. 15 49 24 sheets 749 COLES 28 FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT-

Contract #74146

NOTES:

Inserts for $\frac{3}{4}$ '' ϕ threaded dowel rods, when specified, are to be two strut, coil type for interior beams and single coil, flared loop type for exterior beams.

Prestressing steel shall be uncoated high strength, low relaxation 7-wire strand, Grade 270.

The nominal diameter shall be $^{l}_{2}{}^{\prime\prime}$ and the nominal cross-sectional area shall be 0.153 sq. in.

Non-prestressing steel shall conform to AASHTO designation M-31 or M 322, Grade 60.

A minimum 2^{l}_{2} " ϕ lifting pin shall be used to engage the lifting loops


during handling. Reinforcement bars designated (E) shall be epoxy coated.

Cut G_6 bars when necessary to maintain $I_2^{\prime\prime}$ clearance.


The bottom plates and studs shall be galvanized according to AASHTO M111 and ASTM A385.

Threaded rods shall be ASTM F 1554 Grade 55.

The cut strands at each beam end shall be given two coats of zinc dust spray or paint meeting the requirements of ASTM A 780. The zinc dust spray or paint shall be applied before corrosion appears and allowed to dry according to the manufacturer's specifications prior to another coat of zinc. A concrete sealer meeting the requirements of Section 587 of the Standard Specifications shall be applied to all portions of the I-beam or Bulb-T beam, except the top surface of the top flange and the bottom surface of the bottom flange, starting at each beam end and extending out a distance of 42 inches. The sealer shall be applied after visible crack growth has subsided. This work shall be performed by the producer and included with the cost of the beam.



LIFTING LOOP DETAIL



To outside face 5"

m12 (E)-


ELEVATION OF BEAMS AT PIER

of bar, (Typ.)


└─ Bottom of beam

← End of beams


No. 9 wire ties
(See sheet 9 of 24)




BOTTOM PLATE See bearing details for pintle hole locations when required.



BAR G4



BAR G5



BAR G6

BILL OF MATERIAL

Item	Unit	Quantity
Furnishing and Erecting Precast Prestressed Concrete I-Beams, 42''	Ft.	1708

ILLINOIS DEPARTMENT OF TRANSPORTATION

42" PPC I-BEAM SPANS 1 THRU 4

IL ROUTE 133 OVER THE LITTLE EMBARRAS RIVER F.A.P. ROUTE 749 SECTION (122BR)BR COLES COUNTY STATION 933+50.00 STRUCTURE NO. 015-0074

DATE: MARCH 2006

DRAWN BY: MLO CHECKED BY: PBB

PI-4-42D

7-15-05

TOP PLATE