

URBAN
90% FED.
5% STATE
5% CITY

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
824	*	COLES	7	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

* D7 SIGNAL MODERNIZATION 2007-1

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT		Y031-1F
* 42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SO FT	136	136
* 44000600	SIDEWALK REMOVAL	SO FT	136	136
67100100	MOBILIZATION	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
* 72000200	SIGN PANEL - TYPE 2	SO FT	52	52
81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	89	89
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	89	89
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	924	924
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1269	1269
87502660	TRAFFIC SIGNAL POST, ALUMINUM 12 FT.	EACH	1	1
87502720	TRAFFIC SIGNAL POST, ALUMINUM 18 FT.	EACH	4	4
87700210	STEEL MAST ARM ASSEMBLY AND POLE, 34 FT.	EACH	1	1
87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	1	1
87700250	STEEL MAST ARM ASSEMBLY AND POLE, 42 FT.	EACH	2	2
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	6	6
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	48	48
87900200	DRILL EXISTING HANDHOLE	EACH	5	5
88200410	TRAFFIC SIGNAL BACKPLATE, LOUVERED, FORMED PLASTIC	EACH	18	18
88800100	PEDESTRIAN PUSH-BUTTON	EACH	8	8
89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	1	1
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	1938	1938
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1	1
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	5	5
X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	521	521
X8801310	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	6	6
X8801400	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	4	4
X8801437	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3-SECTION, 1-5-SECTION, BRACKET MOUNTED	EACH	4	4
X8810395	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED	EACH	6	6
X8810495	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, BRACKET MOUNTED	EACH	1	1

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. DATE
HORIZ. DATE

DRAWN BY
CHECKED BY