| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 336 | 99-00232-00-WR | KANE | 97 | 13 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

CONTRACT NO.: 83738

## DRIVEWAY SCHEDULE

| LOCATION | SIDE | DRIVEWAY PAVEMENT REMOVAL QTY. (SQ YD) 44000200 | BITUMINOUS BASE COURSE SUPERPAVE 6" (SQ YD) X3550300 | BITUMINOUS BASE COURSE SUPERPAVE 8" (SQ YD) X3550500 | BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE, MIX "C", N50 (TONS) X4066414 | PIPE CULVERTS, CLASS A, TYPE 1 12" (FEET) 542A0217 | PIPE CULVERTS, CLASS A, TYPE 1 24" (FEET) 542A0229 | END SECTIONS (EACH) 12" 54213447 | END SECTIONS (EACH) 24" 54213459 | TRENCH BACKFILL (CU YD) 20800150 | AGGREGATE SURFACE COURSE TYPE B (TONS) 40200800 |
|---|---|---|---|---|---|---|---|---|---|---|---|
| JERICHO RD. | | | | | | | | | | | |
| STAGE II | | | | | | | | | | | |
| 306+65.41 | | 73 | 53.9 | | 7.3 | | | | | | 24.71 |
| SUBTOTAL | | 73 | 53.9 | | 7.3 | | | | | | 24.71 |
| STAGE III-A | | | | | | | | | | | |
| 311+29.57 | | 270 | 36.0 | | 4.8 | | | | | | 16.59 |
| 311+77.66 | | 48 | 42.1 | | 5.8 | | | | | | 16.25 |
| 312+96.65 | | 33 | 39.9 | | 5.4 | | | | | | 11.17 |
| 313+44.23 | | 37 | 49.6 | | 6.8 | | | | | | 12.52 |
| 313+97.17 | | 37 | 49.4 | | 6.8 | | | | | | 12.52 |
| 314+43.43 | | 34 | 52.6 | | 7.3 | | | | | | 11.51 |
| 315+29.51 | | 26 | 51.5 | | 7.0 | | | | | | 8.8 |
| 315+76.83 | | 31 | 51.8 | | 7.2 | | | | | | 10.49 |
| SUBTOTAL | | 565 | 372.9 | | 51.1 | | | | | | 99.85 |
| STAGE III-B | | | | | | | | | | | |
| 311+11.37 | | 93 | | 137 | 6.7 | | 43' | | 2 | 8.8 | 31.48 |
| 313+20.78 | | 34 | 40.4 | | 5.4 | | | | | | 11.51 |
| 314+20.44 | | 39 | 48.7 | | 6.7 | | | | | | 13.2 |
| 315+18.17 | | 42 | 51.7 | | 7.0 | 36' | | 2 | | 8.5 | 14.22 |
| 316+59.24 | | 42 | 53.7 | | 7.4 | 24' | | 2 | | 5.7 | 14.22 |
| 317+19.60 | | 55 | 61.6 | | 8.4 | | | | | | 18.62 |
| SUBTOTAL | | 305 | 256.1 | 137 | 41.6 | | | 4 | 2 | | 103.25 |
| TOTAL STAGE II | | 73 | 53.9 | | 7.3 | | | | | | 24.71 |
| TOTAL STAGE III-A | | 295 | 372.9 | | 51.4 | | | | | | 99.85 |
| TOTAL STAGE III-B | | 305 | 256.1 | | 41.6 | 60' | 43' | 4 | 2 | 23 | 103.25 |
| TOTAL STAGE IV | | 0 | 0 | | 0 | | | | | | |
| PROJECT TOTAL | | 943 | 683 | 137 | 100 | 60' | 43' | 4 | 2 | 23 | 228 |

## PAVEMENT REMOVAL ITEMS

| LOCATION | PAVEMENT REMOVAL 44000100 SQ YD | BITUMINOUS SURFACE REMOVAL, 1 1/2" 44000006 SQ YD | BITUMINOUS SURFACE REMOVAL BUTT JOINT 40600980 FOOT | COMBINATION CURB & GUTTER REMOVAL 44000500 FOOT |
|---|---|---|---|---|
| STAGE I | | | | |
| JERICHO RD. | | | | |
| 305+12.38 - 308+12.78 | | 1,007 | | |
| STAGE II | | | | |
| ORCHARD RD. | | | | |
| 172+66.73 - 174+24.34 | 95 | | | |
| 178+25.87 - 178+92.30 | 187 | | | |
| 179+74.94 - 183+22.55 | 454 | | | |
| 187+19.56 - 190+47.47 | 420 | | | |
| JERICHO RD. | | | | |
| 308+12.68 - 309+47.11 | 393 | | | |
| 311+29.61 - 317+35.90 | | 1,838 | | |
| STAGE III | | | | |
| ORCHARD RD. | | | | |
| 172+62.62 - 172+43.75 | 367 | | | |
| 172+66.62 - 179+23.05 | 2463 | | | |
| 173+66.17 - 179+23.50 | 575 | | | |
| CORNELL RD. | | | | |
| 40+36.64 - 41+10.33 | 173 | | | |
| JERICHO RD. | | | | |
| 310+17.91 - 311+29.59 | 385 | | | |
| STAGE IIIA | | | | |
| ORCHARD RD. | | | | |
| 166+14.47 - 168+50 | | 740 | | |
| 168+50 - 172+62.62 | 823 | | | |
| 172+42.42 - 172+68.20 | 105 | | | |
| 179+23.05 - 179+59.53 | 24 | | | |
| 179+23.05 - 190+47.48 | 2444 | | | |
| CORNELL RD. | | | | |
| 40+36.64 - 41+10.33 | 142 | | | |
| JERICHO RD. | | | | |
| 310+26.06 - 310+72.44 | 78 | | | |
| STAGE IIIB | | | | |
| ORCHARD RD. | | | | |
| 168+50 - 172+62.62 | 392 | | | |
| 178+92.30 - 179+74.94 | 135 | | | |
| 179+07.67 - 179+74.94 | 89 | | | |
| STAGE IV | | | | |
| ORCHARD RD. | | | | |
| 172+86.24 - 178+38.79 | 368 | | | |
| 179+59.53 - 190+47.48 | 1690 | | | |
| CORNELL RD. | 26 | | | |
| ORCHARD RD. | | | | |
| 166+14.47 - 166+18.97 | | | 19.0 | |
| CORNELL RD. | | | | |
| 40+45.39 - 43+95.00 | | | | 372 |
| 40+44.46 - 41+10.33 | | | | 83 |
| JERICHO RD. | | | | |
| 305+07.88 - 305+12.38 | | | 17.8 | |
| 317+35.90 - 317+40.40 | | | 14.2 | |
| PROJECT TOTAL | 11828 | 3585 | 51 | 455 |

## TREE REMOVAL

| LOCATION | OFFSET | 6-15 UNITS 20100110 | OVER 15 UNITS 20100210 | ACRE 20100500 |
|---|---|---|---|---|
| JERICHO RD | | | | |
| 305+25.24 | 31.00 RT | 12 | | |
| 305+54.46 | 35.14 LT | 14 | | |
| 305+87.24 | 33.07 LT | 12 | | |
| 306+18.90 | 33.35 LT | 12 | | |
| 306+54.44 | 31.58 LT | 10 | | |
| 307+15.43 | 33.43 RT | | 32 | |
| 307+78.43 | 41.95 LT | 10 | | |
| 307+84.57 | 41.84 LT | 12 | | |
| 307+89.10 | 41.75 LT | 14 | | |
| 306+05 - 308+30 | RT | | | 0.03 |
| 313+12.79 | 40.00 LT | | 38 | |
| 313+30.30 | 39.00 LT | | 38 | |
| 315+62.94 | 38.00 LT | 14 | | |
| ORCHARD RD | | | | |
| 172+25.00 - 175+56 | LT | | | 0.26 |
| 175+50 - 177+84 | LT | | | 0.21 |
| TOTAL | | 110 | 108 | 0.5 |

## SIGN REMOVAL

| LOCATION | OFFSET | SIDE | REMOVE SIGN PANEL ASSEMBLY--TYPE A 72400100 (EACH) |
|---|---|---|---|
| ORCHARD RD. | | | |
| 172+08.87 | 57.42 | RT | 1 |
| 172+66.37 | 57.40 | RT | 1 |
| 173+98.32 | 50.77 | RT | 1 |
| 174+87.80 | 51.98 | RT | 1 |
| 177+49.68 | 53.00 | RT | 1 |
| 177+55.31 | 14.36 | LT | 1 |
| 178+62.33 | 51.22 | RT | 1 |
| 178+68.23 | 62.40 | RT | 1 |
| 179+57.64 | 20.76 | LT | 1 |
| 180+74.23 | 33.86 | RT | 1 |
| 183+12.67 | 18.77 | LT | 1 |
| 184+70.63 | 26.93 | LT | 1 |
| 187+89.09 | 33.59 | RT | 1 |
| JERICHO RD. | | | |
| 308+02.42 | 28.89 | RT | 1 |
| 308+95.32 | 23.31 | RT | 1 |
| 310+73.26 | 25.42 | LT | 1 |
| 312+06.75 | 25.38 | RT | 1 |
| 312+26.62 | 41.19 | LT | 1 |
| 312+41.75 | 35.28 | LT | 1 |
| 312+64.51 | 23.34 | RT | 1 |
| 314+89.41 | 22.05 | LT | 1 |
| TOTAL | | | 21 |

rjngroup
Excellence through Ownership
200 West Front Street
Wheaton, Il 60187

| REVISIONS NAME | DATE |
|---|---|
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
KANE COUNTY DIVISION OF TRANSPORTATION
ORCHARD ROAD RECONSTRUCTION

**SCHEDULE OF QUANTITIES**

SCALE: VERT.
HORIZ.
DATE: 11/04/05

DRAWN BY: RJN
CHECKED BY: SPF

9/8/2006 10:29:56 AM K:\n7700\Cad\Design\n7700_Sch_Quantities_2.sgn