

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	PINE STREET		ELDORADO STREET	
				ROADWAY QUANTITY 1000-2A	BRIDGE QUANTITY X171-2A	ROADWAY QUANTITY 1000-2A	BRIDGE QUANTITY X171-2A
20101000	TEMPORARY FENCE	FOOT	480	240	0	240	0
20101100	TREE TRUNK PROTECTION	EACH	8	4	0	4	0
20200100	EARTH EXCAVATION	CU YD	293	89	0	204	0
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	50	25	0	25	0
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	50	25	0	25	0
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	500	300	0	200	0
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	7	4	0	3	0
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	7	4	0	3	0
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	7	4	0	3	0
* 25200110	SODDING, SALT TOLERANT	SQ YD	500	300	0	200	0
* 28000510	INLET FILTERS	EACH	7	2	0	5	0
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	570	465	0	105	0
35102200	AGGREGATE BASE COURSE, TYPE B 10"	SQ YD	130	0	0	130	0
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	45	25	0	20	0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	290	205	0	85	0
40600300	AGGREGATE (PRIME COAT)	TON	2	1	0	1	0
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	77	0	0	0	77
42001300	PROTECTIVE COAT	SQ YD	1882	300	782	220	580
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	295	0	212	0	83
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	61	25	0	36	0
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	30	0	0	30	0
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQ FT	1600	1100	0	500	0
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	200	120	0	80	0
42400800	DETECTABLE WARNINGS	SQ FT	40	28	0	12	0
44000100	PAVEMENT REMOVAL	SQ YD	875	590	0	285	0
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	65	25	0	40	0
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	565	345	0	220	0
44000600	SIDEWALK REMOVAL	SQ FT	1600	1100	0	500	0
44000700	APPROACH SLAB REMOVAL	SQ YD	146	0	84	0	62
50101700	REMOVAL OF EXISTING SUPERSTRUCTURES NO. 1	EACH	1	0	1	0	0
50101800	REMOVAL OF EXISTING SUPERSTRUCTURES NO. 2	EACH	1	0	0	0	1
50102400	CONCRETE REMOVAL	CU YD	27	0	16	0	12
50300225	CONCRETE STRUCTURES	CU YD	29.1	0	10.8	0	18.3
50300255	CONCRETE SUPERSTRUCTURE	CU YD	325.5	0	181.3	0	144.2
50300260	BRIDGE DECK GROOVING	SQ YD	809	0	488	0	321
50300310	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	48	0	20	0	28
50300320	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	20	0	20	0	0
50500505	STUD SHEAR CONNECTORS	EACH	4512	0	2580	0	1932
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	80871	0	44638	0	36233
51100100	SLOPE WALL 4 INCH	SQ YD	275	0	0	0	275
51500100	NAME PLATES	EACH	2	0	1	0	1
58700200	BRIDGE SEAT SEALER	SQ FT	268	0	157	0	111
59000100	EPOXY CRACK SEALING	FOOT	149	0	106	0	43
60250200	CATCH BASINS TO BE ADJUSTED	EACH	1	0	0	1	0
60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1	0	0	1	0
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1	0	0	0
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	3	3	0	0	0

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	PINE STREET		ELDORADO STREET	
				ROADWAY QUANTITY 1000-2A	BRIDGE QUANTITY X171-2A	ROADWAY QUANTITY 1000-2A	BRIDGE QUANTITY X171-2A
60260100	INLETS TO BE ADJUSTED	EACH	1	0	0	1	0
60260300	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1	1	0	0	0
60261300	INLETS TO BE ADJUSTED WITH NEW TYPE 11 FRAME AND GRATE	EACH	1	1	0	0	0
60265900	VALVE VAULTS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	3	3	0	0	0
60266600	VALVE BOXES TO BE ADJUSTED	EACH	1	1	0	0	0
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	350	230	0	120	0
66400105	CHAIN LINK FENCE, 4'	FOOT	90	30	0	60	0
66400205	CHAIN LINK FENCE, 5'	FOOT	30	30	0	0	0
66410300	CHAIN LINK FENCE REMOVAL	FOOT	120	60	0	60	0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	6	0	6	0
67100100	MOBILIZATION	L SUM	1	0.5	0	0.5	0
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	0.5	0	0.5	0
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	660	600	0	60	0
* 78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	70	40	0	30	0
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2	1	0	1	0
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5")	SQ FT	287	0	212	0	75
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	7	2	0	5	0
X0323557	BRIDGE JOINT SYSTEM (EXPANSION), 1"	FOOT	99	0	40	0	59
X0323558	BRIDGE JOINT SYSTEM (EXPANSION), 1-5/8"	FOOT	40	0	40	0	0
X0323670	PREFORMED DETECTOR LOOP	FOOT	130	65	0	65	0
X3550300	BITUMINOUS BASE COURSE SUPERPAVE 6"	SQ YD	75	25	0	50	0
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	15	3	0	12	0
X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50	TON	10	0	0	10	0
X4073081	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 10"	SQ YD	360	360	0	0	0
XX002866	CONCRETE BARRIER WALL (SPECIAL)	CU YD	56.7	0	29.7	0	27.0
XX003338	TEST HOLE	EACH	8	4	0	4	0
XX005964	REMOVE AND RESET BRICK SIDEWALK	SQ FT	10	10	0	0	0
Z0002600	BAR SPLICERS	EACH	104	0	60	0	44
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.5	0	0.5	0
Z0047300	PROTECTIVE SHIELD	SQ YD	1159	0	690	0	469
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	0.5	0	0.5	0
Z0076600	TRAINEES	hour	500	250	0	250	0
X006668	HANDHOLE TO BE ADJUSTED WITH NEW FRAME AND COVER	EACH	1	0	0	1	0
X5051401	FURNISHING AND ERECTING STRUCTURAL STEEL NO. 1	BRIDGE L SUM	1	0	1	0	0
X5051402	FURNISHING AND ERECTING STRUCTURAL STEEL NO. 2	BRIDGE L SUM	1	0	0	0	1

* SPECIALTY ITEMS
 Δ 1080

REVISIONS	
NAME	DATE

GC Giorba Group, Inc.
 CONSULTING ENGINEERS
 9507 North Cumberland Avenue, Suite 402, Chicago, Illinois 60656
 Tel. 773.775.4009 Fax 773.775.4014 Email: chicago@giorba.com

VILLAGE OF WINNETKA
 ELDORADO STREET OVER UNION PACIFIC R.R.
 PINE STREET OVER UNION PACIFIC R.R.
SUMMARY OF QUANTITIES