

PINE STREET

STA.	TO	STA.	EARTH EXCAVATION (CU YD)	*UNDERCUT AND PGE REPLACEMENT (CU YD)	EXCAVATION TO BE USED IN EMBANKMENT (ADJ. FOR SHRINKAGE - 15%) (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
100+00	--	100+20	60	0	51	0	51
101+95	--	102+00	0	0	0	1	-1
102+00	--	102+50	8	0	7	6	1
102+50	--	103+00	21	0	18	0	18
TOTALS			89	25	76	7	69

\* UNDERCUT DETERMINED IN FIELD BY ENGINEER

ELDORADO STREET

STA.	TO	STA.	EARTH EXCAVATION (CU YD)	*UNDERCUT AND PGE REPLACEMENT (CU YD)	EXCAVATION TO BE USED IN EMBANKMENT (ADJ. FOR SHRINKAGE - 15%) (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
200+00	--	200+31	138	0	117	0	117
201+75	--	202+00	21	0	18	0	18
202+00	--	202+40	45	0	38	1	37
TOTALS			204	25	173	1	172

\* UNDERCUT DETERMINED IN FIELD BY ENGINEER

PAY ITEMS	PINE STREET	ELDORADO STREET	TOTALS
EARTH EXCAVATION (CU YD)	89	204	293
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	25	25	50
POROUS GRANULAR EMBANKMENT, SUBGRADE (CU YD)	25	25	50

REVISIONS	
NAME	DATE

VILLAGE OF WINNETKA  
ELDORADO STREET OVER UNION PACIFIC R.R.  
PINE STREET OVER UNION PACIFIC R.R.  
SCHEDULE OF QUANTITIES

SCALE: 1"=20'  
DATE: MARCH 2006

DRAWN BY: EAB  
CHECKED BY: MRJ