



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

November 9, 2006

SUBJECT: FAP Route 310 (US 67)
Project BRF-0310 (095)
Section (41-A) BR
McDonough County
Contract No. 88939
Item No. 49, November 17, 2006 Letting
Addendum B

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised entire Schedule of Prices.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Michael L. Hine
Engineer of Design
and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E.".

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: J. E. Crowe, Region 3, District 4; Roger Driskell; Estimates; Design & Environment File

TBW:RS:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 88939

State Job # - C-94-103-99
 PPS NBR - 4-08275-0100
 County Name - MCDONOUGH- -
 Code - 109 - -
 District - 4 - -
 Section Number - (41A)BR

Project Number
 BRF-0310/095/

Route
 FAP 310

* COMPLETE NEW SCHEDULE

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
A2002014	T-AESCLUSUS GLA 1-3/4	EACH	3.000				
A2002914	T-CELTIS OCCID 1-3/4	EACH	7.000				
A2005014	T-GYMNOCLA DIO 1-3/4	EACH	5.000				
A2006514	T-QUERCUS BICOL 1-3/4	EACH	7.000				
A2006708	T-QUERCUS MACR 1	EACH	5.000				
B2001164	T-CERCIS CAN CL 5'	EACH	5.000				
B2006214	T-SYRING RET TF 1-3/4	EACH	15.000				
X0301512	GDRL AGG EROS CONT	TON	197.000				
X0321475	PIPE ELBOW, 12"	EACH	8.000				
X4066424	BC SC SUPER "D" N50	TON	239.000				
X4066614	BCBC SUP IL-19.0 N50	TON	517.600				
X5020501	UNWAT STR EX PROT L1	EACH	1.000				
X5020502	UNWAT STR EX PROT L2	EACH	1.000				
Z0002600	BAR SPLICERS	EACH	196.000				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 88939

State Job # - C-94-103-99
 PPS NBR - 4-08275-0100
 County Name - MCDONOUGH- -
 Code - 109 - -
 District - 4 - -
 Section Number - (41A)BR

Project Number
 BRF-0310/095/

Route
 FAP 310

* COMPLETE NEW SCHEDULE

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0020800	EROSION CONTROL CURB	FOOT	648.000				
Z0030250	IMP ATTN TEMP NRD TL3	EACH	4.000				
Z0030350	IMP ATTN REL NRD TL3	EACH	2.000				
20100110	TREE REMOV 6-15	UNIT	650.000				
20100210	TREE REMOV OVER 15	UNIT	119.000				
20200100	EARTH EXCAVATION	CU YD	5,300.000				
20300100	CHANNEL EXCAV	CU YD	100.000				
20700400	POROUS GRAN EMB SPEC	CU YD	45.000				
21101615	TOPSOIL F & P 4	SQ YD	4,840.000				
25000300	SEEDING CL 3	ACRE	1.000				
25000400	NITROGEN FERT NUTR	POUND	90.000				
25000500	PHOSPHORUS FERT NUTR	POUND	90.000				
25000600	POTASSIUM FERT NUTR	POUND	90.000				
25000700	AGR GROUND LIMESTONE	TON	2.000				
25002300	TEMP SEEDING	ACRE	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 88939

State Job # - C-94-103-99
 PPS NBR - 4-08275-0100
 County Name - MCDONOUGH - -
 Code - 109 - -
 District - 4 - -
 Section Number - (41A)BR

Project Number
 BRF-0310/095/

Route
 FAP 310

* COMPLETE NEW SCHEDULE

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
25100115	MULCH METHOD 2	ACRE	1.000				
25100630	EROSION CONTR BLANKET	SQ YD	1,000.000				
28000300	TEMP DITCH CHECKS	EACH	5.000				
28000400	PERIMETER EROS BAR	FOOT	825.000				
28000500	INLET & PIPE PROTECT	EACH	1.000				
28100105	STONE RIPRAP CL A3	SQ YD	1,223.000				
28100107	STONE RIPRAP CL A4	SQ YD	1,015.000				
28200200	FILTER FABRIC	SQ YD	2,238.000				
40200800	AGG SURF CSE B	TON	20.500				
40600100	BIT MATLS PR CT	GALLON	500.000				
40600300	AGG PR CT	TON	1.200				
40600980	BIT SURF REM BUTT JT	SQ YD	274.000				
40600990	TEMPORARY RAMP	SQ YD	862.200				
42001165	BR APPR PAVT	SQ YD	236.000				
42001300	PROTECTIVE COAT	SQ YD	354.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 88939

State Job # - C-94-103-99
 PPS NBR - 4-08275-0100
 County Name - MCDONOUGH- -
 Code - 109 - -
 District - 4 - -
 Section Number - (41A)BR

Project Number
 BRF-0310/095/

Route
 FAP 310

* COMPLETE NEW SCHEDULE

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
42001430	BR APPR PVT CON (FLX)	SQ YD	50.700				
44000006	BIT SURF REM 1 1/2	SQ YD	440.000				
44000100	PAVEMENT REM	SQ YD	292.000				
44000920	BIT CONC SHLD REM	SQ YD	96.200				
48202600	BIT SHLD SUPER 8	SQ YD	14.700				
48202800	BIT SHLD SUPER 10	SQ YD	444.900				
48202900	BIT SHLDS SUPR VAR DP	SQ YD	222.200				
50100100	REM EXIST STRUCT	EACH	1.000				
50105220	PIPE CULVERT REMOV	FOOT	34.000				
50200100	STRUCTURE EXCAVATION	CU YD	124.000				
50300100	FLOOR DRAINS	EACH	6.000				
50300225	CONC STRUCT	CU YD	103.900				
50300255	CONC SUP-STR	CU YD	156.200				
50300260	BR DECK GROOVING	SQ YD	270.000				
50300300	PROTECTIVE COAT	SQ YD	354.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 88939

State Job # - C-94-103-99
 PPS NBR - 4-08275-0100
 County Name - MCDONOUGH- -
 Code - 109 - -
 District - 4 - -
 Section Number - (41A)BR

Project Number
 BRF-0310/095/

Route
 FAP 310

* COMPLETE NEW SCHEDULE

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
50800205	REINF BARS, EPOXY CTD	POUND	37,040.000				
51201100	FUR MET PILE SHELL 14	FOOT	1,821.000				
51202600	DRIV & FILLING SHELLS	FOOT	1,821.000				
51203200	TEST PILE MET SHELLS	EACH	2.000				
51205200	TEMP SHT PILING	SQ FT	1,334.000				
51500100	NAME PLATES	EACH	1.000				
542D0223	P CUL CL D 1 18	FOOT	34.000				
54215547	MET END SEC 12	EACH	4.000				
54215553	MET END SEC 18	EACH	2.000				
59100100	GEOCOMPOSITE WALL DR	SQ YD	31.000				
60100945	PIPE DRAINS 12	FOOT	116.000				
60109580	P UNDR FOR STRUCT 4	FOOT	97.000				
60600095	CLASS SI CONC OUTLET	CU YD	3.500				
60900240	TY C INLET BOX 609006	EACH	4.000				
60900515	CONC THRUST BLOCKS	EACH	4.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

88939

State Job # - C-94-103-99
 PPS NBR - 4-08275-0100
 County Name - MCDONOUGH- -
 Code - 109 - -
 District - 4 - -
 Section Number - (41A)BR

Project Number
 BRF-0310/095/

Route
 FAP 310

* COMPLETE NEW SCHEDULE

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
63000000	SPBGR TY A	FOOT	525.000				
63100085	TRAF BAR TERM T6	EACH	4.000				
63100169	TR BAR TRM T1 SPL FLR	EACH	4.000				
66502300	WOV W FENCE REMOV	FOOT	1,040.500				
66600105	FUR ERECT ROW MARKERS	EACH	16.000				
66700205	PERM SURV MKRS T1	EACH	1.000				
67000400	ENGR FIELD OFFICE A	CAL MO	3.000				
67100100	MOBILIZATION	L SUM	1.000				
70100405	TRAF CONT-PROT 701321	EACH	1.000				
70100450	TRAF CONT-PROT 701201	L SUM	1.000				
70100500	TRAF CONT-PROT 701326	L SUM	1.000				
70106500	TEMP BR TRAF SIGNALS	EACH	1.000				
70106700	TEMP RUMBLE STRIP	EACH	6.000				
70300520	PAVT MARK TAPE T3 4	FOOT	8,428.000				
70300625	TEMP PT PVT M LINE 4	FOOT	2,580.000				

