

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	141-ABR	MCDONOUGH	58	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
D-94-025-99				

# SCHEDULE OF QUANTITIES

**78200520 BARRIER WALL MARKERS, TYPE B**

LOCATION	QUANTITY (EACH)
STATION	
RIGHT SIDE	
STA. 667+47.85	1
LEFT SIDE	
STA. 667+35.15	1
TOTAL =	2

**78201000 TERMINAL MARKER - DIRECT APPLIED**

LOCATION	QUANTITY (EACH)
STATION	
STA. 665+35.35, LT	1
STA. 664+47.85, RT	1
STA. 570+35.15, LT	1
STA. 669+47.85, RT	1
TOTAL =	4

**78300100 PAVEMENT MARKING REMOVAL**

LOCATION	QUANTITY (SQ. FT.)
STAGE 1	
STA. 565+23.5 TO 569+59.5 (CENTER AND LEFT)	436.0
STAGE 2	
STA. 565+23.5 TO 569+59.5 (RIGHT)	145.3
TOTAL =	581.3

**Z0020800 EROSION CONTROL CURB**

LOCATION	QUANTITY (FOOT)
STATION	
STA. 565+85.35 TO STA. 567+03.50, LT	118.15
STA. 564+97.85 TO STA. 567+03.50, RT	205.65
STA. 567+79.50 TO STA. 569+95.15, LT	205.65
STA. 567+79.50 TO STA. 568+97.85, RT	118.15
TOTAL =	647.6

**Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3**

LOCATION	QUANTITY (EACH)
STATION	
STA. 565+23.5, RT.	1
STA. 568+92.0, LT.	1
STA. 569+59.5, RT.	1
STA. 567+88.0, LT.	1
TOTAL =	4

**Z0030350 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3**

LOCATION	QUANTITY (EACH)
STATION	
STA. 565+23.5	1
STA. 570+09.5	1
TOTAL =	2

**X030151Z GUARDRAIL AGGREGATE EROSION CONTROL**

LOCATION	QUANTITY (TON)
STATION	
STA. 564+25.35 TO STA. 567+03.50, RT	55.4
STA. 565+12.85 TO STA. 567+03.50, LT	42.5
STA. 567+79.50 TO STA. 569+70.15, RT	42.5
STA. 567+79.50 TO STA. 570+60.00, LT	56.4
TOTAL =	196.8

**X0321475 PIPE ELBOW, 12"**

LOCATION	QUANTITY (EACH)
STATION	
STA. 566+90.0, RT.	2
STA. 566+90.0, LT.	2
STA. 567+93.0, RT.	2
STA. 567+93.0, LT.	2
TOTAL =	8

**X4066424 BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50**

LOCATION	QUANTITY (TON)
STATION	
STA. 564+15.0 TO STA. 566+73.5	91.9
STA. 568+09.5 TO STA. 570+60.0	89.1
TEMPORARY SHOULDER PAVEMENT	
STA. 565+23.5 TO STA. 567+67.5, RT.	6.7
STA. 568+65.5 TO STA. 569+59.5, RT.	6.7
TEMPORARY RAMP	
STA. 565+73.5 TO STA. 566+73.5	22.2
STA. 568+09.5 TO STA. 569+09.5	22.2
TOTAL =	239.0

**X4066614 BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50**

LOCATION	QUANTITY (TON)
STATION	
STA. 565+30.0 TO STA. 566+73.5	191.4
STA. 568+09.5 TO STA. 569+60.0	187.4
TEMPORARY SHOULDER PAVEMENT	
STA. 565+23.5 TO STA. 567+67.5, RT.	87.3
STA. 568+65.5 TO STA. 569+59.5, RT.	51.5
TOTAL =	517.6

LOT DATE = 8/16/2005  
 D.E. NAME = J:\projects\88939\88939.dgn  
 LOT SCALE = 1/8"=1'-0"  
 SER NAME = hudson

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SN 055-0048 SUMMARY OF QUANTITIES
SCALE: VERT. / HORIZ.	DATE	DRAWN BY / CHECKED BY