

| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---------------------------|-----------|---------------|------------------|-----------|
| 332 | RX-1-BR-1 | VERMILION | 140 | 7 |
| STA. _____ | | TO STA. _____ | | |
| FED. ROAD DIST. NO. _____ | | ILLINOIS | FED. AID PROJECT | |

SUMMARY OF QUANTITIES

LOCATION OF WORK:

FAS 332
Vermilion
County
Sta. 186+00.00
To
Sta. 202+00.00
Rural
80% FED
20% STATE
1000

FAS 332
Vermilion
County
SN 092-0205
Rural
80% FED
20% STATE
X081-2A

CONSTRUCTION TYPE CODE:

| CODE NO | ITEM | UNIT | TOTAL QUANTITY | FAS 332 | FAS 332 |
|------------|---|--------|----------------|---------|---------|
| 66406100 | CHAIN LINK GATES, 4' X 18' DOUBLE | EACH | 1.0 | 1.0 | 0.0 |
| 66410300 | CHAIN LINK FENCE REMOVAL | FOOT | 51.0 | 51.0 | 0.0 |
| 66502300 | WOVEN WIRE FENCE REMOVAL | FOOT | 102.0 | 102.0 | 0.0 |
| 66600105 | FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS | EACH | 3.0 | 3.0 | 0.0 |
| 66700095 | PERMANENT SURVEY MARKERS | EACH | 1.0 | 1.0 | 0.0 |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 10.0 | 6.0 | 4.0 |
| 67100100 | MOBILIZATION | L SUM | 1.0 | 1.0 | 0.0 |
| 70100450 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701201 | L SUM | 1.0 | 1.0 | 0.0 |
| 70106700 | TEMPORARY RUMBLE STRIP | EACH | 6.0 | 6.0 | 0.0 |
| 70300100 | SHORT-TERM PAVEMENT MARKING | FOOT | 224.0 | 224.0 | 0.0 |
| 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | 3,602.0 | 3,602.0 | 0.0 |
| 70300280 | TEMPORARY PAVEMENT MARKING - LINE 24" | FOOT | 81.0 | 81.0 | 0.0 |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SO FT | 161.0 | 161.0 | 0.0 |
| * 78001110 | PAINT PAVEMENT MARKING - LINE 4" | FOOT | 2,516.0 | 2,516.0 | 0.0 |
| * 78008310 | POLYUREA PAVEMENT MARKING TYPE II- LINE 4" | FOOT | 1,085.0 | 1,085.0 | 0.0 |
| * 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 15.0 | 15.0 | 0.0 |
| * 78100105 | RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE) | EACH | 6.0 | 6.0 | 0.0 |
| 78200410 | GUARDRAIL MARKERS, TYPE A | EACH | 15.0 | 15.0 | 0.0 |
| 78200520 | BARRIER WALL MARKERS, TYPE B | EACH | 12.0 | 12.0 | 0.0 |
| 78201000 | TERMINAL MARKER - DIRECT APPLIED | EACH | 2.0 | 2.0 | 0.0 |
| 78300200 | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | EACH | 16.0 | 16.0 | 0.0 |
| * 89000100 | TEMPORARY TRAFFIC SIGNAL INSTALLATION | EACH | 1.0 | 1.0 | 0.0 |
| * D2002172 | EVERGREEN, PICEA PUNGENS (COLORADO SPRUCE), 6' HEIGHT, BALLED AND BURLAPPED | EACH | 12.0 | 12.0 | 0.0 |
| X0323082 | DRAINAGE SCUPPERS, DS-33 | EACH | 2.0 | 0.0 | 2.0 |
| X0323586 | PIPE DRAIN REMOVAL | FOOT | 86.0 | 86.0 | 0.0 |
| X0324059 | DEBRIS DEFLECTION SYSTEM, COMPLETE | L SUM | 1.0 | | 1.0 |
| X0324865 | DIAMOND GRINDING (BRIDGE SECTION) | SO YD | 3,620.0 | 1,644.0 | 1,976.0 |
| * X0324952 | DETOUR SIGNING | L SUM | 1.0 | 1.0 | 0.0 |
| X0348700 | AGGREGATE DITCH CHECK | EACH | 1.0 | 1.0 | 0.0 |
| X2800110 | TEMPORARY DITCH CHECKS, AGGREGATE | EACH | 16.0 | 16.0 | 0.0 |
| X4021000 | TEMPORARY ACCESS (PRIVATE ENTRANCE) | EACH | 1.0 | 1.0 | 0.0 |
| X4066414 | BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50 | TON | 90.0 | 90.0 | 0.0 |
| X4066614 | BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50 | TON | 50.0 | 50.0 | 0.0 |
| X4073041 | BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 8" | SO YD | 1,718.0 | 1,718.0 | 0.0 |
| X5012650 | CONCRETE HEADWALL REMOVAL SPECIAL | EACH | 1.0 | 1.0 | 0.0 |
| X5020501 | UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1 | EACH | 1.0 | 0.0 | 1.0 |
| X5020502 | UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2 | EACH | 1.0 | 0.0 | 1.0 |
| X5020503 | UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 3 | EACH | 1.0 | 0.0 | 1.0 |
| X5020504 | UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 4 | EACH | 1.0 | 0.0 | 1.0 |
| X7015005 | CHANGEABLE MESSAGE SIGN | CAL DA | 20.0 | 20.0 | 0.0 |
| XX001017 | REMOVE RIGHT-OF-WAY MARKERS | EACH | 2.0 | 2.0 | 0.0 |
| XX004568 | TEMPORARY ACCESS ROAD | L SUM | 1.0 | 1.0 | 0.0 |
| Z0002600 | BAR SPLICERS | EACH | 104.0 | 0.0 | 104.0 |

* DENOTES SPECIALTY ITEM

PLOT DATE = 8/28/2008
 FILE NAME = s:\projects\90841\summary.dwg
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = sstump

| REVISIONS | | ILLINOIS DEPARTMENT OF TRANSPORTATION |
|-----------|------|---------------------------------------|
| NAME | DATE | |
| | | SUMMARY OF QUANTITIES |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

SCALE: VERT. _____
 HORIZ. _____
 DATE _____

DRAWN BY _____
 CHECKED BY _____