F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
TR 110	80-03108-00-BR	SCHUYLER	20	3
STA. ———		TO STA. ———		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	*	

* BROS-169(35)

TREE REMOVAL SCHEDULE

LOCATION	TREE REMOVAL (6 TO 15 UNITS DIAMETERS)	TREE REMOVAL (OVER 15 UNITS DIAMETERS)	TREE REMOVAL, ACRES
	UNITS	UNITS	ACRES
LT. & RT. STA. 6+77 TO LT. & RT. STA. 7+01			0.05
LT. & RT. STA. 7+48 TO LT. STA. 9+00			0.15
STA. 9+84, 38' LT		24	
STA. 9+87, 32' LT	6		
STA. 9+91, 42' LT	10		
STA. 9+93, 34' LT	12		
STA. 9+96, 36' LT	8		
STA. 10+06, 34' LT	6		
STA. 10+18, 13' RT	8		
STA. 10+22, 13' RT		32	
STA. 10+24, 15' RT	8		
STA. 10+30, 22' RT	10		
STA. 11+22, 15' RT	12		
STA. 11+29, 26' RT		18	
TOTALS	80	74	0.2

TRAFFIC BARRIER TERMINALS AND GUARD RAIL SCHEDULE

LOCATION	TRAFFIC BARRIER TERMINAL, TYPE 5A EACH	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT) EACH	STEEL PLATE BEAM GUARD RAIL, TYPE A FOOT
SW CORNER	1	1	
NE CORNER	1	1	50
TOTALS	2	2	50

CULVERT SCHEDULE

LOCATION	PIPE CULVERTS, CLASS D, TYPE 1 (CMP) 36"	PIPE CULVERTS, CLASS D, TYPE 1 (CMP) 72"	END SECTIONS 36"	END SECTIONS 72"
	FOOT	FOOT	EACH	EACH
RT. STA. 5+50	29		2	
LT. STA. 7+17		2 @ 26		4
TOTALS	29	52	2	4

AGGREGATE SURFACE COURSE SCHEDULE

LOCATION	AGGREGATE SURFACE COURSE TYPE A
	TON
STA. 3+13.74 TO STA. 6+86.57	418
STA. 7+65.43 TO STA. 11+80	464
TOTALS	882

EROSION CONTROL SCHEDULE

LOCATION	EROSION CONTROL BLANKET	TEMPORARY EROSION CONTROL SEEDING	TEMPORARY DITCH CHECKS	PERIMETER EROSION BARRIER	INLET AND PIPE PROTECTION	FENCE (EROSION CONTROL)
	SQ. YD.	POUND	EACH	FOOT	EACH	FOOT
LT. STA. 3+13.74 TO LT. STA. 6+86.57		50				
RT. STA. 3+13.74 TO RT. STA. 5+38	343					
LT STA. 3+13.74 TO LT. STA. 7+00	334					
RT. STA. 3+13.74 TO RT. STA. 6+86.57		30				
LT. STA. 4+00			1			
RT. STA. 4+00			1			
RT. STA. 5+27					1	
LT. STA. 5+50			1			
LT. STA. 5+70 TO LT. STA. 6+75				142		
LT. STA. 7+02			1			
LT. STA. 7+12 TO LT. STA. 7+12						40
RT. STA. 7+40 TO RT. STA. 7+55						30
RT. STA. 7+40 TO RT. STA 9+00				160		
LT. STA. 7+65.43 TO LT. STA. 11+80		40				
RT. STA. 7+65.43 TO LT. STA. 11+80		40				
LT. STA. 8+50 TO LT. STA. 8+60						12
LT. STA. 8+85 TO LT. STA. 9+00						60
LT. STA. 10+00			1			
RT. STA. 10+05 TO RT. STA. 11+00				83		
LT. STA. 10+50 TO LT. STA. 11+00				55		
TOTALS	677	160	5	440	1	142

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION (C)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE 25%	EMBANKMENT (F)	EARTHWORK BALANCE WASTE (+) SHORTAGE (-)
	CU. YD.	CU. YD.	CU. YD.	CU. YD.
STA. 3+13.74 TO STA. 7+12	1123	842	1474	-632
STA. 7+41 TO STA. 11+80	484	363	5735	-5372
TOTALS	① 1607	② 1205	③ 7209	④ -6004

① PAY ITEM - EARTH EXCAVATION
④ PAY ITEM - FURNISH EXCAVATION

SEEDING SCHEDULE

LOCATION	SEEDING CLASS 2 (SPECIAL)
	ACRE
LT. STA. 3+13.78 TO LT. STA. 6+86.57	0.5
RT. STA. 3+13.78 TO RT. STA. 6+86.57	0.3
LT. STA. 7+65.43 TO LT. STA. 11+80	0.4
RT. STA. 7+65.43 TO RT. STA. 11+80	0.4
TOTALS	1.6

RIPRAP SCHEDULE

LOCATION	STONE RIPRAP, CLASS A5	FILTER FABRIC
	TON	SQ. YD.
LT. STA. 7+78 TO LT. STA. 8+90	610	522
TOTALS	610	522

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

T.R. ROUTE 110
SECTION 80-03108-00-BR
BROOKLYN TOWNSHIP
SCHUYLER COUNTY

SCALE: VERT. HORIZ.
DATE 08/21/02
DRAWN BY: JETT
DESIGNED BY: KUNTZMAN
CHECKED BY: COLBROOK

GREENE & BRADFORD, INC. OF SPRINGFIELD
CONSULTING ENGINEERS
820 CONSTITUTION DRIVE
SPRINGFIELD, ILLINOIS 62707
FIRM NO. 184-000576 DESIGN FIRM NO. 184-000576
PROFESSIONAL DESIGN FIRM NO. 184-000576 CORPORATION
(217) 753-8484, (217) 753-5077 FAX, (217) 753-8484 TTY, mail@greenebradford.com

COMPUTER FILE NO. SCHEDULE_01
PROJECT 02341
3/3/06 - MML

IDOTPL-20 1"=20' 8/07/00

T.R. ROUTE 110 (BROOKLYN TOWNSHIP) SCHUYLER COUNTY

DESIGN: INT. | DATE | REASON

PLOTS & CHECKS: INT. | DATE | NO. | REASON

CHECKS: INT. | DATE | REASON

FILE NAME = J:\02341\DRAWINGS\SCHEDULE.dgn
PLOT SCALE = 2.0000 ' / IN.
PLOT DATE = 6/30/2006
DGN = XES_8850_ENG.pltt
PLOT TIME = 10:13:47 AM
OPERATOR = michelleI