

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
..5	..	..JOHNSON..	..15..	..3
STA.	TO STA.			
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

\*FAI 57 & FAI 24  
 \*\*44-1L, 44-3L

### SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	LOCATION 1	LOCATION 2	LOCATION 3	LOCATION 4
				FAI 57 & FAS 1931 GOREVILLE INTERCHANGE	FAI 24 & FAS 927 TUNNEL HILL INTERCHANGE	FAI 24 & US 45 INTERCHANGE AT VIENNA	FAI 24 EAST OF PULLEY'S MILL INTERCHANGE
				RURAL	RURAL	RURAL	RURAL
				90% FED., 10% STATE	90% FED., 10% STATE	90% FED., 10% STATE	90% FED., 10% STATE
				LIGHTING	LIGHTING	LIGHTING	PAVEMENT SENSORS
JOHNSON	JOHNSON	JOHNSON	JOHNSON				
Y030-1E	Y030-1E	Y030-1E	Y030-1E				
QUANTITY	QUANTITY	QUANTITY	QUANTITY				
X0322763	FURNISH AND INSTALL PAVEMENT SENSORS	EACH	2				2.0
*50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	31.0	1.0	19.0	11.0	
67100100	MOBILIZATION	L SUM	1.0	0.5	0.5		
67000400	ENGINEER FIELD OFFICE, TYPE A	CAL MO	3.0	1.5	1.5		
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1.0				1.0
80300100	LOCATING UNDERGROUND CABLE	FOOT	20.0			20.0	
80400100	ELECTRIC SERVICE INSTALLATION	EACH	2.0	1.0	1.0		
81021550	CONDUIT, AUGURED 2" DIA., PVC	FOOT	940.0	300.0	480.0	160.0	
<del>81021590</del>	<del>CONDUIT, AUGURED 4" DIA., PVC</del>	<del>FOOT</del>	<del>45</del>	<del>45</del>			
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	10165.0	4,665.0	4,875.0	625.0	
<del>81600415</del>	<del>UNIT DUCT 2" 4 XLP GROUND 1" POLYETHYLENE</del>	<del>FOOT</del>	<del>4365</del>	<del>4365</del>			
81600315	UNIT DUCT, 2" 6XLP, 1" 6 XLP GROUND 1" POLYETHYLENE	FOOT	6140		5,355.0	785.0	
82103900	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT	EACH	28.0	14.0	14.0		
83034400	LIGHT POLE, STEEL, 45 FT. M. H., TENON MOUNT	EACH	20.0	10.0	10.0		
83035400	LIGHT POLE, STEEL, 45 FT. M. H., TENON MOUNT - TWIN	EACH	4.0	2.0	2.0		
83600355	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 6"	EACH	20.0	10.0	10.0		
83600357	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 8"	EACH	4.0	2.0	2.0		
83800650	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	96.0	48.0	48.0		
82500510	LIGHTING CONTROLLER CB-RCS 60 AMP - 240 VOLT	EACH	2.0	1.0	1.0		
87900100	DRILL EXISTING FOUNDATION	EACH	2.0			2.0	

PLOT DATE = 8/22/2005  
 FILE NAME = C:\Users\mcc\Documents\98981\98981.dwg  
 PLOT SCALE = 1/8" = 1'-0"  
 USER NAME = mccorker

Rev. \*SPECIALTY ITEMS