

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	*	VARIOUS	21	7
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		
* D-9 SAFETY FY 07-1				

RUMBLE STRIP SCHEDULE

LOCATION MILEPOST TO MILEPOST	RUMBLE STRIP	REMARKS
	FOOT	
FRANKLIN		
FAI 57		
SB LANES		
OUTSIDE SHOULDER		
MP 62.10 TO MP 80.68	90,367	GAP SN 028-0002 (133') GAP ENTRANCE RAMP AT IL 149 INTERCHANGE (900') GAP EXIT RAMP AT IL 149 INTERCHANGE (490') GAP SN 028-0005 (195'), SN 028-0007 (368'), SN 028-0008 (235'), GAP ENTRANCE RAMP AT IL 14 INTERCHANGE (900') GAP EXIT RAMP AT IL 14 INTERCHANGE (600') GAP SN 028-0011 (128') GAP ENTRANCE RAMP AT IL 154 INTERCHANGE (940') GAP EXIT RAMP AT IL 154 INTERCHANGE (660') GAP ENTRANCE RAMP AT REST AREA (1225') GAP SN 028-0014 & EXIT RAMP AT REST AREA (962') TOTAL TO BE GAPPED FOR OUTSIDE SHOULDER = 7736'
MEDIAN SHOULDER		
MP 62.10 TO MP 80.68	96,881	GAP SN 028-0002 (133'), SN 028-0005 (195'), SN 028-0007 (368'), SN 028-0008 (235'), SN 028-0011 (128'), SN 028-0014 (163') TOTAL TO BE GAPPED FOR MEDIAN SHOULDER = 1222'
COUNTY TOTAL:	187,248	
PROJECT TOTAL:	879,369	

CABLE BARRIER SCHEDULE

LOCATION STATION TO STATION	REMARKS	LENGTH	HIGH TENSION CABLE	HIGH TENSION CABLE	MOW STRIP	NOTES
			MEDIAN BARRIER	MEDIAN BARRIER		
			FOOT	EACH	SO YD	
1542+00.0 TO 1542+44.0	TERMINAL SECTION	44		1	20	
1542+44.0 TO 1562+56.0		2,012	2,012		894	
1562+56.0 TO 1563+00.0	TERMINAL SECTION	44		1	20	
1563+00.0 TO 1563+55.0	GAP CROSS-OVER					
1563+55.0 TO 1563+99.0	TERMINAL SECTION	44		1	20	CABLE TRANSITIONS FROM TYPICAL #1 TO #2
1563+99.0 TO 1572+91.1		892	892		396	
1572+91.1 TO 0+00	STATION EQUATION					
0+00 TO 5+00.0		500	500		222	
5+00.0 TO 5+44.0	2 TERMINAL SECTIONS	44		2	39	CABLE TRANSITIONS FROM TYPICAL #2 TO #3
5+44.0 TO 41+16.0		3,572	3,572		1,588	
41+16.0 TO 41+60.0	TERMINAL SECTION	44		1	20	TERMINAL SECTION FLAIRS TO WEST OF BNRR OVERPASS PIER
41+40.0 TO 41+84.0	TERMINAL SECTION	44		1	20	TERMINAL SECTION FLAIRS FROM EAST OF BNRR OVERPASS PIER
41+84.0 TO 50+00.0		816	816		363	
50+00.0 TO 53+00.0		300	300		133	
53+00.0 TO 61+26.0		826	826		367	CABLE TRANSITIONS FROM TYPICAL #3 TO #2
61+26.0 TO 61+70.0	TERMINAL SECTION	44		1	20	
61+70.0 TO 67+00.0	GAP CRAB ORCHARD CREEK	530				
67+00.0 TO 67+44.0	TERMINAL SECTION	44		1	20	
67+44.0 TO 74+30.0		686	686		305	
74+30.0 TO 78+50.0		420	420		187	
78+50.0 TO 165+06.0		8,656	8,656		3,847	CABLE TRANSITIONS FROM TYPICAL #1 TO #3
165+06.0 TO 165+50.0	TERMINAL SECTION	44		1	20	
PROJECT TOTALS:			18,680	10	8,498	

PLOT DATE = 9/20/08
 FILE NAME = c:\pwworkspace\98982\98982.dwg
 PLOT SCALE = 1/8" = 1' / IN.
 USER NAME = shppardgl