



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

November 2, 2023

SUBJECT FAU Route 1340 (Touhy Ave)
Project HSIP-5AQU(404)
Section 2021-004-TS&SW
Cook County
Contract No. 62N37Item No. 23, November 17, 2023 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices
2. Revised page ii of the Table of Contents to the Special Provisions
3. Revised page 112 of the Special Provisions
4. Revised sheet 6 of the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

LIGHT EMITTING DIODE (LED) SIGNAL HEAD AND OPTICALLY PROGRAMMED LED SIGNAL HEAD 60

LIGHT EMITTING DIODE (LED) PEDESTRIAN SIGNAL HEAD 64

TRAFFIC SIGNAL BACKPLATE 66

DETECTOR LOOP 67

VIDEO VEHICLE DETECTION SYSTEM 69

EMERGENCY VEHICLE PRIORITY SYSTEM 70

RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, DETECTOR UNIT 71

RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, PHASING UNIT 71

ACCESSIBLE PEDESTRIAN SIGNALS 72

TEMPORARY TRAFFIC SIGNAL INSTALLATION 75

TEMPORARY TRAFFIC SIGNAL TIMING 82

REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT 83

CONCRETE PAD 84

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC) 84

BLENDED FINELY DIVIDED MINERALS (BDE) 86

CEMENT, TYPE IL (BDE) 86

COMPENSABLE DELAY COSTS (BDE) 87

CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE) 90

DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE) 92

PERFORMANCE GRADED ASPHALT BINDER (BDE) 101

PORTLAND CEMENT CONCRETE (BDE) 107

SOURCE OF SUPPLY AND QUALITY REQUIREMENTS (BDE) 107

SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE) 108

SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) 108

SUBMISSION OF PAYROLL RECORDS (BDE) 109

VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE) 110

WEEKLY DBE TRUCKING REPORTS (BDE) 110

WORK ZONE TRAFFIC CONTROL DEVICES (BDE) 110

WORKING DAYS (BDE) 112

ENGINEER’S FIELD OFFICE TYPE A (D1) 112

Revised 11/2/2023

Revise Articles 1106.02(g), 1106.02(k), and 1106.02(l) to read:

“(g) Truck Mounted/Trailer Mounted Attenuators. The attenuator shall be approved for use at Test Level 3. Test Level 2 may be used for normal posted speeds less than or equal to 45 mph.

(k) Temporary Water Filled Barrier. The water filled barrier shall be a lightweight plastic shell designed to accept water ballast and be on the Department’s qualified product list.

Shop drawings shall be furnished by the manufacturer and shall indicate the deflection of the barrier as determined by acceptance testing; the configuration of the barrier in that test; and the vehicle weight, velocity, and angle of impact of the deflection test. The Engineer shall be provided one copy of the shop drawings.

(l) Movable Traffic Barrier. The movable traffic barrier shall be on the Department’s qualified product list.

Shop drawings shall be furnished by the manufacturer and shall indicate the deflection of the barrier as determined by acceptance testing; the configuration of the barrier in that test; and the vehicle weight, velocity, and angle of impact of the deflection test. The Engineer shall be provided one copy of the shop drawings. The barrier shall be capable of being moved on and off the roadway on a daily basis.”

WORKING DAYS (BDE)

Effective: January 1, 2002

The Contractor shall complete the work within 45 working days.

ENGINEER’S FIELD OFFICE TYPE A (D1)

Effective: January 1, 2022

Revise the first paragraph of Article 670.02 to read:

670.02 Engineer’s Field Office Type A (D1). Type A (D1) field offices shall have a ceiling height of not less than 7 feet and a floor space of not less than 1000 square feet with a minimum of two separate offices. The office shall also have a separate storage room capable of being locked for the storage of the nuclear measuring devices. The office shall be provided with sufficient heat, natural and artificial light, and air conditioning. Doors and windows shall be equipped with locks approved by the Engineer.

Add the following to Article 670.07 Basis of Payment.

The building or buildings, fully equipped, will be paid for at the contract unit price per calendar month or fraction thereof for ENGINEER’S FIELD OFFICE, TYPE A (D1).

Revised 11/2/2023