

# KANKAKEE VALLEY AIRPORT AUTHORITY

## KANKAKEE, ILLINOIS

### CONSTRUCTION PLANS FOR GREATER KANKAKEE AIRPORT

#### WIDEN TAXIWAY FILLET AT RUNWAY 22 END AND RELOCATE TAXIWAY A4



J.U.L.I.E.  
 JOINT UTILITY LOCATING  
 INFORMATION FOR EXCAVATORS  
 www.illinois1call.com

THE LOCATION, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES INDICATED ON THE PLANS IS NOT REPRESENTED AS BEING ACCURATE, SUFFICIENT OR COMPLETE IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE ACTUAL LOCATIONS OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY UTILITY COMPANIES OF HIS OPERATIONAL PLANS, OBTAIN FROM RESPECTIVE UTILITY COMPANIES DETAILED INFORMATION AND ASSISTANCE RELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OF THE COMPANIES FOR REMOVAL OR ADJUSTMENT WHERE REQUIRED. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY OF JURISDICTION AND THE ONE-CALL NOTICE SYSTEM. THE ENGINEER SHALL ALSO BE IMMEDIATELY NOTIFIED. ANY SUCH UTILITY OR SERVICES SHALL BE RESTORED TO SERVICE AT ONCE AND PAID FOR BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CONTRACT.



*D. Kyle Peabody*

LICENSE EXPIRATION  
 DATE: 11/30/2023  
 DATE SIGNED: 09/20/2023

ILLINOIS PROJECT: IKK-4991

SEPTEMBER 22, 2023

CALL J.U.L.I.E. FOR UTILITY INFORMATION AT 811.

© Copyright CMT, Inc. 21001660-00


CRAWFORD, MURPHY & TILLY, INC.  
 CONSULTING ENGINEERS  
 License No. 184-000613

SUBMITTED BY *D. Kyle Peabody*  
 D. KYLE PEABODY, P.E.


DATE 09/20/2023

APPROVED BY *Jeff Benoit*  
 JEFF BENOIT - AIRPORT MANAGER

DATE 9-21-23



LOCATION MAP



SITE PLAN

<b>RUNWAY 4/22</b>	
DESIGN AIRCRAFT APPROACH CATEGORY D	
<b>RUNWAY 16/34</b>	
DESIGN AIRCRAFT APPROACH CATEGORY B	
<b>TAXIWAY A, A2, B, A3, A4, A5, D, H</b>	
TAXIWAY DESIGN GROUP 2A AND 2B	
<b>KANKAKEE VALLEY AIRPORT AUTHORITY                  GREATER KANKAKEE AIRPORT</b>	
SECTION: 21 RANGE: R 12 E TOWNSHIP: T 30 N	COUNTY: KANKAKEE TOWNSHIP: OTTO
UNICOM RADIO FREQUENCY - 123.0	



CONSULTANTS

FINAL

WIDEN TAXIWAY FILLET AT  
RUNWAY 22 END AND  
RELOCATE TAXIWAY A4

SEPTEMBER 22, 2023

OWNER



MARK	DATE	DESCRIPTION

CMT PROJECT NO: 21001660.00  
 CAD DWG FILE:  
 DESIGNED BY: STL  
 DRAWN BY: JRO  
 CHECKED BY: STL  
 APPROVED BY: DKP  
 COPYRIGHT:

SHEET TITLE

**INDEX TO SHEETS/  
SUMMARY OF  
QUANTITIES**

**INDEX TO SHEETS**

- 1 COVER SHEET
- 2 INDEX TO SHEETS - SUMMARY OF QUANTITIES
- 3 SITE PLAN AND PROJECT CONTROL PLAN
- 4 SEQUENCE OF CONSTRUCTION PHASE 1
- 5 SEQUENCE OF CONSTRUCTION PHASE 2
- 6 SEQUENCE OF CONSTRUCTION PHASE 3
- 7 SEQUENCE OF CONSTRUCTION PHASE 4A
- 8 SEQUENCE OF CONSTRUCTION PHASE 4B
- 9 SEQUENCE OF CONSTRUCTION GENERAL NOTES AND DETAILS - 1
- 10 SEQUENCE OF CONSTRUCTION GENERAL NOTES AND DETAILS - 2
- 11 STORMWATER POLLUTION PREVENTION PLAN - 1
- 12 STORMWATER POLLUTION PREVENTION PLAN - 2
- 13 STORMWATER POLLUTION PREVENTION PLAN NOTES AND DETAILS - 1
- 14 STORMWATER POLLUTION PREVENTION PLAN NOTES AND DETAILS - 2
- 15 EXISTING CONDITIONS - PROPOSED REMOVALS - 1
- 16 EXISTING CONDITIONS - PROPOSED REMOVALS - 2
- 17 PROPOSED IMPROVEMENTS - 1
- 18 PROPOSED IMPROVEMENTS - 2
- 19 TYPICAL SECTIONS - 1
- 20 TYPICAL SECTIONS - 2
- 21 TAXIWAY A4 PLAN AND PROFILE
- 22 DRAINAGE DETAILS - 1
- 23 DRAINAGE DETAILS - 2
- 24 DRAINAGE DETAILS - 3
- 25 GRADING PLAN - 1
- 26 GRADING PLAN - 2
- 27 ELECTRICAL PLAN - 1
- 28 ELECTRICAL PLAN - 2
- 29 PROPOSED ELECTRICAL CIRCUITRY PLAN - 1
- 30 PROPOSED ELECTRICAL CIRCUITRY PLAN - 2
- 31 ELECTRICAL DETAILS - 1
- 32 ELECTRICAL DETAILS - 2
- 33 ELECTRICAL DETAILS - 3
- 34 GEOTECHNICAL ENGINEERING INFORMATION
- 35 INDEX TO CROSS SECTIONS AND EARTHWORK SUMMARY
- 36 CROSS SECTIONS - 1
- 37 CROSS SECTIONS - 2
- 38 CROSS SECTIONS - 3

**SUMMARY OF QUANTITIES**

ITEM	DESCRIPTION	UNIT	ESTIMATED QUANTITY	RECORD QUANTITY
AR108158	1/C #8 5 KV UG CABLE IN UD	FOOT	5,600	
AR108960	REMOVE CABLE	FOOT	7,000	
AR110502	2-WAY CONCRETE ENCASED DUCT	FOOT	100	
AR110504	4-WAY CONCRETE ENCASED DUCT	FOOT	110	
AR110551	EXTEND DUCT	FOOT	15	
AR110610	ELECTRICAL HANDHOLE	EACH	3	
AR110900	REMOVE DUCT	FOOT	120	
AR125410	MITL-STAKE MOUNTED	EACH	57	
AR125415	MITL-BASE MOUNTED	EACH	8	
AR125443	TAXI GUIDANCE SIGN, 3 CHARACTER	EACH	3	
AR125446	TAXI GUIDANCE SIGN, 6 CHARACTER	EACH	1	
AR125565	SPLICE CAN	EACH	1	
AR125901	REMOVE STAKE MOUNTED LIGHT	EACH	39	
AR125902	REMOVE BASE MOUNTED LIGHT	EACH	4	
AR125904	REMOVE TAXI GUIDANCE SIGN	EACH	3	
AR125906	REMOVE SPLICE CAN	EACH	2	
AR125962	RELOCATE BASE MOUNTED LIGHT	EACH	1	
AR150510	ENGINEER'S FIELD OFFICE	L SUM	1	
AR150520	MOBILIZATION	L SUM	1	
AR152410	UNCLASSIFIED EXCAVATION	CU YD	7,850	
AR152540	SOIL STABILIZATION FABRIC	SQ YD	3,575	
AR156510	SILT FENCE	FOOT	1,250	
AR156520	INLET PROTECTION	EACH	4	
AR208515	POROUS GRANULAR EMBANKMENT	CU YD	1,400	
AR209612	CRUSHED AGG. BASE COURSE - 12"	SQ YD	715	
AR800026	CRUSHED AGG. BASE COURSE - 15"	SQ YD	2,700	
AR401610	BITUMINOUS SURFACE COURSE	TON	780	
AR401900	REMOVE BITUMINOUS PAVEMENT	SQ YD	2,250	
AR403610	BITUMINOUS BASE COURSE	TON	970	
AR602510	BITUMINOUS PRIME COAT	GALLON	1,000	
AR603510	BITUMINOUS TACK COAT	GALLON	700	
AR620520	PAVEMENT MARKING-WATERBORNE	SQ FT	3,550	
AR620525	PAVEMENT MARKING-BLACK BORDER	SQ FT	2,950	
AR620900	PAVEMENT MARKING REMOVAL	SQ FT	4,950	
AR701524	24" RCP, CLASS IV	FOOT	540	
AR701900	REMOVE PIPE	FOOT	560	
AR705526	6" PERFORATED UNDERDRAIN W/SOCK	FOOT	780	
AR751540	4' MANHOLE	EACH	2	
AR751560	6' MANHOLE	EACH	1	
AR751900	REMOVE INLET	EACH	1	
AR800003	2 - 1/C #8 5KV UG CABLE IN UD	FOOT	365	
AR901510	SEEDING	ACRE	4.5	
AR908515	HEAVY-DUTY HYDRAULIC MULCH	ACRE	4.5	



CONSULTANTS

**FINAL**

**WIDEN TAXIWAY FILLET AT  
RUNWAY 22 END AND  
RELOCATE TAXIWAY A4**



SEPTEMBER 22, 2023

OWNER



**LEGEND**

- PROPOSED IMPROVEMENTS
- PROPOSED REMOVALS
- EXISTING HANGAR BUILDING
- EXISTING FENCE
- EXISTING AIRPORT PROPERTY LINE
- BM-1 BENCHMARK
- CP-1 CONTROL POINT



VERTICAL CONTROL		
POINT	DESCRIPTION	ELEVATION
BM-1	CUT "O" AT BEACON	622.410
BM-4	SW BOLT ON WINDSOCK	619.350
BM-14	INLET EAST OF TXY A2 AT TURNING CURVE TO RWY 22 END	617.925

HORIZONTAL CONTROL			
POINT	DESCRIPTION	NORTHING	EASTING
CP-1	IRON ROD WITH CAP	1602510.958	1116210.009
CP-2	IRON ROD WITH CAP	1602497.308	1116561.220
CP-3	IRON ROD WITH CAP	1603024.403	1117266.387
CP-4	IRON ROD WITH CAP	1603408.086	1117651.081
CP-5	IRON ROD WITH CAP	1606982.255	1120057.182
1	RUNWAY 4/22 AND TAXIWAY A5	1602569.994	1116199.123
2	RUNWAY 4/22 AND EXISTING TAXIWAY A4	1603426.484	1116868.559
3	RUNWAY 4/22 AND NEW TAXIWAY A4	1603664.461	1117054.563
4	RUNWAY 4/22 AND NEW TAXIWAY A4	1603418.135	1117369.718
5	RUNWAY 4/22 AND EXISTING TAXIWAY A4	1603180.157	1117183.714
6	RUNWAY 4/22 AND TAXIWAY A5	1602323.667	1116514.277
7	RUNWAY 4/22 AND TAXIWAY A	1607243.202	1119851.722

THE LOCATION OF UNDERGROUND UTILITIES AS INDICATED ON THE PLANS HAS BEEN OBTAINED FROM EXISTING RECORDS. NEITHER THE OWNER NOR THE ARCHITECT/ENGINEER ASSUMES ANY RESPONSIBILITY WHATSOEVER WITH RESPECT TO THE ACCURACY, COMPLETENESS, OR SUFFICIENCY OF THE INFORMATION. THERE IS NO GUARANTEE, EITHER EXPRESSED OR IMPLIED, THAT THE LOCATIONS, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED IN THE CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANIES OF HIS OPERATIONAL PLANS AND SHALL OBTAIN FROM THE RESPECTIVE UTILITY COMPANIES DETAILED INFORMATION AND ASSISTANCE RELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OF THE COMPANIES FOR REMOVAL, RELOCATION OR ADJUSTMENT WHERE REQUIRED. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY OF JURISDICTION. THE ARCHITECT/ENGINEER SHALL ALSO BE IMMEDIATELY NOTIFIED. ANY SUCH MAINS AND SERVICES SHALL BE RESTORED TO SERVICE AT ONCE AND PAID FOR BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CONTRACT.

MARK	DATE	DESCRIPTION

CMT PROJECT NO: 21001660.00  
 CAD DWG FILE:  
 DESIGNED BY: STL  
 DRAWN BY: JRO  
 CHECKED BY: STL  
 APPROVED BY: DKP  
 COPYRIGHT:

**SITE PLAN  
AND PROJECT  
CONTROL PLAN**



CONSULTANTS

FINAL

WIDEN TAXIWAY FILLET AT RUNWAY 22 END AND RELOCATE TAXIWAY A4

SEPTEMBER 22, 2023

OWNER




MARK	DATE	DESCRIPTION

CMT PROJECT NO: 21001660.00  
 CAD DWG FILE:  
 DESIGNED BY: STL  
 DRAWN BY: JRO  
 CHECKED BY: STL  
 APPROVED BY: DKP  
 COPYRIGHT:

SHEET TITLE

### SEQUENCE OF CONSTRUCTION PHASE 1



PHASE 1	OPERATIONAL STATUS/RESTRICTIONS
WORK AREA 1	<ul style="list-style-type: none"> <li>RUNWAY 16/34 OPEN; RUNWAY 4/22 OPEN; TAXIWAY A CLOSED (EAST OF TAXIWAY A5 AND WEST OF TAXIWAY A3); TAXIWAY A CLOSED (EAST OF TAXIWAY A2); TAXIWAY A4 CLOSED; ALL OTHER TAXIWAYS OPEN</li> </ul>

#### PHASE 1: SUGGESTED SEQUENCE OF CONSTRUCTION

- COORDINATE PARTIAL CLOSURE OF TAXIWAY A WITH RESIDENT ENGINEER.
- MARK AIR OPERATIONS AREA (A.O.A.) WITH LATHE AND RIBBON AND PLACE BARRICADES AS SHOWN OR AS DIRECTED BY THE ENGINEER.
- CONSTRUCT PROPOSED IMPROVEMENTS, INCLUDING EARTHWORK GRADING, BITUMINOUS PAVEMENT REMOVAL AND AIRFIELD LIGHTING REMOVAL, SAFETY GRADING, DRAINAGE STRUCTURES INSTALLATION AND CONSTRUCTION OF POROUS GRANULAR EMBANKMENT AND AGGREGATE BASE COURSE FOR PHASE 1 LIMITS.
- CONSTRUCT TEMPORARY WEDGING OF BASE COURSE TO MEET FAA CRITERIA.
- CLEAN PAVEMENTS AND REMOVE BARRICADES.

#### PHASE 1 NOTES

- AT TIMES, AIRCRAFT MAY BE REQUIRED TO EXECUTE A TURNAROUND ON TAXIWAY A AT RUNWAY 22 END. THE CONTRACTOR SHALL ENSURE THAT HIS PERSONNEL ARE CLEAR OF THIS AREA OF TAXIWAY A AT ALL TIMES.
- AT THE CONTRACTOR'S OPTION, PHASES 1 AND 2 MAY BE CONCURRENT.
- AS CONSTRUCTION PROGRESSES IN THE PHASE 2 WORK AREA, THE CONTRACTOR SHALL INSTALL A TAXIWAY CLOSURE MARKER IN ACCORDANCE WITH THE DETAIL SHOWN ON THE SEQUENCE OF CONSTRUCTION GENERAL NOTES AND DETAILS SHEET TO PREVENT AIRCRAFT FROM TURNING ONTO THE PARTIALLY CONSTRUCTED NEW TAXIWAY A4. AS SUBSEQUENT PAVEMENT LAYERS ARE CONSTRUCTED, THE TAXIWAY CLOSURE MARKER SHALL BE TRANSFERRED TO THE TOPMOST LAYER. THE TAXIWAY CLOSURE MARKER IS NOT REQUIRED TO BE IN PLACE DURING WORK WITHIN THE PHASE 2 WORK AREA, BUT SHALL BE IN PLACE PRIOR TO REOPENING RUNWAY 4/22.
- ALL WORK IN THIS PHASE WILL REQUIRE FULL TIME CROSSING GUARDS IN RADIO CONTACT WITH UNICOM FREQUENCY AT LOCATIONS DESIGNATED. AIRCRAFT AND CONSTRUCTION EQUIPMENT WILL BE REQUIRED TO USE SECTIONS OF TAXIWAY A. THE CONTRACTOR WILL BE REQUIRED TO HAVE A MOTORIZED SWEEPER OPERATING FULL TIME TO REMOVE DEBRIS. COST OF CROSSING GUARDS AND SWEEPERS SHALL BE INCIDENTAL TO THE CONTRACT.

#### PHASING NOTES (ALL PHASES)

- THE INTENT OF THE PHASING PLANS IS TO MINIMIZE THE IMPACT OF CONSTRUCTION ON THE OPERATION OF THE AIRPORT. THE CONTRACTOR SHALL CONSTRUCT THE PROJECT IN CONSECUTIVE PHASES AS OUTLINED IN THE PLANS UNLESS OTHERWISE APPROVED BY THE ENGINEER.
- THE CONTRACTOR SHALL SUBMIT A CONSTRUCTION SCHEDULE. STRICT ADHERENCE TO THE APPROVED SCHEDULE WILL BE ENFORCED TO AVOID CONFLICTS WITH OTHER CONSTRUCTION ACTIVITIES ON THE AIRPORT AND THE ADVERSE EFFECTS THEY COULD HAVE ON AIRPORT OPERATIONS.
- THE CONTRACTOR SHALL COORDINATE CLOSELY WITH THE AIRPORT STAFF TO SCHEDULE THE RUNWAY/TAXIWAY CLOSURES. ITEMS SUCH AS THE EXTENDED WEATHER FORECAST, MATERIAL AVAILABILITY, EQUIPMENT DEPENDABILITY AND MANPOWER AVAILABILITY SHALL BE DISCUSSED PRIOR TO SCHEDULING THESE CRITICAL CLOSURES. THE AIRPORT MANAGER AND THE CONTRACTOR SHALL MUTUALLY AGREE ON THE EXACT DATE OF THE CLOSURE.
- CONTRACTOR MUST MAINTAIN ACCESS TO ALL APRON/HANGAR AREAS AT ALL TIMES. CONTRACTOR SHALL RELOCATE EQUIPMENT AT NO ADDITIONAL COST TO THE CONTRACT TO ALLOW AIRCRAFT TO PASS. THE CONTRACTOR SHALL COORDINATE CONSTRUCTION OPERATIONS AT ALL APRON/HANGAR AREAS TO PROVIDE MINIMAL DISRUPTIONS TO AIRCRAFT MOVEMENT IN THAT AREA.
- THE CONTRACTOR SHALL SUFFICIENTLY MARK HIS WORK AREA TO PREVENT PERSONNEL AND EQUIPMENT FROM ACCESSING THE RUNWAY SAFETY AREA(S) WHILE THE RUNWAY IS OPEN TO AIR TRAFFIC. THE MANNER IN WHICH THE WORK AREA IS MARKED SHALL NOT BE CONSIDERED A HAZARD TO AIR TRAFFIC. PREVIOUS METHODS INCLUDE THE INSTALLATION OF LATHE AND RIBBON AT SUFFICIENT SPACING TO PROVIDE GOOD VISIBILITY.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR TRAFFIC CONTROL REQUIRED AT THE STAGING AREA AT THE TERMINAL APRON.

Path: K:\Kankakee\21001660.00\_Releact\TxD\Widom\TwyFiles\Draw\Sheets\2100166000-1kk- seq.dwg  
Date: Monday, October 9, 2023 4:44:01 PM



CONSULTANTS

FINAL

WIDEN TAXIWAY FILLET AT RUNWAY 22 END AND RELOCATE TAXIWAY A4

SEPTEMBER 22, 2023

OWNER





MARK DATE DESCRIPTION

CMT PROJECT NO: 21001660.00  
 CAD DWG FILE:  
 DESIGNED BY: STL  
 DRAWN BY: JRO  
 CHECKED BY: STL  
 APPROVED BY: DKP  
 COPYRIGHT:

SHEET TITLE

# SEQUENCE OF CONSTRUCTION PHASE 2



PHASE 2	ALLOWABLE WORK PERIODS	OPERATIONAL STATUS/RESTRICTIONS
WORK AREA 2	20 CALENDAR DAYS	<ul style="list-style-type: none"> <li>RUNWAY 16/34 OPEN; RUNWAY 4/22 CLOSED; TAXIWAY A (EAST OF RUNWAY 16/34) CLOSED; TAXIWAYS A4 AND A3 CLOSED; ALL OTHER TAXIWAYS OPEN</li> </ul>

### PHASE 2: SUGGESTED SEQUENCE OF CONSTRUCTION

- COORDINATE TEMPORARY CLOSURE OF RUNWAY 4/22 WITH THE RESIDENT ENGINEER AND PLACE CLOSED RUNWAY MARKERS.
- PLACE BARRICADES AS SHOWN OR AS DIRECTED BY THE RESIDENT ENGINEER FOR PHASE 2 LIMITS.
- CONSTRUCT PROPOSED IMPROVEMENTS, INCLUDING EARTHWORK GRADING, BITUMINOUS PAVEMENT REMOVAL AND AIRFIELD LIGHTING REMOVAL, SAFETY GRADING, AND CONSTRUCTION OF POROUS GRANULAR EMBANKMENT AND AGGREGATE BASE COURSE FOR PHASE 2 LIMITS.
- CONSTRUCT TEMPORARY WEDGING OF BASE COURSE TO MEET FAA CRITERIA.
- CLEAN ALL PAVEMENTS, REMOVE PHASE 2 BARRICADES AND REOPEN RUNWAY 4/22 .

### PHASE 2 NOTES

- THE CONTRACTOR SHALL BE ALLOWED NO MORE THAN 20 CALENDAR DAYS CLOSURES TO COMPLETE ALL OF THE PHASE 2 WORK.
- AT THE CONTRACTOR'S OPTION, PHASES 1 AND 2 MAY BE CONCURRENT.
- THE CONTRACTOR SHALL ENTER AND EXIT THE FIELD AT THE LOCATIONS SHOWN DEPENDING ON THE WORK AREA. AT NO TIME SHALL THE CONTRACTOR USE RUNWAY 4/22 AS A HAUL ROUTE.
- ANY DAMAGE CAUSED BY CONTRACTOR HAUL OPERATIONS OVER EXISTING AIRFIELD PAVEMENTS SHALL BE REPAIRED BY THE CONTRACTOR AT NO COST TO THE CONTRACT.
- SEE SEQUENCE OF CONSTRUCTION PHASE 1 AND THE SEQUENCE OF CONSTRUCTION GENERAL NOTES AND DETAILS SHEETS FOR ADDITIONAL REQUIREMENTS.
- ALL WORK IN THIS PHASE WILL REQUIRE FULL TIME CROSSING GUARDS IN RADIO CONTACT WITH UNICOM FREQUENCY AT LOCATIONS DESIGNATED. AIRCRAFT AND CONSTRUCTION EQUIPMENT WILL BE REQUIRED TO USE SECTIONS OF TAXIWAY A. THE CONTRACTOR WILL BE REQUIRED TO HAVE A MOTORIZED SWEEPER OPERATING FULL TIME TO REMOVE DEBRIS. COST OF CROSSING GUARDS AND SWEEPERS SHALL BE INCIDENTAL TO THE CONTRACT.

### LEGEND

- PHASE 2 WORK AREA
- AIRCRAFT MOVEMENT AREA
- ALL PHASES LOW PROFILE BARRICADES FOR HAUL ROUTE (WITH WORK POINT AIRSPACE EVALUATION POINT SHOWN)
- AIR OPERATIONS AREA (A.O.A.) ACTIVE RUNWAYS 250' CENTERLINE TO A.O.A. ACTIVE TAXIWAYS 93' CENTERLINE TO A.O.A.
- TEMPORARY CLOSED RUNWAY MARKER (NONE THIS PHASE)
- TEMPORARY CLOSED TAXIWAY MARKER
- CONTRACTOR'S ACCESS/HAUL ROAD
- CROSSING GUARD AND TEMPORARY "STOP" AND "AIRCRAFT MOVEMENT AREA" SIGN

### GENERAL NOTES - RUNWAY 4/22

- PRIOR TO REOPENING A CLOSED RUNWAY, THE ENTIRE RUNWAY SAFETY AREA (250 FEET FROM CENTERLINE) MUST MEET FAA CRITERIA. FAA CRITERIA REQUIRE THAT THERE BE NO OPEN EXCAVATIONS OR TRENCHES, THE MAXIMUM PAVEMENT DROPOFF BE 3 INCHES, AND ALL GRADES IN ANY DIRECTION BE LESS THAN 3 PERCENT. TEMPORARY WEDGING OF BASE COURSE WILL BE REQUIRED TO MEET CRITERIA.
- A MAXIMUM OF TWENTY (20) CALENDAR DAY CLOSURES ON RUNWAY 4/22 WILL BE ALLOWED. SEE SEQUENCE OF CONSTRUCTION GENERAL NOTES FOR DETAILS ON RUNWAY CLOSURES. FOR EVERY ADDITIONAL RUNWAY 4/22 CLOSURE REQUIRED BY THE CONTRACTOR LIQUIDATED DAMAGES IN THE AMOUNT OF \$1,000 WILL BE ASSESSED.

Path: K:\Kankakee\21001660.00\_Reloc\Twy\DWiden\Twy\Draw\Sheet\sequence of construction - 2.dwg  
Date: Monday, October 9, 2023 4:44:05 PM



CONSULTANTS

FINAL

WIDEN TAXIWAY FILLET AT RUNWAY 22 END AND RELOCATE TAXIWAY A4

SEPTEMBER 22, 2023


OWNER



MARK	DATE	DESCRIPTION

CMT PROJECT NO:	21001660.00
CAD DWG FILE:	
DESIGNED BY:	STL
DRAWN BY:	JRO
CHECKED BY:	STL
APPROVED BY:	DKP
COPYRIGHT:	

SEQUENCE OF CONSTRUCTION PHASE 3



PHASE 3	ALLOWABLE WORK PERIODS	OPERATIONAL STATUS/RESTRICTIONS
WORK AREA 3	4 CALENDAR DAYS	• RUNWAY 16/34 OPEN; RUNWAY 4/22 CLOSED; TAXIWAY A CLOSED; TAXIWAYS A4 AND A3 CLOSED; ALL OTHER TAXIWAYS OPEN

PHASE 3: SUGGESTED SEQUENCE OF CONSTRUCTION

- COORDINATE TEMPORARY CLOSURE OF RUNWAY 4/22 WITH THE RESIDENT ENGINEER AND PLACE CLOSED RUNWAY MARKERS.
- PLACE BARRICADES AS SHOWN OR AS DIRECTED BY THE RESIDENT ENGINEER FOR PHASE 3 LIMITS.
- CONSTRUCT BITUMINOUS PAVING AND TAXIWAY AND RUNWAY SAFETY AREA GRADING FOR PHASE 3 LIMITS.
- CLEAN ALL PAVEMENTS, REMOVE PHASE 3 BARRICADES AND REOPEN RUNWAY 4/22.

PHASE 3 NOTES

1. THE CONTRACTOR SHALL BE ALLOWED NO MORE THAN FOUR (4) CALENDAR DAY CLOSURES TO COMPLETE ALL OF THE PHASE 3 WORK.
2. THE CONTRACTOR SHALL ENTER AND EXIT THE FIELD AT THE LOCATIONS SHOWN DEPENDING ON THE WORK AREA. AT NO TIME SHALL THE CONTRACTOR USE RUNWAY 4/22 AS A HAUL ROUTE.
3. ANY DAMAGE CAUSED BY CONTRACTOR HAUL OPERATIONS OVER EXISTING AIRFIELD PAVEMENTS SHALL BE REPAIRED BY THE CONTRACTOR AT NO COST TO THE CONTRACT.
4. THE CONTRACTOR SHALL COORDINATE WITH THE AIRPORT TO ALLOW AIRCRAFT ACCESS TO AND FROM THE ARMY AVIATION SUPPORT FACILITY AND READINESS CENTER.
5. SEE THE SEQUENCE OF CONSTRUCTION GENERAL NOTES AND DETAILS SHEETS FOR ADDITIONAL REQUIREMENTS.
6. ALL WORK IN THIS PHASE WILL REQUIRE FULL TIME CROSSING GUARDS IN RADIO CONTACT WITH UNICOM FREQUENCY AT LOCATIONS DESIGNATED. AIRCRAFT AND CONSTRUCTION EQUIPMENT WILL BE REQUIRED TO USE SECTIONS OF TAXIWAY A. THE CONTRACTOR WILL BE REQUIRED TO HAVE A MOTORIZED SWEEPER OPERATING FULL TIME TO REMOVE DEBRIS. COST OF CROSSING GUARDS AND SWEEPERS SHALL BE INCIDENTAL TO THE CONTRACT.

LEGEND

- PHASE 3 WORK AREA
- AIRCRAFT MOVEMENT AREA
- ALL PHASES LOW PROFILE BARRICADES FOR HAUL ROUTE
- AIR OPERATIONS AREA (A.O.A.)
- ACTIVE RUNWAYS 250' CENTERLINE TO A.O.A.
- ACTIVE TAXIWAYS 93' CENTERLINE TO A.O.A.
- TEMPORARY CLOSED RUNWAY MARKER (NONE THIS PHASE)
- TEMPORARY CLOSED TAXIWAY MARKER
- CONTRACTOR'S ACCESS/HAUL ROAD
- CROSSING GUARD AND TEMPORARY "STOP" AND "AIRCRAFT MOVEMENT AREA" SIGN

GENERAL NOTES - RUNWAY 4/22

1. PRIOR TO REOPENING A CLOSED RUNWAY, THE ENTIRE RUNWAY SAFETY AREA (250 FEET FROM CENTERLINE) MUST MEET FAA CRITERIA. FAA CRITERIA REQUIRE THAT THERE BE NO OPEN EXCAVATIONS OR TRENCHES, THE MAXIMUM PAVEMENT DROPOFF BE 3 INCHES, AND ALL GRADES IN ANY DIRECTION BE LESS THAN 3 PERCENT. TEMPORARY WEDGING OF BASE COURSE WILL BE REQUIRED TO MEET CRITERIA.
2. A MAXIMUM OF FOUR (4) CALENDAR DAY CLOSURES ON RUNWAY 4/22 WILL BE ALLOWED. SEE SEQUENCE OF CONSTRUCTION GENERAL NOTES FOR DETAILS ON RUNWAY CLOSURES. FOR EVERY ADDITIONAL RUNWAY 4/22 CLOSURE REQUIRED BY THE CONTRACTOR LIQUIDATED DAMAGES IN THE AMOUNT OF \$1,000 WILL BE ASSESSED.

Path: K:\Kankakee\21001660.dwg, RelocTwyD\WidomTwyFiles\Draw\Sheets\sequence of construction -3.dwg Date: Monday, October 9, 2023 4:44:11 PM




CONSULTANTS

**FINAL**

WIDEN TAXIWAY FILLET AT  
RUNWAY 22 END AND  
RELOCATE TAXIWAY A4

SEPTEMBER 22, 2023

OWNER



PHASE 4A	OPERATIONAL STATUS/RESTRICTIONS
WORK AREA 4A	<ul style="list-style-type: none"> <li>RUNWAY 16/34 OPEN; RUNWAY 4/22 OPEN; TAXIWAY A CLOSED (EAST OF TAXIWAY A5 AND WEST OF TAXIWAY A3); TAXIWAY A CLOSED (EAST OF TAXIWAY A2); TAXIWAY A4 CLOSED; ALL OTHER TAXIWAYS OPEN</li> </ul>

**PHASE 4A: SUGGESTED SEQUENCE OF CONSTRUCTION**

- COORDINATE PARTIAL CLOSURE OF TAXIWAY A WITH RESIDENT ENGINEER.
- PLACE BARRICADES AS SHOWN OR AS DIRECTED BY THE RESIDENT ENGINEER FOR PHASE 4A LIMITS.
- CONSTRUCT LIGHTING INSTALLATION AND SEEDING AND MULCHING FOR PHASE 4A LIMITS.
- REMOVE BARRICADES.

**PHASE 4A NOTES**

1. AT TIMES, AIRCRAFT MAY BE REQUIRED TO EXECUTE A TURNAROUND ON TAXIWAY A AT RUNWAY 22 END. THE CONTRACTOR SHALL ENSURE THAT HIS PERSONNEL ARE CLEAR OF THIS AREA OF TAXIWAY A AT ALL TIMES.
2. SEE THE SEQUENCE OF CONSTRUCTION GENERAL NOTES AND DETAILS SHEETS FOR ADDITIONAL REQUIREMENTS.
3. ALL WORK IN THIS PHASE WILL REQUIRE FULL TIME CROSSING GUARDS IN RADIO CONTACT WITH UNICOM FREQUENCY AT LOCATIONS DESIGNATED. AIRCRAFT AND CONSTRUCTION EQUIPMENT WILL BE REQUIRED TO USE SECTIONS OF TAXIWAY A. THE CONTRACTOR WILL BE REQUIRED TO HAVE A MOTORIZED SWEEPER OPERATING FULL TIME TO REMOVE DEBRIS. COST OF CROSSING GUARDS AND SWEEPERS SHALL BE INCIDENTAL TO THE CONTRACT.

**LEGEND**

- PHASE 4A WORK AREA
- AIRCRAFT MOVEMENT AREA
- ALL PHASES LOW PROFILE BARRICADES FOR HAUL ROUTE (WITH WORK POINT AIRSPACE EVALUATION POINT SHOWN)
- AIR OPERATIONS AREA (A.O.A.) ACTIVE RUNWAYS 250' CENTERLINE TO A.O.A. ACTIVE TAXIWAYS 93' CENTERLINE TO A.O.A.
- TEMPORARY CLOSED RUNWAY MARKER (NONE THIS PHASE)
- TEMPORARY CLOSED TAXIWAY MARKER
- CONTRACTOR'S ACCESS/HAUL ROAD
- CROSSING GUARD AND TEMPORARY "STOP" AND "AIRCRAFT MOVEMENT AREA" SIGN

Path: K:\Kankakee\A021001660.00\_RelocTaxiDWiden\Draw\Sheets\sequence of construction - 4b.dwg  
 Date: Monday, October 9, 2023 4:44:16 PM

MARK	DATE	DESCRIPTION

CMT PROJECT NO:	21001660.00
CAD DWG FILE:	
DESIGNED BY:	STL
DRAWN BY:	JRO
CHECKED BY:	STL
APPROVED BY:	DKP
COPYRIGHT:	

**SEQUENCE OF CONSTRUCTION PHASE 4A**




MARK	DATE	DESCRIPTION

CMT PROJECT NO:	21001660.00
CAD DWG FILE:	
DESIGNED BY:	STL
DRAWN BY:	JRO
CHECKED BY:	STL
APPROVED BY:	DKP
COPYRIGHT:	

SHEET TITLE

### SEQUENCE OF CONSTRUCTION PHASE 4B



PHASE 4B	ALLOWABLE WORK PERIODS	OPERATIONAL STATUS/RESTRICTIONS
WORK AREA 4B	10 CALENDAR DAYS	<ul style="list-style-type: none"> <li>RUNWAY 16/34 OPEN; RUNWAY 4/22 CLOSED; TAXIWAY A (EAST OF RUNWAY 16/34) CLOSED; TAXIWAYS A4 (NORTH OF TAXIWAY A) AND A3 CLOSED; ALL OTHER TAXIWAYS OPEN</li> </ul>

#### PHASE 4B: SUGGESTED SEQUENCE OF CONSTRUCTION

- COORDINATE TEMPORARY CLOSURE OF RUNWAY 4/22 WITH THE RESIDENT ENGINEER AND PLACE CLOSED RUNWAY MARKERS.
- PLACE BARRICADES AS SHOWN OR AS DIRECTED BY THE RESIDENT ENGINEER FOR PHASE 4B LIMITS.
- CONSTRUCT LIGHTING INSTALLATION AND SEEDING AND MULCHING FOR PHASE 4B LIMITS.
- REMOVE PHASE 4B BARRICADES AND REOPEN RUNWAY 4/22.

#### PHASE 4B NOTES

- THE CONTRACTOR SHALL BE ALLOWED NO MORE THAN TEN (10) CALENDAR DAY CLOSURES TO COMPLETE ALL OF THE PHASE 4B WORK.
- THE CONTRACTOR SHALL ENTER AND EXIT THE FIELD AT THE LOCATIONS SHOWN DEPENDING ON THE WORK AREA. AT NO TIME SHALL THE CONTRACTOR USE RUNWAY 4/22 AS A HAUL ROUTE.
- ANY DAMAGE CAUSED BY CONTRACTOR HAUL OPERATIONS OVER EXISTING AIRFIELD PAVEMENTS SHALL BE REPAIRED BY THE CONTRACTOR AT NO COST TO THE CONTRACT.
- SEE THE SEQUENCE OF CONSTRUCTION GENERAL NOTES AND DETAILS SHEETS FOR ADDITIONAL REQUIREMENTS.
- ALL WORK IN THIS PHASE WILL REQUIRE FULL TIME CROSSING GUARDS IN RADIO CONTACT WITH UNICOM FREQUENCY AT LOCATIONS DESIGNATED. AIRCRAFT AND CONSTRUCTION EQUIPMENT WILL BE REQUIRED TO USE SECTIONS OF TAXIWAY A. THE CONTRACTOR WILL BE REQUIRED TO HAVE A MOTORIZED SWEEPER OPERATING FULL TIME TO REMOVE DEBRIS. COST OF CROSSING GUARDS AND SWEEPERS SHALL BE INCIDENTAL TO THE CONTRACT.

#### GENERAL NOTES - RUNWAY 4/22

- BECAUSE OF THE CRITICAL LIMITATIONS WHICH THE CLOSURE OF RUNWAY 4/22 PLACES ON THE USERS OF THE AIRPORT, LIQUIDATED DAMAGES IN THE AMOUNT OF \$2,500 WILL BE DEDUCTED FROM THE MONIES OWED THE CONTRACTOR FOR EACH HALF HOUR OVER 6:00 AM UNTIL SPECIFIED WORK IS COMPLETED AND THE RUNWAY IS REOPENED TO AIRCRAFT TRAFFIC. DAMAGES MAY BE ASSESSED STARTING AT 6:01 AM ON ANY DAY THE RUNWAY IS NOT REOPENED.
- A MAXIMUM OF THREE (3) CLOSURES ON RUNWAY 4/22 WILL BE ALLOWED. RUNWAY CLOSURES, NIGHTTIME (10 PM - 6 AM). SEE SEQUENCE OF CONSTRUCTION GENERAL NOTES FOR DETAILS ON RUNWAY CLOSURES. FOR EVERY ADDITIONAL RUNWAY 4/22 CLOSURE REQUIRED BY THE CONTRACTOR LIQUIDATED DAMAGES IN THE AMOUNT OF \$2,500 WILL BE ASSESSED.

#### LEGEND

- PHASE 4B WORK AREA
- AIRCRAFT MOVEMENT AREA
- ALL PHASES LOW PROFILE BARRICADES FOR HAUL ROUTE
- AIR OPERATIONS AREA (A.O.A.)  
ACTIVE RUNWAYS 250' CENTERLINE TO A.O.A.  
ACTIVE TAXIWAYS 93' CENTERLINE TO A.O.A.
- TEMPORARY CLOSED RUNWAY MARKER (NONE THIS PHASE)
- TEMPORARY CLOSED TAXIWAY MARKER
- CONTRACTOR'S ACCESS/HAUL ROAD
- CROSSING GUARD AND TEMPORARY "STOP" AND "AIRCRAFT MOVEMENT AREA" SIGN

Path: K:\Kankakee\A021001660.dwg, Project: Widen Taxiway A4, Sequence of Construction - 4.dwg, Date: Monday, October 9, 2023 4:44:21 PM





CONSULTANTS

FINAL

WIDEN TAXIWAY FILLET AT RUNWAY 22 END AND RELOCATE TAXIWAY A4

SEPTEMBER 22, 2023

OWNER



MARK DATE DESCRIPTION

CMT PROJECT NO: 21001660.00
CAD DWG FILE:
DESIGNED BY: STL
DRAWN BY: JRO
CHECKED BY: STL
APPROVED BY: DKP
COPYRIGHT:

SHEET TITLE

SEQUENCE OF CONSTRUCTION GENERAL NOTES AND DETAILS - 1

PHASING NOTES (ALL PHASES)

- 1. THE INTENT OF THE PHASING PLANS IS TO MINIMIZE THE IMPACT OF CONSTRUCTION ON THE OPERATION OF THE AIRPORT. THE CONTRACTOR SHALL CONSTRUCT THE PROJECT IN CONSECUTIVE PHASES AS OUTLINED IN THE PLANS UNLESS OTHERWISE APPROVED BY THE RESIDENT ENGINEER AND AIRPORT EXECUTIVE DIRECTOR.
2. PRIOR TO REOPENING A CLOSED RUNWAY, THE ENTIRE (RSA) RUNWAY SAFETY AREA (250 FEET FROM CENTERLINE AND INCLUDING BEYOND THE END OF THE RUNWAY WITHIN AIRPORT PROPERTY) AND (TOFA) TAXIWAY OBJECT FREE AREA MUST MEET FAA CRITERIA. FAA CRITERIA REQUIRES THAT THERE BE NO OPEN EXCAVATIONS OR TRENCHES IN THE SAFETY AREA(S), THE MAXIMUM PAVEMENT DROP OFF BE 3 INCHES, AND ALL GRADES IN ANY DIRECTION BE LESS THAN 3 PERCENT. STEEL PLATES, TEMPORARY WEDGING OF BASE COURSE AND BITUMINOUS CONCRETE MAY BE REQUIRED TO MEET CRITERIA. ALL NECESSARY TEMPORARY MEASURES SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
3. THE CONTRACTOR SHALL SUBMIT A CONSTRUCTION SCHEDULE. STRICT ADHERENCE TO THE APPROVED SCHEDULE WILL BE ENFORCED TO AVOID CONFLICTS WITH OTHER CONSTRUCTION ACTIVITIES ON THE AIRPORT AND THE ADVERSE EFFECTS THEY COULD HAVE ON AIRPORT OPERATIONS.
4. THE CONTRACTOR SHALL COORDINATE CLOSELY WITH THE AIRPORT STAFF TO SCHEDULE THE RUNWAY/TAXIWAY CLOSURES. ITEMS SUCH AS THE EXTENDED WEATHER FORECAST, MATERIAL AVAILABILITY, EQUIPMENT DEPENDABILITY AND MANPOWER AVAILABILITY SHALL BE DISCUSSED PRIOR TO SCHEDULING THIS CRITICAL CLOSURE. THE AIRPORT EXECUTIVE DIRECTOR AND THE CONTRACTOR SHALL MUTUALLY AGREE ON THE EXACT DATES AND TIMES OF THE CLOSURE(S).
5. CONTRACTOR MUST MAINTAIN ACCESS TO ALL ACTIVE AND OPEN AREAS AT ALL TIMES. CONTRACTOR SHALL RELOCATE EQUIPMENT AT NO ADDITIONAL COST TO CONTRACTOR TO ALLOW AIRCRAFT TO PASS. CONTRACTOR SHALL COORDINATE CONSTRUCTION OPERATIONS AT ALL ACTIVE AND OPEN AREAS TO PROVIDE MINIMAL DISRUPTIONS TO AIRCRAFT MOVEMENT IN THAT AREA.
6. FAA AND AIRPORT ACCESS ROAD(S) SHALL NOT BE USED AS A HAUL ROAD BY THE CONTRACTOR WITHOUT PRIOR APPROVAL.
7. TO THE EXTENT POSSIBLE THE CONTRACTOR SHALL HAVE ALL EMPLOYEE PARKING OUTSIDE OF AIRPORT FENCE OR AS INDICATED AT THE LOCATION SHOWN.
8. THE AIRPORT RESERVES THE RIGHT TO MODIFY THE SEQUENCE OF CONSTRUCTION INCLUDING BUT NOT LIMITED TO PHASING, WORK AREAS, BARRICADE PLACEMENT, ACCESS AND HAUL ROUTES, AND CONTRACTOR MOVEMENTS AT ANY TIME DURING THE PROJECT WITH FAA, IDA AND ATCT APPROVAL.
9. ALL WORK IN THIS PHASE WILL REQUIRE FULL TIME CROSSING GUARDS IN RADIO CONTACT WITH UNICOM FREQUENCY AT LOCATIONS DESIGNATED. AIRCRAFT AND CONSTRUCTION EQUIPMENT WILL BE REQUIRED TO USE SECTIONS OF TAXIWAY A. THE CONTRACTOR WILL BE REQUIRED TO HAVE A MOTORIZED SWEEPER OPERATING FULL TIME TO REMOVE DEBRIS. COST OF CROSSING GUARDS AND SWEEPERS SHALL BE INCIDENTAL TO THE CONTRACT.

CONTRACTOR SHALL PLAN AND PERFORM HIS WORK SO AS NOT TO INTERFERE OR HINDER THE PROGRESS, WORK OR HAUL ROAD ACCESS OF OTHER CONTRACTORS (SEE STANDARD SPECIFICATIONS SECTION 50-05). THE PRIME CONTRACTOR WILL BE RESPONSIBLE TO COORDINATE CONSTRUCTION ACTIVITIES AND ACCESS BETWEEN ALL ON-SITE CONTRACTORS/SUBCONTRACTORS.

AIRSPACE ELEVATION POINTS

Table with 6 columns: POINT, NEAREST ACTIVE RUNWAY, LATITUDE, LONGITUDE, GROUND ELEVATION, TOP ELEVATION. Rows A through M.

DESIGN AIRCRAFT APPROACH CATEGORY: B AND D

AIRCRAFT DESIGN GROUP: III
RUNWAY 4/22 SAFETY AREA WIDTH: 250'
RUNWAY 16/34 SAFETY AREA WIDTH: 250'
TAXIWAY CENTERLINE TO OBJECT SEPARATION: 93'
TAXILANE CENTERLINE TO OBJECT SEPARATION: 86.5'

MAXIMUM ANTICIPATED HEIGHT OF EQUIPMENT - 25'

GENERAL NOTES

- 1. THE SUGGESTED SEQUENCE OF CONSTRUCTION SHOWN IS INTENDED TO ALLOW FOR THE ORDERLY CONSTRUCTION OF THE PROPOSED IMPROVEMENTS WHILE MAINTAINING AIRCRAFT ACCESS AT ALL TIMES. THE PHASING SHOWN IS A SUGGESTED SEQUENCE OF CONSTRUCTION ONLY. THIS SEQUENCE MAY BE MODIFIED HOWEVER, ALTERNATE STAGING PLANS MUST MAINTAIN AIRPORT OPERATIONS TO THE SATISFACTION OF THE AIRPORT MANAGER AND RESIDENT ENGINEER AND BE APPROVED BY THE DIVISION OF AERONAUTICS AND FEDERAL AVIATION ADMINISTRATION.
2. ALL OPERATIONS SHALL BE IN CONFORMANCE WITH AC 150/5370-2G (LATEST EDITION) OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION.
3. CONTRACTOR'S EQUIPMENT SHALL BE STORED IN THE EQUIPMENT AND MATERIAL STORAGE/STAGING AREA WHEN CONSTRUCTION IS NOT IN PROGRESS.
4. THE AIRPORT MANAGER IN CONSULTATION WITH THE RESIDENT ENGINEER SHALL HAVE FINAL SAY IN THE APPROVAL OF THE CONSTRUCTION OPERATING SEQUENCE AS IT RELATES TO PEDESTRIAN, VEHICULAR AND AIRCRAFT SAFETY.
5. ALL EXISTING PAVEMENTS, DRIVES OR ANY OTHER AREAS USED AS A HAUL ROAD OR STORAGE AREA BY THE CONTRACTOR SHALL BE RESTORED IN KIND TO THEIR PRE-CONSTRUCTION CONDITION OR TO THE SATISFACTION OF THE RESIDENT ENGINEER AND AIRPORT MANAGER. THE COST OF MAINTAINING, REPAIRING OR CONSTRUCTING THESE PAVEMENTS AND AREAS SHALL BE INCIDENTAL TO THE CONTRACT. EXISTING AREAS OUTSIDE THE PROJECT LIMITS WHICH ARE DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED BY HIM AT HIS EXPENSE TO THE SATISFACTION OF THE RESIDENT ENGINEER AND THE AIRPORT MANAGER.
6. THE CONTRACTOR SHALL KEEP ALL TRUCKS, EQUIPMENT AND MATERIALS OFF OF THE EXISTING TAXIWAYS, APRONS AND RUNWAYS OUTSIDE OF THE PROJECT LIMITS EXCEPT AS SHOWN OR WITH THE PRIOR PERMISSION OF THE RESIDENT ENGINEER.
7. WORK PERFORMED BY THE CONTRACTOR OUTSIDE OF DAYLIGHT HOURS SHALL BE DONE UNDER SUFFICIENT ARTIFICIAL LIGHTING TO ALLOW FOR PROPER CONSTRUCTION METHODS AND INSPECTIONS. LIGHT SHALL CONSIST OF MOVABLE POLE MOUNTED FLOODLIGHTS AND/OR SPOTLIGHTS OF SUFFICIENT NUMBER TO ILLUMINATE THE WORK AREA. VEHICLE HEADLIGHTS WILL BE ALLOWED ONLY IN ADDITION TO OTHER LIGHTS MENTIONED ABOVE. LIGHTING SHALL BE AS APPROVED BY THE RESIDENT ENGINEER AND SHALL NOT BE USED IF THEY AFFECT FLIGHT SAFETY. CONTRACTOR'S WORK HOURS SHALL BE IN ACCORDANCE WITH LOCAL ORDINANCES.
8. THE CONTRACTOR WILL BE REQUIRED TO HAVE A SWEEPER AVAILABLE FOR USE AT ALL TIMES. WHEN ACTIVE AIRFIELD PAVEMENTS ARE UTILIZED AS HAUL ROADS BY THE CONTRACTOR, MATERIAL TRACKED ON TO THE PAVEMENT SHALL BE CONTINUALLY REMOVED WITH SAID SWEEPER. THIS SWEEPING SHALL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
9. MATERIALS REMOVED FROM THE PROJECT WILL BE DISPOSED OF OFF AIRPORT PROPERTY, UNLESS NOTED OTHERWISE.
10. PAYMENT FOR TRAFFIC CONTROL INCLUDING, BUT NOT LIMITED TO BARRICADES, SIGNING, RUNWAY CLOSED MARKERS, AIR OPERATIONS AREA (A.O.A.) LATHE AND RIBBON, ETC. SHALL NOT BE PAID SEPARATELY, BUT SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT. BARRICADES WITH TWO ORANGE FLAGS (20" x 20") ON EACH BARRICADE SHALL BE PLACED AT THE LOCATIONS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER. BARRICADES SHALL BE WEIGHTED TO PREVENT BLOWING OVER. BARRICADES SHALL HAVE A STEADY BURN OR FLASHING RED LIGHT. BARRICADE INSTALLATION WILL BE REQUIRED PRIOR TO ACCESS TO THE A.O.A. BY CONTRACTOR'S WORKERS, EQUIPMENT OR MATERIAL. SIGNS SHALL BE PLACED AT EACH TAXIWAY/RUNWAY CLOSURE LOCATION AND SHALL BE ATTACHED TO THE BARRICADES. EACH BARRICADE LOCATION SHALL CONSIST OF ONE "DO NOT ENTER" SIGN AND ONE "AIRCRAFT MOVEMENT AREA" SIGN. SIGNS SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT. THE CONTRACTOR SHALL SUPPLY AND USE AS DIRECTED BY THE AIRPORT, REFLECTIVE LOW PROFILE TYPE BARRICADES. ALL BARRICADES SHALL BE PLACED OUTSIDE OF ACTIVE SAFETY AREAS.
11. THE CONTRACTOR SHALL CONTACT THE AIRPORT MANAGER THROUGH THE RESIDENT ENGINEER FOURTEEN (14) WORKING DAYS IN ADVANCE OF THE START OF CONSTRUCTION SO THAT THE APPROPRIATE NOTAMS MAY BE ISSUED.
12. THE CONTRACTOR SHALL BE RESPONSIBLE FOR KEEPING ALL CONSTRUCTION ACCESS GATES CLOSED DURING NON WORKING HOURS. THE CONTRACTOR SHALL PROVIDE A SIGN AT THE ACCESS GATE SAYING "AUTHORIZED PERSONNEL ONLY". THE CONTRACTOR SHALL CLOSE AND LOCK THE ACCESS GATE UPON LEAVING THE SITE. THROUGHOUT THE DURATION OF THE CONTRACT, ANY DAMAGES TO THE ACCESS ROAD, ACCESS GATE OR FENCING ADJACENT TO THE PROJECT SHALL BE REPAIRED BY THE CONTRACTOR TO THE SATISFACTION OF THE RESIDENT ENGINEER. ALL COST RELATING TO CONTRACTOR'S ACCESS AND SECURITY SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
13. CONTRACTOR WILL BE REQUIRED TO PUT AIRPORT FLAGS AND HAVE BEACON LIGHTS ON ALL EQUIPMENT AT ALL TIMES DURING CONSTRUCTION. SEE FLAG DETAIL.
14. IN THE CASE OF AN EMERGENCY, CONTRACTOR SHALL NOTIFY AIRPORT MANAGER AND THE RESIDENT ENGINEER IMMEDIATELY.
15. DURING ADVERSE WEATHER, THE CONTRACTOR SHALL MAKE PROVISIONS FOR ACCESS TO THE WORK AT NO ADDITIONAL COST TO THE CONTRACT. NO EXTENSION OF CONTRACT TIME WILL BE CONSIDERED FOR DELAYS DUE TO LACK OF ADEQUATE ACCESS TO THE WORK.
16. THE TALLEST PIECE OF CONSTRUCTION EQUIPMENT IS ANTICIPATED TO BE AN ASPHALT/STONE TRUCK WHICH HAS A MAXIMUM HEIGHT OF 25 FEET IN A DUMP POSITION.
17. IF RUNWAY NUMERALS ARE PRESENT DURING CONSTRUCTION THEN CONTRACTOR SHALL PLACE CLOSED RUNWAY MARKER OVER NUMERALS AS DETAILED, OTHERWISE PLACE RUNWAY CLOSED MARKER IN TURF AT ENDS OF RUNWAY AS DETAILED.
18. THE AIRPORT WILL BE IN OPERATION DURING THE CONSTRUCTION OF THIS PROJECT. COORDINATION OF WORK WITH THE AIRPORT IS MANDATORY SO AS TO MINIMIZE IMPACTS ON AIRPORT OPERATIONS.
19. APPROXIMATE LOCATION OF HAUL ROUTES ON THE AIRPORT SITE ARE SHOWN ON THE GENERAL PROJECT LAYOUT AND THE PHASING PLANS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE OFF-SITE HAUL ROUTES (STATE HIGHWAYS, COUNTY ROADS OR CITY STREETS) WITH THE APPROPRIATE OWNER WHO HAS JURISDICTION OVER THE AFFECTED ROUTE. ON-SITE ROADS USED AS HAUL ROUTES SHALL BE MAINTAINED BY THE CONTRACTOR AND SHALL BE RESTORED AT THE CONTRACTOR'S EXPENSE TO THEIR ORIGINAL CONDITION UPON COMPLETION OF BEING USED AS A HAUL ROUTE. THE BEFORE AND AFTER CONDITION OF ON-SITE HAUL ROUTES SHALL BE JOINTLY INSPECTED AND DETERMINED BY THE CONTRACTOR AND THE ENGINEER. FENCING, DRAINAGE, GRADING AND OTHER MISCELLANEOUS CONSTRUCTION REQUIRED TO CONSTRUCT TEMPORARY HAUL ROUTES OR ACCESS POINTS ON THE AIRPORT WILL BE THE CONTRACTOR'S TOTAL RESPONSIBILITY AND SHALL BE APPROVED BY THE ENGINEER PRIOR TO THE WORK. ALL ON-SITE ACCESS ROADS TO AIRPORT FACILITIES SHALL REMAIN OPEN AND MAINTAINED AT ALL TIMES.
20. MOBILIZATION/EQUIPMENT STORAGE AREA WILL BE MADE AVAILABLE FOR CONTRACTOR'S MOBILIZATION AND STORAGE AS SHOWN ON THE PLANS. THIS AREA SHALL BE RESTORED TO THE ORIGINAL CONDITION UPON COMPLETION OF THE PROJECT AT THE CONTRACTOR'S EXPENSE.
21. LOCATION OF KNOWN EXISTING AIRPORT UNDERGROUND CABLES ARE SHOWN ON THE PLANS AND MUST BE VERIFIED BY THE CONTRACTOR. REPAIR OF DAMAGED CABLE MUST BE STARTED IMMEDIATELY AND CONTINUED UNTIL COMPLETED. ALL SUCH REPAIRS SHALL BE IN ACCORDANCE WITH THE SPECIFICATIONS, OR AS DIRECTED BY THE OWNER OF THE CABLE OR FACILITY, AND SHALL BE AT THE CONTRACTOR'S EXPENSE. IF FAA CABLES ARE DAMAGED, REPAIRS SHALL BE DONE FROM PREVIOUS EXISTING TERMINATION POINT TO NEXT EXISTING TERMINATION POINT IN ACCORDANCE WITH FAA REQUIREMENTS AND IN THE PRESENCE OF A FAA REPRESENTATIVE. THE OWNER MAY ELECT TO HAVE THE REPAIR PERFORMED BY OTHERS IN WHICH CASE THE CONTRACTOR SHALL BE RESPONSIBLE FOR PAYING THE INCURRED COSTS OF REPAIRS.
22. COORDINATION MEETINGS - THE CONTRACTOR SHALL CONDUCT WEEKLY COORDINATION MEETINGS TO DISCUSS WORK AREAS AND SCHEDULING, ETC. WITH THE RESIDENT ENGINEER, AIRPORT OPERATIONS, FAA, AND OTHER APPROPRIATE OFFICIALS. MINUTES FROM THE WEEKLY MEETINGS SHALL BE PREPARED BY THE CONTRACTOR, FURNISHED TO ALL ATTENDEES PRIOR TO THE SUBSEQUENT MEETING, AND KEPT ON FILE AT THE FIELD OFFICE. THE COORDINATION MEETING COSTS SHALL BE CONSIDERED INCIDENTAL TO THE PROJECT.

CONTRACTOR CROSSING RUNWAY/TAXIWAY/TAXILANE/APRON AIR OPERATIONS AREA (A.O.A.)

- 1. ANYTIME THE CONTRACTOR IS REQUIRED TO UTILIZE OR CROSS ACTIVE AIRFIELD PAVEMENTS FOR ACCESS TO AND FROM THE WORK ZONE, A FULL TIME CROSSING GUARD IN RADIO CONTACT WITH AIR TRAFFIC SHALL BE FURNISHED BY THE CONTRACTOR FOR MOVEMENTS OF VEHICLES OR EQUIPMENT TO AND FROM THE WORK ZONE. THE RADIO OPERATOR SHALL BE FAMILIAR WITH AIRPORT GROUND CONTROL PROCEDURES AND DEMONSTRATE KNOWLEDGE OF SAME TO THE AIRPORT. THE AIRPORT RESERVES THE RIGHT TO APPROVE THE CROSSING GUARDS. THE CONTRACTOR SHALL PROVIDE THEIR OWN RADIOS. THIS COST SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PAYMENT OF MUNICIPAL FINES (\$500 PER OCCURRENCE) DUE TO AIRFIELD INCURSIONS BY HIS EMPLOYEES, SUBCONTRACTORS, SUPPLIERS, CONSULTANTS AND/OR AGENTS.
2. ANY PAVEMENT DAMAGED BY CONTRACTOR'S OPERATIONS SHALL BE REPAIRED IMMEDIATELY BY HIM TO THE SATISFACTION OF THE RESIDENT ENGINEER AND AIRPORT MANAGER AT NO ADDITIONAL COST TO THE OWNER. PAVEMENT SHALL BE CONTINUALLY SWEEPED TO PROVIDE DEBRIS FREE SURFACE DURING ALL HAUL ROAD OPERATIONS. THIS COST SHALL NOT BE PAID SEPARATELY BUT SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
3. WORK WITHIN THE A.O.A. SHALL BE EXPEDITED. ANY DROP OFF SHALL BE ADEQUATELY LIGHTED, SIGNED AND BARRICADED. NO MATERIAL SHALL BE STOCKPILED WITHIN THE A.O.A. SHOULD IT BE NECESSARY FOR THE CONTRACTOR TO TEMPORARILY RELOCATE MEN AND EQUIPMENT TO ALLOW AIRCRAFT TO PASS, THEY SHALL DO SO AT NO EXTRA COST TO THE PROJECT. THE CONTRACTOR SHALL NOTIFY THE RESIDENT ENGINEER AND AIRPORT MANAGER TEN (10) WORKING DAYS IN ADVANCE OF ANY PLANNED CONSTRUCTION WITHIN THESE LIMITS.

LIMITATIONS ON CONSTRUCTION WITHIN RUNWAY'S AIRCRAFT OPERATIONS AREA (AOA) AND TAXIWAY/TAXILANE OBJECT FREE AREA (TOFA)

RUNWAYS:

THE CONTRACTOR SHALL NOTIFY THE RESIDENT ENGINEER AND AIRPORT MANAGER TEN (14) WORKING DAYS IN ADVANCE OF ANY PLANNED CONSTRUCTION WITHIN THESE LIMITS. WORK SHALL BE EXPEDITED IN THESE AREAS AND AT THE END OF EACH WORKING DAY THESE AREAS SHALL BE SMOOTHLY GRADED TO ALLOW THE RUNWAY TO BE REOPENED. AT LEAST ONE OF THE RUNWAYS SHALL REMAIN IN OPERATION AT ALL TIMES. IF NECESSARY STEEL PLATES SHALL BE FURNISHED AND INSTALLED BY THE CONTRACTOR TO COVER ANY OPEN TRENCHES OR EXCAVATION WITHIN THE RSA IF DURING RUNWAY CLOSURE AN EMERGENCY IS DECLARED, THE CONTRACTOR SHALL IMMEDIATELY CLEAR THE RUNWAY OF ALL VEHICLES, MEN AND EQUIPMENT. REFERENCE TABLE ON PREVIOUS SHEET FOR SAFETY AREA WIDTHS.

TAXIWAYS / TAXILANES:

ANY WORK WITHIN TAXIWAY / TAXILANE OBJECT FREE AREA (TOFA) WILL REQUIRE A TAXIWAY / TAXILANE CLOSURE. WORK WITHIN THE TOFA SHALL BE EXPEDITED. ANY DROP OFF SHALL BE ADEQUATELY LIGHTED, SIGNED AND BARRICADED. NO MATERIAL SHALL BE STOCKPILED WITHIN THE TOFA. SHOULD IT BE NECESSARY FOR THE CONTRACTOR TO TEMPORARILY RELOCATE EQUIPMENT TO ALLOW AIRCRAFT TO PASS, THEY SHALL DO SO AT NO EXTRA COST TO THE PROJECT. THE CONTRACTOR SHALL NOTIFY THE RESIDENT ENGINEER AND AIRPORT MANAGER FIVE (5) WORKING DAYS IN ADVANCE OF ANY PLANNED CONSTRUCTION WITHIN THESE LIMITS. REFERENCE TABLE ON PREVIOUS SHEET FOR OBJECT FREE AREA WIDTHS. NO DROP-OFFS OR OPEN EXCAVATIONS WILL BE ALLOWED WITHIN THE TAXIWAY / TAXILANE SAFETY AREAS OF OPEN TAXIWAYS / TAXILANES.















CONSULTANTS

FINAL

WIDEN TAXIWAY FILLET AT RUNWAY 22 END AND RELOCATE TAXIWAY A4

SEPTEMBER 22, 2023

OWNER





MARK DATE DESCRIPTION

CMT PROJECT NO: 21001660.00  
CAD DWG FILE:  
DESIGNED BY: STL  
DRAWN BY: JRO  
CHECKED BY: STL  
APPROVED BY: DKP  
COPYRIGHT:

SHEET TITLE  
**EXISTING CONDITIONS/  
PROPOSED  
REMOVALS - 2**

EXISTING CONDITIONS LEGEND

- 626- EXISTING CONTOUR
- EXISTING CONDUIT/DUCT BANK
- ST- EXISTING STORM SEWER
- UD- EXISTING UNDERDRAIN
- W- EXISTING WATERMAIN
- EXISTING STORM INLET
- EXISTING SLOPE BOX
- EXISTING WATER VALVE
- EXISTING UNDERDRAIN CLEANOUT STRUCTURE
- BASE-MOUNTED TAXIWAY EDGE LIGHT
- STAKE-MOUNTED TAXIWAY EDGE LIGHT
- AIRFIELD GUIDANCE SIGN
- EXISTING SPLICE CAN
- BASE-MOUNTED RUNWAY LIGHT
- EXISTING ELECTRICAL MANHOLE
- BURIED CONCRETE ENCASED DUCT BANK
- CKT#1- EXISTING RUNWAY 4/22 CIRCUIT
- CKT#3- EXISTING TAXIWAY A2, A3, A4 AND A5 CIRCUIT
- CKT#4- EXISTING TAXIWAY B/BB CIRCUIT
- CKT#7- EXISTING ELECTRIC CIRCUIT 7
- CKT#8- EXISTING WINDCONE/RUNWAY 22 PAPI
- CKT#10- EXISTING RUNWAY 22 REIL
- CKT#17- EXISTING RUNWAY 16 PAPI
- X ITEM TO BE REMOVED
- PROPOSED PAVEMENT REMOVALS



NOTES

1. THE EXISTING PAVEMENT TO BE REMOVED SHALL BE SAWED FULL DEPTH AROUND PERIMETER OF THE REMOVAL LIMITS. COST OF SAWCUTTING AND DISPOSAL OF PAVEMENT SHALL BE CONSIDERED INCIDENTAL TO THE ITEM.
2. CONTRACTOR TO TAKE MEASURES TO PROTECT ALL UNDERGROUND UTILITIES INCLUDING, BUT NOT LIMITED TO, NEW AND EXISTING SHALLOW STORM SEWER PIPE FROM DAMAGE DUE TO CONSTRUCTION EQUIPMENT.
3. ITEMS REMOVED DUE TO PROPOSED PAVEMENT EXCAVATION WILL NOT BE PAID FOR SEPARATELY BUT WILL BE CONSIDERED INCIDENTAL TO UNCLASSIFIED EXCAVATION UNLESS OTHERWISE NOTED ON THE PLANS.
4. AT ALL TIMES THE CONTRACTOR SHALL PERFORM ALL MAINTENANCE WORK NECESSARY TO KEEP EACH PAVEMENT SECTION LAYER IN A SATISFACTORY CONDITION.
5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL DAMAGE DONE BY HIS HAULING AND CONSTRUCTION EQUIPMENT. ANY WORK NECESSARY TO CORRECT DAMAGED WORK AND EXISTING PAVEMENT SHALL BE PERFORMED BY THE CONTRACTOR AND AT THE EXPENSE OF THE CONTRACTOR.
6. ALL EDGE LIGHTS AND SIGNS THAT ARE TO BE REMOVED SHALL BE SALVAGED AND RETURNED TO THE AIRPORT. IF THE AIRPORT ELECTS NOT TO SALVAGE ANY EQUIPMENT, CONTRACTOR SHALL DISPOSE OF ALL EQUIPMENT OFF AIRPORT PROPERTY AT NO ADDITIONAL COST TO THE CONTRACT. LIGHT BASES AND SIGN FOUNDATIONS SHALL BE DISPOSED OF OFF AIRPORT PROPERTY.
7. ALL EXISTING CONDUCTORS BETWEEN LIGHTS AND SIGNS ARE TO BE REMOVED, UNLESS OTHERWISE NOTED. ABANDON CONDUIT IN PLACE IF IT IS NOT IN CONFLICT WITH NEW CONSTRUCTION.
8. ALL LIGHT REMOVALS SHALL INCLUDE COMPLETE REMOVAL OF LIGHT FIXTURES, TRANSFORMERS, AND BASE CANS / STAKE MOUNT UNLESS OTHERWISE NOTED.
9. ALL SIGN REMOVALS SHALL INCLUDE COMPLETE REMOVAL OF SIGNS, ISOLATION TRANSFORMERS AND FOUNDATION, UNLESS OTHERWISE NOTED.
10. ALL BASE-MOUNTED RUNWAY EDGE LIGHTS TO BE REMOVED SHALL BE DONE CAREFULLY TO AVOID DAMAGE, PRESERVED AND RELOCATED DURING NEW CONSTRUCTION.
11. EXISTING FAA POWER AND COMMUNICATIONS CABLES TO BE REMOVED SHALL BE COORDINATED WITH FAA. CONTRACTOR SHALL REMOVE ALL CABLES AND ASSOCIATED GUARD WIRE AND GROUND RODS. COST OF REMOVALS SHALL BE INCIDENTAL TO NEW CABLES.

















CONSULTANTS

FINAL

WIDEN TAXIWAY FILLET AT  
RUNWAY 22 END AND  
RELOCATE TAXIWAY A4

SEPTEMBER 22, 2023

OWNER



MARK DATE DESCRIPTION

CMT PROJECT NO: 21001660.00

CAD DWG FILE:

DESIGNED BY: STL

DRAWN BY: JRO





CHECKED BY: STL

APPROVED BY: DKP

COPYRIGHT:

SHEET TITLE

**DRAINAGE  
DETAILS - 2**





CONSULTANTS

FINAL

WIDEN TAXIWAY FILLET AT  
RUNWAY 22 END AND  
RELOCATE TAXIWAY A4

SEPTEMBER 22, 2023

OWNER



MARK | DATE | DESCRIPTION

CMT PROJECT NO: 21001660.00  
CAD DWG FILE:  
DESIGNED BY: STL  
DRAWN BY: JRO  
CHECKED BY: STL  
APPROVED BY: DKP  
COPYRIGHT:

SHEET TITLE

**DRAINAGE  
DETAILS - 3**

**SECTION PARALLEL TO PIPE**  
(Without curb at top-left)

**SECTION PERPENDICULAR TO PIPE**  
(With conical top-left)

**FLAT SLAB TOP JOINT CONFIGURATIONS**  
(Shown at access hole)

**BASE SLAB JOINT CONFIGURATIONS**

**SHEAR KEY GEOMETRY**  
(Reinforcement not shown for clarity)

**GENERAL NOTES**  
Pipe holes shall be formed to facilitate proper placement of hole reinforcement.  
The manufacturer shall ensure that all precast manhole sections are additionally reinforced where required to resist damage from handling, shipping and installation stresses.  
Lifting holes shall be located in the sections as per the manufacturer's recommendations.  
See Standard 602701 for details of manhole steps.  
All dimensions are in inches (millimeters) unless otherwise noted.

**GEOMETRIC LIMITS FOR PIPE PENETRATION HOLES**  
Note 1: A minimum of 9 (230) of monofibek reinforced concrete shall be maintained above pipe penetration holes > 32 (810).  
Note 2: A minimum 12 (300) inside arc length of reinforced concrete shall be maintained between pipe penetration holes < 24 (600).  
Note 3: A maximum of 60 percent of the inside perimeter of the reinforced concrete manhole walls may be removed.  
Note 4: Horizontal joints that intersect pipe penetration holes > 15 (380) shall have one joint splice for every location around the perimeter of the joint where the inside arc length between pipe penetration holes < 24 (600). See joint splice detail.  
Note 5: The recommended pipe penetration hole is equal to the O.D. of the pipe plus 4 (100).  
Note 6: Only pipe penetration holes > 15 (380) are allowed in riser sections.

DATE	REVISIONS
1-1-21	Revised Note 1, Note 2 and Writing note general note.
3-1-19	Moved wall reinforcement from inside face to middle.

**PRECAST MANHOLE TYPE A  
6' (1.83 m) DIAMETER**  
(Sheet 1 of 3)  
STANDARD 602406-11

Illinois Department of Transportation  
PASSED: [Signature] 2021  
ENGINEER OF PUBLIC WORKS PROCEDURES  
APPROVED: [Signature] 2021  
ENGINEER OF PUBLIC WORKS PROCEDURES

**PLAN - FLAT SLAB TOP**  
(Showing layout of bottom reinforcement bars and c bars)

**PLAN - FLAT SLAB TOP**  
(Showing layout of welded wire reinforcement and c bars)

**GENERAL NOTES**  
\* #5 (#16) bars for risers < 10 ft (3.05 m) tall or #6 (#19) bars for risers > 10 ft (3.05 m) tall bottom. Bundle first bar with closest WWR bar to the opening and place second bar > 3 (75) away.

Location	Riser Height (RH)	WWR (each direction)	Rebar (each direction except as noted)	Bar Size
Top Mat	All	0.11 sq. ft./ft. (233 sq. mm/m)	0.11 sq. ft./ft. (233 sq. mm/m)	#3 or #4 (#10) (#13)
Bottom Mat	RH < 10 ft (3.05 m)	** 0.62 sq. ft./ft. (1312 sq. mm/m)	6	#5 (#16)
	RH > 10 ft (3.05 m)	** 0.88 sq. ft./ft. (1863 sq. mm/m)	6	#6 (#19)

\*\* Only one layer of WWR permitted to avoid congestion.

Location	Orientation	WWR or Rebar
4 ft (1.22 m) Ø Riser	Circumferential	0.12 sq. ft./ft. (254 sq. mm/m) (150)
	Vertical	0.045 sq. ft./ft. (95 sq. mm/m) (200)
6 ft (1.83 m) Ø Barrel	Circumferential	0.18 sq. ft./ft. (381 sq. mm/m) (150)
	Vertical	0.045 sq. ft./ft. (95 sq. mm/m) (200)

Location	Riser Height (RH) / Total Height (TH)	WWR or Rebar (each direction)
Top Mat	RH < 10 ft (3.05 m) / 6 TH < 20 ft (6.10 m)	0.26 sq. ft./ft. (559 sq. mm/m) (150)
Bottom Mat	RH > 10 ft (3.05 m) / or TH > 20 ft (6.10 m)	0.40 sq. ft./ft. (847 sq. mm/m) (150)

**PRECAST MANHOLE TYPE A  
6' (1.83 m) DIAMETER**  
(Sheet 2 of 3)  
STANDARD 602406-11

Illinois Department of Transportation  
PASSED: [Signature] 2021  
ENGINEER OF PUBLIC WORKS PROCEDURES  
APPROVED: [Signature] 2021  
ENGINEER OF PUBLIC WORKS PROCEDURES

**JOINT SPICE**

**CONNECTION ANGLE**

**TIE PLATE**

**FLAT SLAB TOP REINFORCEMENT**

Location	Riser Height (RH)	WWR (each direction)	Rebar (each direction except as noted)	Bar Size
Top Mat	All	0.11 sq. ft./ft. (233 sq. mm/m)	0.11 sq. ft./ft. (233 sq. mm/m)	#3 or #4 (#10) (#13)
Bottom Mat	RH < 10 ft (3.05 m)	** 0.62 sq. ft./ft. (1312 sq. mm/m)	6	#5 (#16)
	RH > 10 ft (3.05 m)	** 0.88 sq. ft./ft. (1863 sq. mm/m)	6	#6 (#19)

\*\* Only one layer of WWR permitted to avoid congestion.

**WALL REINFORCEMENT**

Location	Orientation	WWR or Rebar
4 ft (1.22 m) Ø Riser	Circumferential	0.12 sq. ft./ft. (254 sq. mm/m) (150)
	Vertical	0.045 sq. ft./ft. (95 sq. mm/m) (200)
6 ft (1.83 m) Ø Barrel	Circumferential	0.18 sq. ft./ft. (381 sq. mm/m) (150)
	Vertical	0.045 sq. ft./ft. (95 sq. mm/m) (200)

**BASE SLAB REINFORCEMENT**

Location	Riser Height (RH) / Total Height (TH)	WWR or Rebar (each direction)
Top Mat	RH < 10 ft (3.05 m) / 6 TH < 20 ft (6.10 m)	0.26 sq. ft./ft. (559 sq. mm/m) (150)
Bottom Mat	RH > 10 ft (3.05 m) / or TH > 20 ft (6.10 m)	0.40 sq. ft./ft. (847 sq. mm/m) (150)

**PRECAST MANHOLE TYPE A  
6' (1.83 m) DIAMETER**  
(Sheet 3 of 3)  
STANDARD 602406-11

Illinois Department of Transportation  
PASSED: [Signature] 2021  
ENGINEER OF PUBLIC WORKS PROCEDURES  
APPROVED: [Signature] 2021  
ENGINEER OF PUBLIC WORKS PROCEDURES



















CONSULTANTS

FINAL

WIDEN TAXIWAY FILLET AT  
RUNWAY 22 END AND  
RELOCATE TAXIWAY A4

SEPTEMBER 22, 2023

OWNER



MARK	DATE	DESCRIPTION

CMT PROJECT NO: 21001660.00

CAD DWG FILE:

DESIGNED BY: STL

DRAWN BY: JRO


CHECKED BY: STL

APPROVED BY: DKP

COPYRIGHT:

SHEET TITLE

**ELECTRICAL  
DETAILS - 2**



**NEW AIRFIELD GUIDANCE SIGN, L-858 (LED) DETAIL**

NOT TO SCALE

**SIGNAGE NOTES**

- ALL SIGNS ARE 2-SIDED LED SIGNS SIZE 2, CLASS 2 AS MANUFACTURED BY ADB OR APPROVED EQUAL. SIGNS SHALL BE CAPABLE OF BEING CONNECTED TO A 3-STEP OR 5-STEP REGULATOR.
- TRANSFORMER WATTAGE AS RECOMMENDED BY MANUFACTURER FOR LED SIGNS.
- LIGHTED SIGNS SHALL BE BASE MOUNTED ONLY.
- THE NUMBER OF MODULES PER SIGN SHALL BE AS RECOMMENDED BY THE MANUFACTURER.
- CONTRACTOR SHALL SUBMIT DETAILED SHOP DRAWINGS INCLUDING SIGN, COLOR, SIZE AND PROPOSED LEGEND, IN ENOUGH DETAIL TO DETERMINE PROPOSED SPACING AND OTHER INFORMATION REQUIRED BY THE SPECIAL PROVISIONS.
- CONTRACTOR TO VERIFY PROPOSED SIGN LOCATIONS AND ORIENTATIONS WITH RESIDENT ENGINEER PRIOR TO INSTALLATION.


AIRFIELD SIGNAGE SCHEDULE						
SIGN NUMBER	NEW SIGN FACE	NEW SIGN LEGEND	NEW SIGN TYPE	NEW SIGN LOCATION	NOTES	STATION AND OFFSET
S1	N S		2,3 2,1	TAXIWAY A4	NEW 6 CHARACTER SIGN	TAXIWAY A4 -STA. 2+57.00 OFF. 60.00 RT
S2	E W		3 0	RUNWAY 4/22	NEW 3 CHARACTER SIGN	RUNWAY 4-22 -STA. 115+07.98 OFF. 86.38 RT
S3	E W		0 3	RUNWAY 4/22	NEW 3 CHARACTER SIGN	RUNWAY 4-22 -STA. 113+22.54 OFF. 86.41 RT
S4	N S		2,0 2,1	TAXIWAY A	NEW 3 CHARACTER SIGN	TAXIWAY A -STA. 160+57.76 OFF. 68.10 LT

**NEW SIGN TYPE LEGEND**

- 0 — BLANK PANEL - BLACK
- 1 — RUNWAY/TAXIWAY HOLDLINE - WHITE LEGEND ON RED BACKGROUND
- 2 — LOCATION SIGN - YELLOW LEGEND ON BLACK BACKGROUND
- 3 — DIRECTION/INFORMATION SIGN - BLACK LEGEND ON YELLOW BACKGROUND

**NOTE**

- GUIDANCE SIGN PANEL SIZE WILL BE BASED ON THE MANUFACTURER'S RECOMMENDATION.



**COMPLETED STAKE MOUNTED  
LIGHT, BASE MOUNTED LIGHT AND  
SIGN REMOVAL**

N.T.S.


NOTE: COST OF BACKFILL AND RESTORATION SHALL BE INCIDENTAL TO THE CONTRACT.

**LIGHTING NOTES**

- TRANSFORMER WATTAGE AS RECOMMENDED BY MANUFACTURER FOR EACH LAMP TYPE.
- NON-LED FIXTURES SHALL UTILIZE QUARTZ LAMPS.
- THE LIGHT FIXTURE SHALL BE BONDED TO THE LIGHT BASE INTERNAL GROUND LUG VIA A #6 AWG STRANDED COPPER WIRE RATED FOR 600 VOLTS WITH GREEN XHHW INSULATION. THE GROUND WIRE LENGTH SHALL BE SUFFICIENT TO ALLOW THE REMOVAL OF THE LIGHT FIXTURE FROM THE LIGHT BASE FOR ROUTINE MAINTENANCE. SEE THE LIGHT FIXTURE MANUFACTURER'S INSTRUCTIONS FOR PROPER METHODS OF ATTACHING THIS BONDING WIRE.
- LED LIGHT FIXTURES SHALL AS INDICATED ON THE PLANS AND SPECIFICATIONS.
- AFTER INSTALLATION OF CABLE IN UNIT DUCT, SEAL END OF CONDUIT TO MAKE WATERTIGHT.
- PRECAST BASE MAY BE USED.

**GENERAL NOTES**


- TRANSFORMER HOLDER MAY BE ANY COMMERCIALY AVAILABLE BRICK.
- BREAKING GROOVE COUPLINGS SHALL NOT BE OVER 1" ABOVE GROUND LINE.
- ISOLATION TRANSFORMERS SHALL HAVE A FACTORY INSTALLED PLUG (TYPE 1, CLASS A, STYLE 2) AND RECEPTACLE (TYPE 1, CLASS A, STYLE 9). A TYPE 1, CLASS B, STYLE 3 PLUG AND TYPE 1, CLASS B, STYLE 10 RECEPTACLE SHALL BE INSTALLED ON THE 1/C, No. 8, 5000 V., L-824 TYPE C CABLES FOR CONNECTION TO EACH TRANSFORMER.
- TO FURTHER REDUCE THE POSSIBILITY OF WATER/MOISTURE ENTRANCE INTO THE CONNECTOR BETWEEN THE CABLE AND THE FIELD ATTACHED CONNECTOR, IT IS REQUIRED THAT A HEAT SHRINKABLE TUBING WITH INTERNAL ADHESIVE BE APPLIED OVER THE ENTIRE CABLE CONNECTOR.
- AT THE CONTRACTOR'S OPTION, IN LIEU OF TAPE AND HEAT SHRINKABLE TUBING, A SELF-SEALING STYLE CONNECTOR L-823 "COMPLETE KITS" OR FAA APPROVED EQUAL MAY BE USED.
- LAMP FOR FIXTURES SHALL BE AS SPECIFIED IN THE SPECIAL PROVISIONS. ISOLATION TRANSFORMERS SHALL BE SIZED PER THE FIXTURE MANUFACTURER, 6.6 AMP.
- THE CONCRETE BASE FOR BASE MOUNTED LIGHTS AND SIGNS SHALL BE TROWEL FINISHED WITH A 45° BEVELED EDGE AND SLOPED TO DRAIN.




**GRADING AIRFIELD SIGN DETAILS**

**NOTES:**

- SLOPES SHOWN ARE FROM FAA STANDARDS AND MAY NOT REFLECT THE ACTUAL GRADES/SLOPES IN THE FIELD
- IT IS ESTIMATED THAT 2 C.Y. OF EMBANKMENT MAY BE REQUIRED TO CONSTRUCT THE SIGN BASE FOUNDATIONS. ALL MATERIAL USED TO CONSTRUCT THE EMBANKMENT SHALL BE APPROVED BY THE RESIDENT ENGINEER. ALL OFFSITE MATERIAL USED TO CONSTRUCT THE EMBANKMENT SHALL BE CATEGORIZED AS CLEAN CONSTRUCTION OR DEMOLITION DEBRIS IN ACCORDANCE WITH SECTION 905-1.2 OF THE SPECIAL PROVISIONS. COSTS TO CONSTRUCT THE EMBANKMENT SHALL BE INCIDENTAL TO THE SIGN PAY ITEM. ESTIMATED QUANTITY OF EMBANKMENT IS FOR INFORMATION ONLY AND NO ADDITIONAL COMPENSATION SHALL BE MADE FOR ANY ADDITIONAL EMBANKMENT NEEDED.
- ACTUAL LOCATION OF THE SIGN WITHIN THE TAXIWAY SAFETY AREA WILL VARY DUE TO PAVEMENT WIDTHS AND VARIANCES IN SIGN FOUNDATION LENGTHS.
- DIMENSIONS:  
RUNWAY 4/22 = 250'  
RUNWAY 16/34 = 75'  
ALL TAXIWAYS = 66.5'




**TYPICAL LANDSCAPING FOR NEW SIGN**



**CONCRETE ELECTRICAL HANDHOLE DETAIL - IDOT STANDARD NO. 814001**

**NOTES:**

- CONDUIT ENTRANCES AND NUMBER OF CONDUITS SHALL BE AS SHOWN ON SITE PLAN VIEW.
- COVER SHALL BE STAMPED "ELECTRICAL".
- FRENCH DRAIN AGGREGATE SHALL BE CA-18 (COST INCIDENTAL TO HANDHOLE).
- COVER SHALL BE HINGED WITH A SAFETY BAR.



**NEW BASE MOUNTED MEDIUM INTENSITY TAXIWAY LIGHT**

NOT TO SCALE

Path: K:\kankakee\21001660.00\_Relect\21001660.00\_WidenTwyFiles\Draws\Sheets\electrical\details - 2.dwg  
Date: Monday, October 9, 2023 4:46:50 PM









**GENERAL EARTHWORK NOTES:**

1. ALL EARTHWORK QUANTITIES ARE CALCULATED BASED ON THE MATERIAL IN ITS INITIAL OR FINAL POSITION AS SHOWN IN THE PLANS AND QUANTIFIED BY THE METHOD OF AVERAGE END AREAS.
2. AREAS OF UNSUITABLE MATERIAL (UNCLASSIFIED EXCAVATION) SHALL BE AS DESIGNATED BY THE ENGINEER. THE QUANTITY OF UNSUITABLE MATERIAL SHALL NOT BE USED AS EMBANKMENT FILL MATERIAL, UNLESS AUTHORIZED BY THE ENGINEER.
3. PAYMENT FOR UNCLASSIFIED EXCAVATION IS THE SUM OF TOPSOIL STRIPPING AND UNCLASSIFIED EXCAVATION AREAS. UNCLASSIFIED EXCAVATION AREA ALSO INCLUDES PGE SUBGRADE STABILIZATION AREA AS DIRECTED BY THE RESIDENT ENGINEER.
4. THE CONTRACTOR SHALL ENSURE THAT 4 INCHES OF TOPSOIL CAN BE SPREAD OVER THE LIMITS OF THE GRADED AREA. IN SOME CASES, CONTRACTOR MAY BE REQUIRED TO OVER-EXCAVATE TO PROVIDE THE REQUIRED 4-INCH TOPSOIL LAYER. THE EARTHWORK QUANTITIES SHOWN INCLUDE THE REQUIRED OVER-EXCAVATION AND ARE SHOWN IN THE CROSS SECTIONS.
5. TOPSOIL PLACEMENT, EMBANKMENT FILL AND SHOULDER FILL SHALL BE CONSIDERED INCLUDED IN THE CONTRACT UNIT PRICE FOR UNCLASSIFIED EXCAVATION. NO SEPARATE PAYMENT WILL BE MADE FOR TOPSOIL PLACEMENT, EMBANKMENT FILL AND SHOULDER FILL.
6. ANY EXCESS MATERIAL INCLUDING CLAY, UNSUITABLE MATERIAL AND TOPSOIL SHALL BE HAULED OFF AIRPORT PROPERTY AND DISPOSED OF BY THE CONTRACTOR. CCDD TESTING REQUIREMENTS SHALL PER THE SPECIAL PROVISIONS SECTION 152.
7. PER THE GEOTECHNICAL INVESTIGATION REPORT, AVERAGE 12 INCHES OF TOPSOIL IS PRESENT AND USED IN QUANTITY ESTIMATION. TOPSOIL STRIPPED SHALL BE INCORPORATED INTO THE REQUIRED TOPSOIL PLACEMENT ON DISTURBED AREAS OUTSIDE OF NEW PAVEMENT.

**EARTHWORK SUMMARY TABLE**

LOCATION	TOPSOIL STRIPPING INITIAL POSITION (CUBIC YARD)	TOPSOIL PLACEMENT FINAL POSITION (CUBIC YARD)	SHOULDER FILL FINAL POSITION (CUBIC YARD)	UNCLASSIFIED EXCAVATION INITIAL POSITION (CUBIC YARD)	EMBANKMENT FILL FINAL POSITION (CUBIC YARD)
TAXIWAY A4 RELOCATION	3,140	2,340	1,390	3,700	110
TAXIWAY WIDENING AT RUNWAY 22 END	200	240	50	560	0
TOTAL	3,340	2,580	1,440	4,260	110

NOTE: UNCLASSIFIED EXCAVATION QUANTITY INCLUDES 15% NOMINAL NEW PAVEMENT AREA FOR PGE STABILIZATION.



CONSULTANTS

**FINAL**

WIDEN TAXIWAY FILLET AT  
RUNWAY 22 END AND  
RELOCATE TAXIWAY A4

SEPTEMBER 22, 2023

OWNER



MARK	DATE	DESCRIPTION

CMT PROJECT NO: 21001660.00  
 CAD DWG FILE:  
 DESIGNED BY: STL  
 DRAWN BY: JRO  
 CHECKED BY: STL  
 APPROVED BY: DKP  
 COPYRIGHT:

**INDEX TO CROSS SECTIONS AND EARTHWORK SUMMARY**





