F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
83	*	COOK	631	595
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* (2424 & 2626)R-2		CONTRACT NO. 62111		

LEGEND

EXISTING PAVEMENT

STRUCTURAL EXCAVATION

RAILROAD AVE. BRIDGE
SN 016-2792
(SEE STRUCTURAL PLANS)

℄ RAILROAD AVE

3.235

2 %

PH3 ST1
EARTH EXC. (SQ M) = 18.17
EMBKMT. (SQ M) = 26.79
UNSUIT. MAT. (SQ M) = 0.00
STR. EXC. (SQ M) = 8.96
SPOIL (SQ M) = 4.56

LIMITS OF STR. EXC. (TYP.)

LIMITS OF STR. EXC. (TYP.)

300+075.000

CROSS-SECTIONS FOR RAILROAD AVENUE

ORIGINAL SURVEY | SURVEYED | BY | DATE
NOTE BOOK | PLOTTED | | |
NO. | TEMPLATE | | |
| AREAS | | |
| AREAS CHECKED | | |

..\VPR70012A.DGN, ..\VRR70022A.DGN, ..\VPR70012A.DGN, ..\VDR99003I2A.DGN, ..\TST2012A.DGN, ..\VPR99D02A.DGN, ..\VX060252A.DGN, ..\TLTL0012A.DGN, ..\VRA0012A.DGN, ..\VRR0012A.DGN
8-16-2005, 10:28:58 T:\DOCUMENT\99375O\CIVIL\DGN\XS170042A.DGN BAJZEKKJ