

F.A.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90	2003-028F	COOK	419	12
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
62580				

SHEET NUMBER STATION	TO STATION	TEMPORARY SIGNING (SQ FT)	REMOVE SIGN PANEL TYPE 3 (SQ FT)	RELOCATE SIGN PANEL TYPE 3 (SQ FT)	REMOVE, STORE AND RE-ERECT SIGN PANEL (SQ FT)
MOT-01 2626+00	2638+00	71 179 109 120	NONE	NONE	254 254
MOT-02 2638+00	75+94	NONE	NONE	NONE	150
MOT-03 75+94	87+94	NONE	NONE	NONE	NONE
MOT-04 87+94	99+94	47	NONE	NONE	NONE
MOT-05 99+94	111+94	47	NONE	NONE	NONE
MOT-06 111+94	125+39	47 12	NONE	NONE	NONE
MOT-07		NONE	NONE	NONE	NONE
MOT-08 125+39	137+39	NONE	NONE	NONE	NONE
MOT-09 137+39	149+39	NONE	NONE	NONE	NONE
MOT-10 149+39	161+39	53 10 3 34 56	NONE	NONE	NONE
MOT-11 161+39	173+25	74 45 56 36	NONE	NONE	NONE
MOT-12 173+25	184+51	74 56 36	NONE	NONE	NONE
MOT-13 184+51	196+51	74	NONE	NONE	NONE
MOT-14 196+51	208+51	53	NONE	NONE	NONE
MOT-15 208+51	-	6	NONE	NONE	NONE
MOT-16 99+94	111+94	NONE	NONE	NONE	NONE
MOT-17 111+94	125+39	NONE	NONE	NONE	NONE

SHEET NUMBER STATION	TO STATION	TEMPORARY SIGNING (SQ FT)	REMOVE SIGN PANEL TYPE 3 (SQ FT)	RELOCATE SIGN PANEL TYPE 3 (SQ FT)	REMOVE, STORE AND RE-ERECT SIGN PANEL (SQ FT)
MOT-19 125+39	137+39	NONE	NONE	NONE	NONE
MOT-20 2626+00	2638+00	8 7 20 42 42 33	338 338	338 338	NONE
MOT-21 2638+00	75+94	150 60 44 15	NONE	NONE	NONE
MOT-22 75+94	87+94	NONE	NONE	NONE	NONE
MOT-23 87+94	99+94	104	NONE	NONE	NONE
MOT-24 99+94	111+94	NONE	NONE	NONE	NONE
MOT-25 111+94	125+39	104	NONE	NONE	NONE
MOT-27 125+39	137+39	46	NONE	NONE	NONE
MOT-28 137+39	149+39	NONE	NONE	NONE	NONE
MOT-29 149+39	161+39	NONE	NONE	NONE	NONE
MOT-30 161+39	173+25	NONE	NONE	NONE	NONE
MOT-31 173+25	184+51	45	NONE	NONE	NONE
MOT-32 184+51	196+51	NONE	NONE	NONE	NONE
MOT-33 196+51	208+51	NONE	NONE	NONE	NONE
MOT-34 208+51	-	NONE	NONE	NONE	NONE
MOT-35 2626+00	2638+00	NONE	338 254 338 254	338 254 338 254	NONE
MOT-36 2638+00	75+94	NONE	NONE	NONE	NONE

SHEET NUMBER STATION	TO STATION	TEMPORARY SIGNING (SQ FT)	REMOVE SIGN PANEL TYPE 3 (SQ FT)	RELOCATE SIGN PANEL TYPE 3 (SQ FT)	REMOVE, STORE AND RE-ERECT SIGN PANEL (SQ FT)
MOT-37 75+94	87+94	NONE	NONE	NONE	NONE
MOT-38 87+94	99+94	103	NONE	NONE	NONE
MOT-39 99+94	111+94	23	NONE	NONE	NONE
MOT-40 111+94	125+39	23	NONE	NONE	NONE
MOT-42 125+39	137+39	23	NONE	NONE	NONE
MOT-43 137+39	149+39	NONE	NONE	NONE	NONE
MOT-44 149+39	161+39	NONE	NONE	NONE	NONE
MOT-45 161+39	173+25	NONE	NONE	NONE	NONE
MOT-46 173+25	184+51	7	NONE	NONE	NONE
MOT-47 184+51	196+51	NONE	NONE	NONE	NONE
TOTAL		2,198	1,859	1,859	657

CHANGEABLE MESSAGE SIGNS

THE CONTRACTOR IS RESPONSIBLE FOR COORDINATING THE PLACEMENT AND MESSAGES FOR ALL PORTABLE CHANGEABLE MESSAGE SIGNS. PROVIDED BELOW FOR INFORMATION ONLY ARE ANTICIPATED LOCATIONS AND DURATIONS AT EACH LOCATION FOR PORTABLE CHANGEABLE MESSAGE SIGNS:

LOCATION	CMS (EACH)	TOTAL DURATION (CAL MO)
EB KENNEDY (I-94/90) AT CHICAGO AVE.	1	4
EB DAN RYAN (I-94/90) AT 18TH ST.	1	9
WB DAN RYAN (I-94/90) AT 26TH ST.	1	9
TOTAL		22

PROVIDED BELOW FOR INFORMATION ONLY ARE ANTICIPATED LOCATIONS AND DURATIONS, AT EACH LOCATION, FOR PORTABLE CHANGEABLE MESSAGE SIGNS THAT ARE BEING FURNISHED AND MAINTAINED BY CONTRACT 62300. CONTRACT 62580 CONTRACTOR IS RESPONSIBLE FOR COORDINATING WITH CONTRACT 62300 CONTRACTOR ON THE PLACEMENT OF THESE CMS'S AND THEIR MESSAGES AS THEY RELATE TO CONTRACT 62580. ONLY CONTRACT 62300 WILL BE PAID FOR THESE CMS'S. CONTRACT 62580 COORDINATION EFFORTS WILL NOT BE MEASURED FOR PAYMENT BUT IS CONSIDERED INCLUDED IN THE CONTRACT UNIT PRICE FOR TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS).

PROVIDED BELOW FOR INFORMATION ONLY ARE ANTICIPATED LOCATIONS AND DURATIONS, AT EACH LOCATION, FOR PORTABLE CHANGEABLE MESSAGE SIGNS THAT ARE BEING FURNISHED AND MAINTAINED BY CONTRACT 62302. CONTRACT 62580 CONTRACTOR IS RESPONSIBLE FOR COORDINATING WITH CONTRACT 62302 CONTRACTOR ON THE PLACEMENT OF THESE CMS'S AND THEIR MESSAGES AS THEY RELATE TO CONTRACT 62580. ONLY CONTRACT 62302 WILL BE PAID FOR THESE CMS'S. CONTRACT 62580 COORDINATION EFFORTS WILL NOT BE MEASURED FOR PAYMENT BUT IS CONSIDERED INCLUDED IN THE CONTRACT UNIT PRICE FOR TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS).

LOCATION	CMS (EACH)	TOTAL DURATION (CAL MO)
WB CHICAGO SKYWAY (I-90) AT STONY ISLAND	1	4
WB DAN RYAN (I-94) AT 95TH STREET	1	9
WB DAN RYAN (I-94) AT 75TH STREET	1	9
WB DAN RYAN (I-94) AT 71ST STREET	1	9
WB DAN RYAN (I-94/90) AT 51ST STREET	1	9
WB DAN RYAN (I-94/90) AT 31ST STREET	1	9
NB STEVENSON (I-55) AT ASHLAND AVE.	1	4
SB STEVENSON (I-55) AT MICHIGAN AVE.	1	4
NB STAGE 2 CONSTRUCTION	1	4
TOTAL		59

LOCATION	CMS (EACH)	TOTAL DURATION (CAL MO)
EB DAN RYAN (I-94/90) AT ROOSEVELT RD (12TH ST.)	1	4
NB STEVENSON (I-55) AT ASHLAND AVE.	1	4
SB STEVENSON (I-55) AT MICHIGAN AVE.	1	4
SB LAKE SHORE DRIVE AT CERMAK RD. (22ND ST.)	1	4
FRANKLIN CONNECTOR AT CERMAK RD. (22ND ST.)	1	4
EB DAN RYAN (I-94/90) AT 51ST STREET	2	13
EB DAN RYAN (I-94) AT 65TH STREET	1	9
EB DAN RYAN (I-94) AT 71ST STREET	2	13
TOTAL		55

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbainc.com

REVISIONS	
NAME	DATE
ADDENDUM 1	9/6/05

CSCH-07

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
NB DAN RYAN ELEVATED BRIDGE
REPAIR FROM 15TH TO 28TH STREETS
CIVIL SCHEDULES

SCALE: =NTS
DATE: 8/12/2005

DRAWN BY: RA
CHECKED BY: RS

M:\62580\62580\CHANGING SHEETS\62580_12\FPT_SCH07.dgn 10/5/2005 9/7/2005