

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	2004-083 I	COOK & DuPAGE	40	2
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 62825

INDEX OF SHEETS

DESCRIPTION

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	INDEX OF SHEETS, STATE STANDARDS, AND GENERAL NOTES
3	SUMMARY OF QUANTITIES
4-5	LOCATION MAPS OF CURB AND GUTTER REPAIR
6-9	SCHEDULE OF QUANTITIES
10	CITY OF CHICAGO PCC CONCRETE DRIVEWAY, ALLEY RETURN AND SIDEWALK
11	CURB OR CURB AND GUTTER REMOVAL AND REPLACEMENT
12	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS
13-16	STANDARD TRAFFIC SIGNAL DESIGN DETAILS
17	DETECTOR LOOP INSTALLATION DETAILS FOR ROADWAY RESURFACING
18-39	DETECTOR LOOP LOCATION DETAILS
40	TEMPORARY INFORMATION SIGNING

STATE STANDARDS

- 000001-04 STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
- 424001-02 CURB RAMPS FOR SIDEWALKS
- 606001-02 CONCRETE CURB AND COMBINATION CONCRETE CURB AND GUTTER
- 701301-02 LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
- 701501-02 LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
- 701701-04 URBAN LANE CLOSURE, MULTILANE INTERSECTION
- 701601-04 URBAN LANE CLOSURE, MULTILANE, 1W OR 2W, WITH MOUNTABLE MEDIAN
- 701606-04 URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN
- 701801-03 LANE CLOSURE, MULTILANE, 1W OR 2W, CROSSWALK OR SIDEWALK CLOSURE
- 702001-05 TRAFFIC CONTROL DEVICES

GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 1-800-892-0123 OR "CUAN" (CHICAGO UTILITY ALERT NETWORK), (312)-744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS FACILITIES. (48 HOUR NOTIFICATION IS REQUIRED).

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.

THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

THESE PLANS HAVE BEEN PREPARED FROM NOTES RECEIVED FROM FIELD MAINTENANCE ENGINEERS.

THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURING THE CONSTRUCTION OF THIS PROJECT.

SPECIFIC LOCATIONS AND QUANTITIES ARE TENTATIVE AND AT THE DISCRETION OF THE ENGINEER.

SALT TOLERANT SODDING SHALL BE INCIDENTAL TO THIS CONTRACT.

ANY CURB NEEDING TO BE REPAINTED SHALL BE INCIDENTAL TO THIS CONTRACT.

THE CONTRACTOR SHALL REPLACE ANY PAVEMENT MARKINGS REMOVED, DAMAGED, OR OTHERWISE DISTURBED AS A RESULT OF CONSTRUCTION ACTIVITY. THESE MARKINGS SHALL BE REPLACED WITH LIKE MATERIAL AND SHALL BE CONSIDERED INCIDENTAL TO THE COST OF THE CURB AND GUTTER WORK.

QUESTIONS REGARDING ANY OF THE CURB AND GUTTER REPAIR LOCATIONS MUST BE REFERRED TO MR. FRANK VITAGLIANO, MAINTENANCE YARD TECHNICIAN, AT (708) 544-9372

MIXTURE REQUIREMENTS

MIXTURE USE	AC/PG	RAP % (MAX)	DESIGN AIR VOIDS
BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	PG 64-22	15	4% @ 50

NOTE:
THE UNIT WEIGHT USED TO CALCULATE ALL BITUMINOUS SURFACE MIX QUANTITIES IS 112 LBS./SQ. YD./ IN.

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION INDEX OF SHEETS, STATE STANDARDS, AND GENERAL NOTES VARIOUS ROUTES CURB AND GUTTER REPAIR
NAME	DATE	
		SCALE: VERT. _____ HORIZ. _____ DATE _____
DRAWN BY _____		CHECKED BY _____