

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	2004-083 I	COOK & DUPAGE	40	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	
CONTRACT NO. 62825				

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		COOK SFTY-1B	DUPAGE SFTY-1B					CODE NO		ITEM	UNIT			
42001300	PROTECTIVE COAT	SQ YD	1868	1864	4											
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	902	902												
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	902	902												
44001115	BITUMINOUS CONCRETE SURFACE REMOVAL (FULL DEPTH)	SQ YD	167	166	11											
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	5981	5976	5											
44004610	SIDEWALK REMOVAL AND REPLACEMENT (SPECIAL)	SQ FT	5175	5150	25											
67100100	MOBILIZATION	L SUM	1	1												
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1												
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1												
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1												
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1												
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1												
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	2949	2949												
X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	TON	29	28	1											

S:\PROJECTS\2004\2004-083 I\180556118005600032

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
VARIOUS ROUTES
CURB AND GUTTER REPAIR