

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	2004-083 I	COOK	40	9
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	HIGHWAY PROJECT		

CONTRACT NO.: 62825

SCHEDULE OF QUANTITIES

Location	Comb. Conc C&G / R & R Linear Feet	Bituminous Conc. Surface R & R Full Depth	Carriage Sidewalk	5' Parallel Sidewalk	Driveway	Handicap Walk	Grass	Remarks
W/B 79 TH ST N/W CORNER OF MAYFIELD	13'	X					X	CORNER RADIUS
W/B 79 TH ST 5934	5'	X					X	
W/B 79 TH ST 6000	75'	X	X					BETWEEN CORNER AND DRIVEWAY
W/B 79 TH ST 6058	8'	X					X	EAST OF SEWER
W/B 79 TH ST 6118	14'	X			12' OF 14'		2' OF 14'	CONCRETE DRIVE
W/B 79 TH ST 6120	14'	X			X			CONCRETE DRIVE
W/B 79 TH ST 6134	14'	X			X			CONCRETE DRIVE
W/B 79 TH ST 6212	18'	X			16' OF 18'		2' OF 18'	
W/B 79 TH ST WEST OF MERRIMAC	81'	X					X	VARIOUS LOCATIONS BETWEEN MERRIMAC AND MOBILE IN FRONT OF SCHOOL
W/B 79 TH ST NE CORNER OF MERRIMAC	9'	X				X		
W/B 79 TH ST 6510	17'	X			12' OF 17'		5' OF 17'	SHOULD REPAIR 9' OF APRON DUE FROM SEWER DAMAGE
W/B 79 TH ST 6550	6'	X					X	EAST OF E&J DELI DRIVEWAY
W/B 79 TH ST AT NATOMA	21'	X					X	FROM N/E CORNER OF NATOMA
W/B 79 TH ST AT N/W CORNER OF NATOMA	8'	X					X	CORNER RADIUS
W/B 79 TH ST AT NE CORNER OF NEWCASTLE	16'	X		5' OF 16'			11' OF 16'	CORNER RADIUS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
VARIOUS ROUTES
CURB AND GUTTER REPAIR

SCALE: VERT. 1"=50'
HORIZ. 1"=50'
DATE 8/30/2005

DRAWN BY
CHECKED BY