

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	99-1-N	WILL	52	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

Contract 62834

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	URBAN 100% STATE 1000-2A	TRAFFIC SIGNALS 100% STATE Y031-1F	MONEE F. P. D. 100% Y031-3D	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	376	376			
20400800	FURNISHED EXCAVATION	CU YD	87	87			
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1359	1359			
25000210	SEEDING, CLASS 2A	ACRE	0.3	0.3			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	27	27			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	27	27			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	27	27			
28000400	PERIMETER EROSION BARRIER	FOOT	1800	1800			
20200100	EARTH EXCAVATION	CU YD	975	975			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	4	4			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	1	1			
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	148	148			
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	52	52			
40600030	AGGREGATE (PRIME COAT)	TON	21	21			
44000008	BITUMINOUS SURFACE REMOVAL 2 1/2"	SQ YD	7069	7069			
44000100	PAVEMENT REMOVAL	SQ YD	433	433			
44000112	BITUMINOUS REMOVAL OVER PATCHES 3"	SQ YD	300	300			
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	291	291			
44001430	BITUMINOUS SHOULDER REMOVAL	SQ YD	1462	1462			
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	52	52			
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	52	52			
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	68	68			
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	39	39			
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	39	39			
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	50	50			
44213200	SAW CUTS	FOOT	4218	4218			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	9	9			
48200400	BITUMINOUS SHOULDERS 6"	SQ YD	262	262			
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	400	400			

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	URBAN 100% STATE 1000-2A	TRAFFIC SIGNALS 100% STATE Y031-1F	MONEE F. P. D. 100% Y031-3D	
* 63000005	STEEL PLATE BEAM GUARD RAIL, TYPE B	FOOT	950	950			
63200310	GUARDRAIL REMOVAL	FOOT	950	950			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5			
67100100	MOBILIZATION	L SUM	1	1			
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1			
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20	20			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1995	1995			
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	194	194			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	6645	6645			
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	428	428			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	53	53			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	202	202			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2886	2886			
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	194	194			
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	6645	6645			
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	428	428			
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	53	53			
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	202	202			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	58	58			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	24	24			
* 80802200	WOOD POLE, 40 FT., CLASS 2	EACH	8		8		
* 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1		1		
* 85700300	FULL-ACTUATED CONTROLLER AND TYPE V CABINET	EACH	1		1		

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

9/20/2005 13:00:00