

PROJECT: PLANTING BEDS AND CORNER GARDENS
 AT 95TH, 94TH, 87TH, AND 79TH STREETS
 COOK COUNTY / CITY OF CHICAGO

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	*	COOK	30	3
STA. 1200+00.00		TO STA. 1330+00.00		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
• (1516.1, 1717 & 1818) I-4				62933

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	URBAN TOTAL	100% STATE		100% CITY OF CHICAGO
				DAN RYAN Y003	DAN RYAN Y003	DAN RYAN Y003
20700220	POROUS GRANULAR EMBANKMENT	CU YD	29	29		
25000210	SEEDING CLASS 2A	ACRE	0.25	0.25		
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	4	4		
* 42001300	PROTECTIVE COAT	SQ YD	325	325		
44000112	BITUMINOUS REMOVAL OVER PATCHES 3"	SQ YD	43	43		
50200100	STRUCTURE EXCAVATION	CU YD	48	48		
56104600	WATER VALVES, 2"	EACH	2			2
56200900	WATER SERVICE LINE 2 1/2"	FOOT	45			45
* 60600605	CONCRETE CURB, TYPE B	FOOT	222	222		
67100100	MOBILIZATION	L SUM	1	1		
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	69	69		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	54	54		
C2C03930	SHRUB, ILEX VERTICILLATA 'JIM DANDY' (JIM DANDY WINTERBERRY), 24" HEIGHT CONTAINER	EACH	1	1		
C2C03932	SHRUB, ILEX VERTICILLATA 'RED SPRITE' (RED SPRITE DWARF WINTERBERRY), 24" HEIGHT CONTAINER	EACH	5	5		
A2008750	TREE, ULMUS X PATRIOT (PATRIOT ELM), 3" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	4	4		
B2005216	TREE, MALUS SUTYZAM (SUGAR TYME CRABAPPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	6	6		
K1003680	MULCH	SQ YD	183	183		
X0301407	PERENNIAL PLANTS, GALLON POT	UNIT	16	16		
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	120	120		
X0324525	PLANTING MIX FURNISH AND PLACE 36"	SQ YD	195	195		
X0325102	INSPECTION PIPE, 4 INCH	EACH	4			4
X0325103	WATER METER IN VAULT, 2 INCH	EACH	2			2
X0325104	WATER TAP, 2 INCH	EACH	2			2
X0325105	IRRIGATION SYSTEM	SQ YD	183			183
X0325106	IRRIGATION SYSTEMS FALL SHUTDOWN	EACH	2			2
X0325107	IRRIGATION SYSTEMS SPRING STARTUP	EACH	2			2
X0325109	POROUS GRANULAR MATERIAL	CU YD	66	66		
* X0656300	PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	28	28		
X4420222	CLASS C PATCHES, TYPE I 10 1/2	SQ YD	10	10		
X4420223	CLASS C PATCHES, TYPE II 10 1/2	SQ YD	20	20		
* X6065740	CONCRETE MEDIAN SURFACE, 5" (MODIFIED)	SQ FT	2647	2647		
X7015000	CHANGEABLE MESSAGE SIGNS	CAL MO	12	12		
XX001363	PERENNIAL PLANT, NARCISSUS	UNIT	50	50		
XX003710	BACKFLOW PREVENTER (RPZ), 2 INCH	EACH	2			2
Z0027800	GEOTECHNICAL FABRIC	SQ YD	195	195		

* - SPECIALTY ITEM

TYLIN INTERNATIONAL

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.I. 94 (DAN RYAN EXPRESSWAY)
 SUMMARY OF QUANTITIES

SCALE: NONE
 DATE: SEPTEMBER 2, 2005
 DRAWN BY: JDF
 CHECKED BY: RTM