

**70300220 TEMPORARY PAVEMENT MARKING - LINE 4"**

LOCATION	QUANTITY (FOOT)
STAGE I	
STA. 554+25.0 TO STA. 563+00.0 (WHITE)	875
STA. 553+72.5 TO STA. 563+47.5 (YELLOW)	975
STAGE II	
STA. 553+82.5 TO STA. 563+37.5 (YELLOW)	955
STA. 554+36.0 TO STA. 562+88.0 (WHITE)	852
TOTAL =	3,657

**70300280 TEMPORARY PAVEMENT MARKING - LINE 24"**

LOCATION	QUANTITY (FOOT)
HAHNAMAN ROAD	
EAST SIDE	12.0
WEST SIDE	12.0
TOTAL =	24.0

**70301000 WORK ZONE PAVEMENT MARKING REMOVAL**

LOCATION	QUANTITY (SQ. FT.)
TEMPORARY PAVEMENT MARKING	
STAGE I	618.7
STAGE II	602.4
TEMPORARY STOP BARS	
HAHNAMAN ROAD	48.0
TOTAL =	1,267.1

**70400100 TEMPORARY CONCRETE BARRIER**

LOCATION	QUANTITY (FOOT)
STATION	
STA 553+72.5 TO 563+47.5 (STAGE I)	975
TOTAL =	975

**70400200 RELOCATE TEMPORARY CONCRETE BARRIER**

LOCATION	QUANTITY (FOOT)
STATION	
STA 553+82.5 TO 563+37.5 (STAGE II)	955
TOTAL =	955

**78001100 PAINT PAVEMENT MARKING - LINE 4"**

LOCATION	QUANTITY (FOOT)
STATION	
STA. 554+55.0 TO STA. 562+70.00 RT. (WHITE)	815
STA. 554+55.0 TO STA. 562+70.00 LT. (WHITE)	815
STA. 554+55.0 TO STA. 562+70.00 (YELLOW)	203.8
x 2 APPLICATIONS	
TOTAL =	3,667.6

**78100100 RAISED REFLECTIVE PAVEMENT MARKER**

LOCATION	QUANTITY (EACH)
STATION	
554+22.50	1
555+02.50	1
555+82.50	1
556+82.50	1
559+82.50	1
560+82.50	1
561+42.50	1
562+22.50	1
563+02.50	1
TOTAL =	9

**78100105 RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)**

LOCATION	QUANTITY (EACH)
STATION	
557+42.50	1
558+22.50	1
559+02.50	1
TOTAL =	3

**78200200 BIDIRECTIONAL PRISMATIC BARRIER REFLECTOR**

LOCATION	QUANTITY (EACH)
STA. 547+70 LT.	1
STA. 558+20 RT.	1
STA. 558+50 LT.	1
STA. 559+00 RT.	1
TOTAL =	4

**78200420 GUARDRAIL MARKERS, TYPE B**

LOCATION	QUANTITY (EACH)
STA. 555+80 RT.	1
STA. 556+10 LT.	1
STA. 556+60 RT.	1
STA. 556+90 LT.	1
STA. 557+40 RT.	1
STA. 559+30 LT.	1
STA. 559+80 RT.	1
STA. 560+10 LT.	1
STA. 560+80 RT.	1
STA. 556+90 LT.	1
STA. 561+40 RT.	1
TOTAL =	11

**78201000 TERMINAL MARKER - DIRECT APPLIED**

LOCATION	QUANTITY (EACH)
STATION	
555+18.61 RT	1
555+50.90 LT.	1
561+25.10 RT.	1
561+57.39 LT.	1
TOTAL =	4

**78300100 PAVEMENT MARKING REMOVAL**

LOCATION	QUANTITY (SQ. FT.)
STATION	
CENTER: STA. 553+72.5 TO STA. 554+55.0	6.9
CENTER: STA. 562+70.0 TO STA. 563+47.5	6.5
RT: STA. 554+25.0 TO STA. 563+00.0	291.7
TOTAL =	305.1

**78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL**

LOCATION	QUANTITY (EACH)
STATION	
STA. 553+72.5 TO STA. 563+47.5	13
TOTAL =	13

**Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3**

LOCATION	QUANTITY (EACH)
U.S. 40	
NORTH END	1
SOUTH END	1
TOTAL =	2

**Z0030350 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3**

LOCATION	QUANTITY (EACH)
U.S. 40	
NORTH END	1
SOUTH END	1
TOTAL =	2

**A2007814 TREE, TILIA AMERICANA (AMERICAN LINDEN/BASSWOOD), 1-3/4" CALIPER, BALLED AND BURLAPPED**

LOCATION	QUANTITY (EACH)
JOB SITE	3
TOTAL =	3

**X4066414 BIT, CONC. SURF. CSE., SUPERPAVE. MIX "C", N50**

LOCATION	QUANTITY (TON)
STATION	
LT SHOULDER: 554+55 TO 562+70	148.7
RT SHOULDER: 554+55 TO 562+70	272.9
PAVEMENT: 554+55 TO 562+70	139.9
TOTAL =	559.5

**X4066765 LEVELING BINDER (MACHINE METHOD), SUPERPAVE, N50**

LOCATION	QUANTITY (TON)
STATION	
554+90.00 TO 557+16.50	94.3
559+59.50 TO 562+35.00	174.3
TOTAL =	268.6

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**