

←X071-2A→

←X071-2A→

SUMMARY OF QUANTITIES			80% FED 20% ST	CONSTRUCTION TYPE CODE		
CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	BRIDGE	SAFETY SFTY-3N
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	20	20		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	141	141		
20200100	EARTH EXCAVATION	CU YD	2834	2834		
20300100	CHANNEL EXCAVATION	CU YD	1148	1148		
20400800	FURNISHED EXCAVATION	CU YD	6958	6958		
20700220	POROUS GRANULAR EMBANKMENT	CU YD	131	131		
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	124		124	
25000310	SEEDING, CLASS 4	ACRE	0.30	0.30		
25001830	SEEDING, CLASS 6 (MODIFIED)	ACRE	2.10	2.10		
25100115	MULCH, METHOD 2	ACRE	4.50	4.50		
25100630	EROSION CONTROL BLANKET	SQ YD	2201	2201		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	241	241		
28000300	TEMPORARY DITCH CHECKS	EACH	11	11		
28000400	PERIMETER EROSION BARRIER	FOOT	1240	1240		
28000500	INLET & PIPE PROTECTION	EACH	3	3		
28100107	STONE RIPRAP, CLASS A4	SQ YD	784		784	
28100807	STONE DUMPED RIPRAP, CLASS A4	TON	27	27		
28200200	FILTER FABRIC	SQ YD	824	40	784	
35101400	AGGREGATE BASE COURSE, TYPE B	TON	797	797		
40600990	TEMPORARY RAMP	SQ YD	236	236		
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	17	17		
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	253	253		
42001300	PROTECTIVE COAT	SQ YD	253	253		
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	51	51		
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	1037	1037		
44000100	PAVEMENT REMOVAL	SQ YD	313	313		

* SPECIALTY ITEMS

SUMMARY OF QUANTITIES			80% FED 20% ST	CONSTRUCTION TYPE CODE		
CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	BRIDGE	SAFETY SFTY-3N
44004250	PAVED SHOULDER REMOVAL	SQ YD	425	425		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1844	1844		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	146	146		
48202000	BITUMINOUS SHOULDERS SUPERPAVE	TON	433	433		
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1	
50104900	REMOVAL OF EXISTING SUB-STRUCTURES	EACH	2		2	
50200100	STRUCTURE EXCAVATION	CU YD	280		280	
50300100	FLOOR DRAINS	EACH	18		18	
50300150	NEOPRENE EXPANSION JOINT 2"	FOOT	92		92	
50300225	CONCRETE STRUCTURES	CU YD	100.6		100.6	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	228.6		228.6	
50300260	BRIDGE DECK GROOVING	SQ YD	722		722	
50300300	PROTECTIVE COAT	SQ YD	890		890	
50300310	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	18		18	
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1	
50500505	STUD SHEAR CONNECTORS	EACH	3762		3762	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	62670		62670	
51201000	FURNISHING METAL PILE SHELLS 12"	FOOT	1736		1736	
51202600	DRIVING AND FILLING SHELLS	FOOT	1736		1736	
51203200	TEST PILE METAL SHELLS	EACH	2		2	
51205200	TEMPORARY SHEET PILING	SQ FT	1887		1887	
51500100	NAME PLATES	EACH	1		1	
54201063	PIPE CULVERTS, CLASS D, TYPE 2 18"	FOOT	74	74		
54215547	METAL END SECTIONS 12"	EACH	4	4		
54215553	METAL END SECTIONS 18"	EACH	2	2		
54390090	INSERTION CULVERT LINER 12"	FOOT	70	70		
54390160	INSERTION CULVERT LINER 21"	FOOT	90	90		

SUMMARY OF QUANTITIES
 IL 40 OVER GREEN RIVER
 F.A.P. RTE 646 (IL RTE 40) SECTION 102 BR-2
 WHITESIDE COUNTY