

AGGREGATE BASE COURSE, TYPE B						35101400
LOCATION STATION TO STATION	LT/RT	AREA	AREA	THICK	WEIGHT	
		SO FT	SO YDS	INCH		
FIELD ENTRANCES						
STA. 680+00.00	LT	11418	1268.61	8	578.49	
STA. 680+00.00	RT	2235.50	248.39	8	113.27	
UNDER BIT. SHOULDER FOR RUN ABOUT						
STA. 669+70.00 TO STA. 673+62.15	RT	2548.69	283.19	4	64.57	
STA. 676+20.20 TO STA. 678+70.00	RT	1599.61	177.73	4	40.52	
TOTAL					796.84	

TEMPORARY RAMP						40600990
LOCATION STATION	LT/RT	WIDTH	HEIGHT	LENGTH	QUANTITY	
		FEET	INCHES	FEET		
STAGE I						
STA. 669+70.00	RT	17.5	0.75	2.5	4.86	
STA. 673+54.63	RT	17.5	1.50	5	9.72	
STA. 676+00.63	RT	17.5	1.50	5	9.72	
STA. 678+70.00	RT	17.5	0.75	2.5	4.86	
STAGE II						
STA. 669+70.00	LT	12	0.75	2.5	3.33	
STA. 673+54.63	LT	12	1.50	5	6.67	
STA. 676+00.63	LT	12	1.50	5	6.67	
STA. 678+70.00	LT	12	0.75	2.5	3.33	
STAGE III (FINAL)						
STA. 668+70.00	LT	12	1.50	5	6.67	
STA. 668+70.00	RT	12	1.50	5	6.67	
STA. 680+50.00	LT	12	1.50	5	6.67	
STA. 680+50.00	RT	12	1.50	5	6.67	
TEMPORARY TAPERS FOR WINTER SHUTDOWN (240:l (H:V))						
STA. 673+54.63	LT	12	1.50	30	40.00	
STA. 673+54.63	RT	12	1.50	30	40.00	
STA. 676+00.63	LT	12	1.50	30	40.00	
STA. 676+00.63	RT	12	1.50	30	40.00	
TOTAL					235.83	

INCIDENTAL BITUMINOUS SURFACING				40800040
LOCATION	AREA	AREA	WEIGHT	
	SO FT	SO YD	TONS	
STA. 680.00 LT	689.64	76.63	8.58	
STA. 680.00 RT	697.00	77.44	8.67	
TOTAL			17.26	

BRIDGE APPROACH PAVEMENT			42001165
LOCATION STATION TO STATION	AREA	SO YD	
	SO FT	SO YD	
STA. 673+54.60 TO STA. 673+84.60	126.70		
STA. 675+70.60 TO STA. 676+00.60	126.70		
TOTAL			253.40

PROTECTIVE COAT			42001300
LOCATION STATION TO STATION	AREA	SO YD	
	SO FT	SO YD	
STA. 673+54.60 TO STA. 673+84.60	126.70		
STA. 675+70.60 TO STA. 676+00.60	126.70		
TOTAL			253.40

BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)			42001430
LOCATION STATION TO STATION	AREA	SO YD	
	SO FT	SO YD	
STA. 673+48.60 TO STA. 673+54.60	25.3		
STA. 676+00.60 TO STA. 676+06.60	25.3		
TOTAL			50.6

PAVEMENT REMOVAL				44000100
LOCATION	LENGTH	WIDTH	AREA	
	FEET	FEET	SO YDS	
STA. 673+48.63 TO STA. 674+07.35	58.71	24	156.56	
STA. 675+47.98 TO STA. 676+06.63	58.65	24	156.40	
TOTAL				312.96

BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)						44000030
LOCATION STATION TO STATION	DESCRPT.	LENGTH	WIDTH	AREA		
		FEET	FEET	SO FT	SO YD	
RESURFACING						
STA. 668+70.00 TO STA. 669+00.00	TAPER	30	24	80		
STA. 669+00.00 TO STA. 669+75.00	MAINLINE	75	24	200		
STA. 678+70.00 TO STA. 680+50.00	MAINLINE	180	24	480		
STA. 678+70.00 RT TO STA. 680+50.00 RT	SHOULDER	180	4	80		
STA. 679+66.00 LT TO STA. 680+50.00 LT	SHOULDER	84	4	37.33		
TEMPORARY TAPERS FOR WINTER SHUTDOWN						
STA. 673+24.63 TO STA. 673+54.63		30	24	80		
STA. 676+00.63 TO STA. 676+30.63		30	24	80		
TOTAL					1037.33	

PAVED SHOULDER REMOVAL						44004250
LOCATION STATION TO STATION	LT/RT	LENGTH	WIDTH	AREA		
		FEET	FEET	SO FT	SO YDS	
STA. 668+70.00 TO STA. 673+98.36	LT	528.36	4	2113.44	234.83	
STA. 675+37.18 TO STA. 679+66.00	LT	428.82	4	1715.28	190.59	
TOTAL					425.41	

STRIP REFLECTIVE CRACK CONTROL TREATMENT			44300200
LOCATION	LT/RT	LENGTH	
		FEET	
STA. 668+70.00 TO STA. 673+39.56	LT	469.56	
STA. 675+97.56 TO STA. 680+50.00	LT	452.44	
STA. 668+70.00 TO STA. 673+57.64	RT	487.64	
STA. 676+15.65 TO STA. 680+50.00	RT	434.35	
TOTAL			1843.99

AGGREGATE SHOULDERS TYPE B							48101200
LOCATION STATION TO STATION	LT/RT	LENGTH	WIDTH	LT	RT	WEIGHT	
				AVG. THICK	AVG. THICK		
STA. 668+70.00 TO STA. 669+00.00	LT	30.00	4	8		6.15	
STA. 669+00.00 TO STA. 670+00.00	LT & RT	100.00	4	8	6.0	34.44	
STA. 670+00.00 TO STA. 671+00.00	LT & RT	100.00	4	8	7.0	39.77	
STA. 671+00.00 TO STA. 671+10.50	LT	10.50	4	8		2.05	
STA. 677+82.25 TO STA. 677+92.80	RT	10.55	4		6.5	3.07	
STA. 677+92.80 TO STA. 679+00.00	LT & RT	107.20	4	8	6	39.97	
STA. 679+00.00 TO STA. 679+71.00	LT & RT	71.00	4	8	4	18.45	
STA. 680+29.00 TO STA. 680+50.00	LT & RT	21.00	4	3.0	2	2.46	
TOTAL						146.36	

SHOULDER DRAIN SCHEDULE					
LOCATION STATION	LT/RT	54215547	60105000	60900240	60900515
		METAL END SECTIONS 12"	PIPE DRAIN, CORR. STEEL OR ALUM. ALLOY 12"	TYPE C, INLET BOX STANDARD 609006	CONCRETE THRUST BLOCKS
STA. 673+46.00	LT	1	15.5	1	1
STA. 675+82.05	LT	1	15.3	1	1
STA. 673+73.20	RT	1	31.0	1	1
STA. 676+09.00	RT	1	12.0	1	1
TOTAL		4	73.8	4	4

FIELD TILE SCHEDULE					
LOCATION	61100500	61133100	61140000	61140100	61140200
	EXPLORATION TRENCH 52" DEPTH	FIELD TILE JUNCTION VAULTS, 2' DIA.	STORM SEWER, SPECIAL 8"	STORM SEWER, SPECIAL 10"	STORM SEWER, SPECIAL 12"
JOB SITE (AS PER GENERAL NOTE)	115	2	115	115	115
TOTAL		115	2	115	115

METAL END SECTIONS 18"			54215553
LOCATION STATION	LT/RT	EACH	
		SO FT	SO YD
STA. 679+63.40	LT	1	
STA. 680+37.40	LT	1	
TOTAL			2

INSERTION CULVERT LINER 12"			54390090
LOCATION STATION TO STATION	LT/RT	LENGTH	
		FOOT	
STA. 673+70.10 TO STA. 674+40.10	RT	70	
TOTAL			70

INSERTION CULVERT LINER 21"			54390160
LOCATION STATION TO STATION	LT/RT	LENGTH	
		FOOT	
STA. 672+97.80 TO STA. 673+87.80	LT	90	
TOTAL			90

GUARDRAIL SCHEDULE				
LOCATION STATION TO STATION	LT/RT	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	STEEL PLATE BEAM GUARDRAIL, TYPE A	TRAFFIC BARRIER TERMINAL, TYPE 6
			63100169 EACH	63000000 FOOT
STA. 671+33.00 TO STA. 671+83.00	LT	1		
STA. 671+83.00 TO STA. 673+33.00	LT		150.00	
STA. 673+33.00 TO STA. 673+66.15	LT			1
STA. 671+22.50 TO STA. 671+72.50	RT	1		
STA. 671+72.50 TO STA. 673+60.00	RT		187.50	
STA. 673+60.00 TO STA. 673+93.15	RT			1
STA. 675+62.15 TO STA. 675+95.30	LT			1
STA. 675+95.30 TO STA. 677+20.30	LT		125.00	
STA. 677+20.30 TO STA. 677+70.30	LT	1		
STA. 675+89.10 TO STA. 676+22.25	RT			1
STA. 676+22.25 TO STA. 677+09.75	RT		87.50	
STA. 677+09.75 TO STA. 677+59.75	RT	1		
TOTAL		4	550.00	4

FURNISHING AND ERECTING RIGHT OF WAY MARKERS				66600105
LOCATION	LT/RT	OFFSET	EACH	
			SO FT	SO YD
STA. 668+00.00	LT	40.42	1	
STA. 669+00.00	LT	70	1	
STA. 672+00.00	LT	80	1	
STA. 673+00.00	LT	80	1	
STA. 674+00.00	LT	60	1	
STA. 680+50.00	LT	60	1	
STA. 681+00.00	LT	41.65	1	
STA. 668+00.00	RT	39.58	1	
STA. 669+00.00	RT	80	1	
STA. 672+00.00	RT	110	1	
STA. 673+50.00	RT	110	1	
STA. 674+01.49	RT	68.81	1	
TOTAL			12	

FLAP GATES				CONTRACT NO. 64427	
LOCATION	FLAP GATE 15"	FLAP GATE 24"	TOTAL		
			SO FT	SO YD	TON
60801015		60801024			
JOB SITE (AS PER GENERAL NOTE)	1	1			
TOTAL			1	1	

PIPE CULVERTS, CLASS D, TYPE 2, 18"				542D1063
LOCATION STATION	OFFSET	LT/RT	LENGTH	
			FOOT	
STA. 680+00.00	43	LT	74	
TOTAL			74	

GUARDRAIL REMOVAL			63200310
LOCATION STATION TO STATION	LT/RT	LENGTH	
		FEET	
STA. 673+14.20 TO STA. 673+90.09	LT	75.95	
STA. 673+47.99 TO STA. 674+23.84	RT	75.89	
STA. 675+31.55 TO STA. 675+64.03	LT	49.09	
STA. 675+65.33 TO STA. 676+40.99	RT	75.70	
TOTAL			276.63

PERMANENT SURVEY MARKERS, TYPE II		66700305
LOCATION STATION TO STATION	QUANTITY	
	EACH	
STA. 673+84.60 TO STA. 675+70.60	1	
TOTAL		1

SCHEDULE OF QUANTITIES
 IL 40 OVER GREEN RIVER
 F.A.P. RTE 646 (IL RTE 40) SECTION 102 BR-2
 WHITESIDE COUNTY