

ENGINEER'S FIELD OFFICE, TYPE A	67000400
DESCRIPTION	QUANTITY
	CAL MO
PRELIMINARY CONSTRUCTION	1
BRIDGE AND ROADWAY CONSTRUCTION (RT SIDE)	3
BRIDGE AND ROADWAY CONSTRUCTION (LT SIDE)	3
FINAL CONSTRUCTION	1
MISCELLANEOUS CLEANUP, ETC.	1
TOTAL	9

MOBILIZATION	67100100
LOCATION	L. SUM
ENTIRE JOB SITE	1
TOTAL	1

TRAFFIC CONTROL & PROTECTION, STANDARD 701321	70100405
LOCATION	EACH
ENTIRE JOB SITE	1
TOTAL	1

TRAFFIC CONTROL & PROTECTION, STANDARD 701201	70100450
LOCATION	L. SUM
ENTIRE JOB SITE	1
TOTAL	1

TRAFFIC CONTROL & PROTECTION, STANDARD 701306	70100460
LOCATION	L. SUM
ENTIRE JOB SITE	1
TOTAL	1

TRAFFIC CONTROL & PROTECTION, STANDARD 701326	70100500
LOCATION	L. SUM
ENTIRE JOB SITE	1
TOTAL	1

TRAFFIC CONTROL SURVEILLANCE	70103815
DESCRIPTION	QUANTITY
	CAL DA
PRELIMINARY SHOULDER WORK (LT. SIDE)	4
SHOULDER WORK AT NORTH END (LT. SIDE)	2
SHOULDER WORK AT NORTH END (RT. SIDE)	2
TOTAL	8

TEMPORARY RUMBLE STRIP	70106700
DESCRIPTION	QUANTITY
	EACH
NORTH SIDE OF BRIDGE	3
SOUTH SIDE OF BRIDGE	3
TOTAL	6

NOTE: PLACE TEMPORARY RUMBLE STRIPS AS PER HIGHWAY STANDARD 701321.

TRAFFIC STAGING SCHEDULE								
LOCATION STATION TO STATION	LT/RT	STAGE	70106500	70400100	70400200	70030350	70030250	
			TEMPORARY BRIDGE TRAFFIC SIGNALS	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	
			EACH	FOOT	FOOT	EACH	EACH	
STA. 667+00.00	RT	1 & 2						
STA. 667+25.00	LT	1 & 2						
STA. 668+30.00		1 & 2				1	1	
STA. 668+30.00 TO STA. 669+70.00		1 & 2		140	140			
STA. 669+70.00 TO STA. 678+70.00		1 & 2		900	900			
STA. 678+70.00 TO STA. 680+10.00		1		140				
STA. 678+70.00 TO STA. 679+60.00		2			90			
STA. 680+10.00		1				1		
STA. 679+90.00		2					1	
STA. 681+15.00	RT	1						
STA. 681+40.00	LT	1						
STA. 680+65.00	RT	2						
STA. 680+90.00	LT	2						
TOTAL			1	1180	1130	2	2	

SHORT-TERM PAVEMENT MARKING	70300100		
LOCATION STATION TO STATION	NO. OF APPLICATIONS	APPLIED	QUANTITY FOOT
STA. 669+00.00 TO STA. 673+48.63	2	CENTERLINE	81.56
STA. 676+06.63 TO STA. 680+50.00	2	CENTERLINE	80.60
STA. 669+00.00 TO STA. 680+50.00	1	CENTERLINE	104.54
TOTAL			266.70

TEMPORARY PAVEMENT MARKING	70300200	
LOCATION STATION TO STATION	APPLIED	QUANTITY FOOT
PLACED ON LEVELING BINDER		
STA. 669+00.00 TO STA. 674+77.63	S. BOUND NO PASSING	577.63
STA. 674+77.63 TO STA. 680+50.00	N. BOUND NO PASSING	572.37
PLACED ON SURFACE		
STA. 669+00.00 TO STA. 680+50.00	N. BOUND EDGELINE	1150.00
STA. 669+00.00 TO STA. 680+50.00	S. BOUND EDGELINE	1150.00
STA. 669+00.00 TO STA. 680+50.00	CENTERLINE	287.50
STA. 669+00.00 TO STA. 674+77.63	S. BOUND NO PASSING	577.63
STA. 674+77.63 TO STA. 680+50.00	N. BOUND NO PASSING	572.37
TOTAL		4887.50

PAVEMENT MARKING TAPE, TYPE III 4"	70300520		
LOCATION STATION TO STATION	LT/RT	APPLIED	QUANTITY FOOT
STAGE I			
STA. 668+70.00 TO STA. 679+66.00	LT	EDGELINE	1096.00
STAGE II			
STA. 669+00.00 TO STA. 679+50.00	RT	EDGELINE	1050.00
TOTAL			2146

WORK ZONE PAVEMENT MARKING REMOVAL	70301000	
LOCATION STATION TO STATION	APPLIED	QUANTITY SO FT
SHORT TERM PAVEMENT MARKING REMOVAL		
STA. 669+00.00 TO STA. 680+50.00	CENTERLINE	34.85
TEMPORARY PAVEMENT MARKING REMOVAL		
STA. 669+00.00 TO STA. 680+50.00	N. BOUND EDGELINE	383.33
STA. 669+00.00 TO STA. 680+50.00	S. BOUND EDGELINE	383.33
STA. 669+00.00 TO STA. 680+50.00	CENTERLINE	95.83
STA. 669+00.00 TO STA. 674+77.63	S. BOUND NO PASSING	192.54
STA. 674+77.63 TO STA. 680+50.00	N. BOUND NO PASSING	190.79
TOTAL		1280.68

PAINT PAVEMENT MARKING - LINE 4"	78001110	
LOCATION STATION TO STATION	APPLIED	QUANTITY FOOT
STA. 669+00.00 TO STA. 680+50.00	N. BOUND EDGELINE	1150.00
STA. 669+00.00 TO STA. 680+50.00	S. BOUND EDGELINE	1150.00
STA. 669+00.00 TO STA. 680+50.00	CENTERLINE	287.50
STA. 669+00.00 TO STA. 674+77.63	S. BOUND NO PASSING	577.63
STA. 674+77.63 TO STA. 680+50.00	N. BOUND NO PASSING	572.37
TOTAL		3737.50

\* NOTE: ACTUAL "NO PASSING" ZONES TO BE LOCATED IN THE FIELD BY THE ENGINEER

GUARDRAIL AND BARRIER WALL MARKERS					
LOCATION STATION	LT/RT	SPACING (FEET)	TERMINAL MARKERS - DIRECT APPLIED	GUARDRAIL MARKER TYPE A	BARRIER WALL MARKER TYPE B
			78201000	78200410	78200520
			EACH	EACH	EACH
STA. 677+70.30	LT		1		
STA. 676+90.30	LT	80.0		1	
STA. 676+10.30	LT	80.0		1	
STA. 675+30.30	LT	80.0		1	
STA. 674+50.30	LT	80.0			1
STA. 673+70.30	LT	80.0			1
STA. 672+90.30	LT	80.0		1	
STA. 672+10.30	LT	80.0		1	
STA. 671+33.00	LT	77.3	1		
STA. 671+22.50	RT		1		
STA. 672+02.50	RT	80.0		1	
STA. 672+82.50	RT	80.0		1	
STA. 673+62.50	RT	80.0		1	
STA. 674+42.50	RT	80.0			1
STA. 675+22.50	RT	80.0			1
STA. 676+02.50	RT	80.0		1	
STA. 676+82.50	RT	80.0		1	
STA. 677+59.75	RT	77.3	1		
TOTAL			4	10	4

CONSTRUCTION LAYOUT	Z0013798
LOCATION	L. SUM
ENTIRE JOB SITE	1
TOTAL	1

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	78300200
LOCATION STATION TO STATION	QUANTITY EACH
STA. 668+70.00 TO STA. 669+75.00	2
STA. 678+70.00 TO STA. 680+50.00	4
TOTAL	6

RAISED REFLECTIVE PAVEMENT MARKER	78100100
LOCATION STATION TO STATION	QUANTITY EACH
STA. 668+70.00 TO STA. 673+54.63	6
STA. 676+00.63 TO STA. 680+50.00	6
(@ 80' SPACING O.C.)	
TOTAL	12

PAVEMENT MARKING REMOVAL	78300105		
LOCATION STATION TO STATION	LT/RT	APPLIED	QUANTITY FOOT
STAGE I			
STA. 668+70.00 TO STA. 679+66.00	LT	EDGELINE	1096
TOTAL			1096

SCHEDULE OF QUANTITIES  
 IL 40 OVER GREEN RIVER  
 F.A.P. RTE 646 (IL RTE 40) SECTION 102 BR-2  
 WHITESIDE COUNTY