



- Notes:
1. Hatched area to be poured after superstructure forms have been removed. Quantity of concrete included with Concrete Superstructure.
  2. Space reinforcement in cap to miss anchor bolts.
  3. Pour steps monolithically with cap.
  4. Reinforcement bars designated (E) shall be epoxy coated.
  5. Quantity of concrete in end post included with Concrete Superstructure on sheet 7 of 24.

**NORTH ABUTMENT DETAILS**  
IL RTE 40 OVER GREEN RIVER  
F.A.P. 646 SECTION (102)BR-2  
WHITESIDE COUNTY  
STATION 674+77.63  
S.N. 098-0018

DESIGNED	DDB	<p>RANDOLPH &amp; ASSOCIATES, INC. 111 N. PEPPER PARKWAY, PEORIA, IL 61615-2134 TEL. 309-253-2888 FAX. 309-253-8388 11.000.001-1001 WWW.RANDOLPH-ASSOCIATES.COM</p>	FILE NUMBER	136.111
CHECKED	JFJ		DATE	June 2004
DRAWN	JDB			
IN CHARGE	DDB			

R:\Projects\0136\0136-111\_green.ph\1\Bridge\Planse\15 NORTH ABUT DETAILS.dgn 8/9/2005 9:59:23 AM

A-1-D 9-01-03