

| | | | | |
|---------------------|----------|------------------|--------------|-----------|
| F.A. PROJECT NO. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 513 | 116R-4 | DEKALB | 416 | 6 |
| STA. | TO STA. | | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

| CODE NUMBER | PAY ITEMS | UNIT | 80% FED / 20% STATE TOTAL QUANTITY 1 000-2A |
|-------------|---|---------|---|
| 63200310 | GUARDRAIL REMOVAL | FOOT | 104 |
| 63301210 | REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL, TYPE A | FOOT | 75 |
| 63500105 | DELINEATORS | EACH | 2 |
| 66410400 | CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED | FOOT | 166 |
| 66600105 | FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS | EACH | 8 |
| 66700305 | PERMANENT SURVEY MARKERS, TYPE II | EACH | 7 |
| 66900105 | UNDERGROUND STORAGE TANK REMOVAL | EACH | 6 |
| 66900200 | NON-SPECIAL WASTE DISPOSAL | CU YD | 895 |
| * 66900450 | SPECIAL WASTE PLANS AND REPORT | L SUM | 1 |
| 66900530 | SOIL DISPOSAL ANALYSIS | EACH | 2 |
| 66901000 | BACKFILL PLUGS | CU.YD. | 27 |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 24 |
| 67100100 | MOBILIZATION | L SUM | 1 |
| 70100200 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701331 | EACH | 4 |
| 70100500 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701326 | L SUM | 1 |
| 70102620 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701501 | L SUM | 1 |
| 70102622 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701502 | L SUM | 1 |
| 70102640 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701801 | L SUM | 1 |
| 70103815 | TRAFFIC CONTROL SURVEILLANCE | CAL DAY | 300 |
| 70300520 | PAVEMENT MARKING TAPE, TYPE III, 4" | FOOT | 16,178 |
| 70300610 | TEMPORARY PAINT PAVEMENT MARKING, LETTERS AND SYMBOLS | SO FT | 1,248 |
| 70300625 | TEMPORARY PAINT PAVEMENT MARKING LINE 4" | FOOT | 16,564 |
| 70300635 | TEMPORARY PAINT PAVEMENT MARKING LINE 6" | FOOT | 824 |
| 70300640 | TEMPORARY PAINT PAVEMENT MARKING LINE 8" | FOOT | 2,086 |
| 70300645 | TEMPORARY PAINT PAVEMENT MARKING LINE 12" | FOOT | 877 |
| 70300660 | TEMPORARY PAINT PAVEMENT MARKING LINE 24" | FOOT | 298 |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SO FT | 8,988 |
| * 78000100 | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | SO FT | 1,966 |
| * 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 24,723 |
| * 78000400 | THERMOPLASTIC PAVEMENT MARKING - LINE 6" | FOOT | 1,305 |
| * 78000500 | THERMOPLASTIC PAVEMENT MARKING - LINE 8" | FOOT | 2,988 |
| * 78000600 | THERMOPLASTIC PAVEMENT MARKING - LINE 12" | FOOT | 1,180 |
| * 78000650 | THERMOPLASTIC PAVEMENT MARKING - LINE 24" | FOOT | 419 |
| * 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 205 |
| 78200410 | GUARDRAIL MARKERS, TYPE A | EACH | 6 |
| 78300100 | PAVEMENT MARKING REMOVAL | SO FT | 2,243 |

PLOT DATE = Fri Sep 02 09:56:37 2005
 FILE NAME = C:\Users\jordanhd\Documents\6451Z\116R-4.dgn
 PLOT SCALE = 80,0000 / IN.
 USER NAME = jordanhd