

F.A.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
573	J168-4	DEKALB	416	1
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CODE NUMBER	PAY ITEMS	UNIT	80% FED / 20% STATE TOTAL QUANTITY 1 000-2A
* A2001714	TREE, ACER SACCHARUM (SUGAR MAPLE), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	5
* A2007814	TREE, TILIA AMERICANA (AMERICAN LINDEN / BASSWOOD), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	5
* B2002716	TREE, MALUS ADIRONDACK (ADIRONDACK CRABAPPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	5
* B2004114	TREE, MALUS PRAIRIFIRE (PRAIRIFIRE CRABAPPLE), 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	4
* B2004814	TREE, MALUS SARGENTII (SARGENT CRABAPPLE), 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	5
* D2001772	EVERGREEN, PICEA ABIES (NORWAY SPRUCE), 6' HEIGHT, BALLED AND BURLAPPED	EACH	37
X0300351	CONCRETE STEP REMOVAL	EACH	10
* X0322033	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	1,712
* X0322089	STORM SEWER (WATER MAIN REQUIREMENTS) 36 INCH	FOOT	317
* X0322090	STORM SEWER (WATER MAIN REQUIREMENTS) 42 INCH	FOOT	466
X0322118	REMOVE CONCRETE FLARED END SECTIONS	EACH	2
* X0322125	STORM SEWER (WATER MAIN REQUIREMENTS) 24 INCH	FOOT	2,967
* X0322127	STORM SEWER (WATER MAIN REQUIREMENTS) 30 INCH	FOOT	1,692
X0322352	SEEDING MOBILIZATION	EACH	2
* X0322782	SANITARY SEWER, PVC (D3034) SDR 26, 8"	FOOT	115
X0322903	SAW CUTTING, (FULL DEPTH)	FOOT	144
X0539800	TREE GRATES	EACH	9
X0712400	TEMPORARY PAVEMENT	SQ YD	12,809
X0919000	TEMPORARY PAVEMENT REMOVAL	SQ YD	12,809
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	1,886
X4066526	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	817
X4066656	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N70	TON	1,383
X4066810	POLYMERIZED LEVELING BINDER (HAND METHOD), SUPERPAVE N70	TON	10
X4066910	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	TON	391
X4402815	ISLAND PAVEMENT REMOVAL AND REPLACEMENT	SQ FT	210
X4409420	BITUMINOUS SURFACE REMOVAL 3 1/4"	SQ YD	523
X6330103	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL, TANGENT	EACH	2
XX000061	STUMP REMOVAL	EACH	1
XX001135	PAVEMENT PATCHING SPECIAL	SQ YD	2,551
XX003000	CLASS SI CONCRETE STEPS	CU YD	70
* XX004205	OUTSIDE DROP CONNECTION	EACH	1
XX146400	STORM SEWER REMOVAL	FOOT	2,050

PLOT DATE = Wed Sep 14 13:00:20 2005
 FILE NAME = C:\pwork\64517\64517.dgn
 PLOT SCALE = 50.0000 / IN.
 USER NAME = jpr-dshhd