

F.A.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
573	J168-4	DEKALB	416	39
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

44000500	COMBINATION CURB AND GUTTER REMOVAL	REMARKS
EQ FT	LOCATION	
	US 30	
61.0	RT 798+50.00 TO 798+74.00	
43.0	RT 799+19.54 TO 799+89.70	
192.1	LT 812+52.96 TO 814+45.08	
164.8	RT 817+23.68 TO 818+88.45	
153.3	LT 818+06.36 TO 819+59.62	
382.0	RT 819+17.10 TO 822+99.11	
157.3	LT 821+13.41 TO 822+70.74	
286.9	LT 823+51.21 TO 826+38.07	
132.9	RT 824+22.23 TO 825+55.08	
315.4	RT 826+73.08 TO 829+88.44	
242.1	LT 826+82.11 TO 829+24.19	
242.0	RT 830+31.12 TO 832+73.16	
316.6	LT 830+39.85 TO 833+56.42	
	SYCAMORE ST.	
48.0	RT 139+08.07 TO 139+56.11	
	MAPLE ST.	
117.5	LT 160+39.85 TO 161+57.33	
90.9	RT 160+61.07 TO 161+51.92	
	OAK ST.	
178.3	RT 181+69.60 TO 183+42.60	
25.0	LT 182+66.77 TO 182+83.83	
59.7	LT 182+94.72 TO 183+40.09	
20.1	LT 185+06.33	NW CORNER
28.5	RT 185+06.33	NE CORNER
	WALNUT ST	
21.6	LT 205+08.45	NW CORNER
20.0	RT 205+08.50	NE CORNER
	COSTER PL	
24.9	RT 224+23.43	NW CORNER
28.4	RT 224+23.40	NE CORNER
	DONALD ST.	
23.3	LT 244+26.16	NW CORNER
15.0	LT 242+70.00 TO 242+85.00	ADJACENT TO DRIVEWAY
<b>TOTAL</b>	<b>3,390.6</b>	

44000600	SIDEWALK REMOVAL	REMARKS
SQ.FT	LOCATION	
	US 30	
39.2	LT 797+08.00 TO 797+08.00	
1,494.5	RT 810+95.32 TO 814+55.04	
46.2	LT 812+12.24 TO 812+19.77	
3,556.7	LT 812+49.59 TO 819+74.44	
1,678.0	RT 814+92.20 TO 818+86.16	
1,323.1	LT 819+99.27 TO 823+00.95	
1,627.0	RT 819+10.96 TO 822+98.50	
2,146.8	LT 823+29.54 TO 826+42.16	
1,872.1	RT 823+31.55 TO 826+39.96	
2,400.9	RT 826+74.54 TO 829+82.38	
3,156.5	LT 826+75.64 TO 829+79.51	
3,745.3	LT 830+23.90 TO 833+61.71	
2,352.7	RT 830+31.03 TO 832+71.75	
1,670.6	LT 833+90.67 TO 837+30.98	
1,609.2	LT 837+60.72 TO 841+50.56	
2,611.4	LT 841+79.49 TO 847+97.56	
38.6	RT 846+67.54 TO 846+77.67	
2,031.1	LT 848+26.42 TO 852+64.37	
1,350.6	LT 852+89.68 TO 855+97.84	
	RAY ST.	
500.1	RT 898+51.29 TO 899+76.41	
	WALGREN ST.	
381.8	RT 68+94.29 TO 69+72.37	
555.8	LT 68+25.00 TO 69+70.51	
	S. VIEW ST.	
558.6	LT 78+44.14 TO 79+68.22	
484.3	RT 78+43.89 TO 79+69.49	
	N. VIEW ST.	
324.0	LT 80+32.59 TO 81+15.34	
48.2	RT 80+32.62 TO 80+43.02	
	GARFIELD ST.	
322.5	RT 100+34.57 TO 101+17.07	
	MAY ST.	
156.7	LT 119+29.10 TO 119+65.11	
477.3	LT 120+34.36 TO 121+59.15	
415.5	LT 120+97.45 TO 121+56.64	

44000600	SIDEWALK REMOVAL (CONT.)	REMARKS
SQ.FT	LOCATION	
	US 30	
	SYCAMORE ST.	
398.0	RT 138+79.18 TO 139+64.62	
550.3	LT 138+96.85 TO 139+66.61	
245.5	LT 141+11.32 TO 141+55.47	
	MAPLE ST.	
656.5	RT 160+34.30 TO 161+85.38	
617.2	LT 160+37.09 TO 161+56.23	
	OAK ST.	
265.7	LT 179+15.54 TO 179+70.19	
659.7	RT 180+34.48 TO 181+84.19	
749.3	LT 180+34.82 TO 181+79.92	
30.4	RT 183+44.68	
123.0	LT 185+08.75	
124.2	RT 185+09.45	
	WALNUT ST.	
115.5	LT 205+06.44	
108.8	RT 205+06.92	
	COSTER PL.	
59.3	RT 220+30.45 TO 220+45.78	
116.7	RT 220+30.45	
114.9	LT 220+89.79	
	DONALD ST.	
68.5	LT 244+24.21	
70.8	RT 244+25.36	
	REESE ST.	
265.4	LT 260+26.96 TO 260+97.22	
<b>TOTAL</b>	<b>44,314.8</b>	

44002020	CONCRETE MEDIAN SURFACE REMOVAL	REMARKS
SQ.FT.	LOCATION	
181.4	RT 798+50.00 TO 798+74.00	ISLAND SURFACE TO BE REMOVED
<b>TOTAL</b>	<b>181.4</b>	

44004300	PAVEMENT BREAKING	REMARKS
SQ.YD.	LOCATION	
388.9	860+75.00 TO 862+50.00	10" CONCRETE
<b>TOTAL</b>	<b>388.9</b>	

44200998	CLASS B PATCHES, TYPE III, 12 INCH	REMARKS
SQ.YD.	LOCATION	
42.6	799+45.0	
<b>TOTAL</b>	<b>42.6</b>	

44213200	SAW CUTS	REMARKS
EQ FT	LOCATION	
69.2	RT 798+50.2 TO 798+78.10	
67.8	RT 802+32.8 TO 802+50.70	
<b>TOTAL</b>	<b>136.9</b>	

44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	REMARKS
EQ FT	LOCATION	
463.0	LT 793+05.00 TO 797+68.00	NEW WIDENING
303.0	LT 800+00.00 TO 803+03.00	NEW WIDENING
1,382.0	LT 785+98.00 TO 799+80.00	OLD WIDENING
277.5	LT 797+68.00 TO 799+80.00	OLD WIDENING
400.1	RT 792+56.90 TO 796+57.00	NEW WIDENING
185.0	RT 799+65.00 TO 801+50.00	NEW WIDENING
1,328.0	RT 786+37.00 TO 799+65.00	OLD WIDENING
153.0	RT 801+50.00 TO 803+03.00	OLD WIDENING
6,730.0	803+00.00 TO 870+30.00	STAGE TWO CONSTRUCTION
43.0	N. VIEW ST	STAGE TWO CONSTRUCTION
40.0	GARFIELD ST	STAGE TWO CONSTRUCTION
42.0	MAY ST	STAGE TWO CONSTRUCTION
35.0	SYCAMORE ST	STAGE TWO CONSTRUCTION
37.0	MAPLE ST	STAGE TWO CONSTRUCTION
39.0	OAK ST	STAGE TWO CONSTRUCTION
48.0	WALNUT ST	STAGE TWO CONSTRUCTION
47.0	COSTER PL	STAGE TWO CONSTRUCTION
54.0	DONALD ST	STAGE TWO CONSTRUCTION
62.0	REES ST	STAGE TWO CONSTRUCTION

PLOT DATE = Fri Sep 02 09:35:55 2005  
 FILE NAME = C:\p\c\jones\200709\dm1700c-vr.dgn  
 PLOT SCALE = 50.0000 / 1 IN.  
 USER NAME = jonesdm