CONTRACT NO. 64517

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
573	1168-4	DEKALB	416	43
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

60610400 COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24

EOOT	LOCATION					REMARKS
	S. SOMONAUK RD.					
16.0		RT	19+62.20	TO	19+80.23	ISLAND
TOTAL 16.0						

60618300 CONCRETE MEDIAN SURFACE, 4 INCH

SQ FT	LOCATION					REMARKS
	S. SOMONAUK RD.					
117.8		RT	19+62.20	TO	19+80.23	ISLAND
	HIGH SCHOOL ENTRANCE					
57.7		LT	300+45.00	TO	300+70.90	ISLAND
TOTAL 175.5						

61133100 FIELD TILE JUNCTION VAULTS, 2' DIA.

EACH	LOCATION	REMARKS
2	LT/RT	USE IN CASE OF FIELD TILE INTERCEPTION
TOTAL 2		

61140000 STORM SEWERS, SPECIAL 8"

EOOT	LOCATION	REMARKS
100	LT/RT	USE IN CASE OF FIELD TILE INTERCEPTION
TOTAL 100		

61140100 STORM SEWERS, SPECIAL 10"

EOOT	LOCATION	REMARKS
100	LT/RT	USE IN CASE OF FIELD TILE INTERCEPTION
TOTAL 100		

61140200 STORM SEWERS, SPECIAL 12"

EOOT	LOCATION	
100	LT/RT	USE IN CASE OF FIELD TILE INTERCEPTION
TOTAL 100		

63000000 STEEL PLATE BEAM GUARDRAIL TYPE A

EOOT	LOCATION					REMARKS
	US 30					
150.0		LT	786+65.92	TO	788+15.92	
37.5		RT	787+05.73	TO	787+43.23	
TOTAL 187.5						

63100085 TRAFFIC BARRIER TERMINAL, TYPE 6

EACH	LOCATION					REMARKS
	US 30					
1		LT	785+97.17	TO	786+28.42	
1		RT	786+36.98	TO	786+68.23	
TOTAL 2						

63200310 GUARDRAIL REMOVAL

EOOT	LOCATION					REMARKS
	US 30					
33.15		LT	785+97.15	TO	786+24.40	TYPE 6 TERMINAL
33.15		RT	786+37.17	TO	786+68.42	TYPE 6 TERMINAL
37.50		LT	856+30.55	TO	856+52.16	NE QUAD. OF US 30 AND SANDWICH RD.
TOTAL 103.80						

63301210 REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL, TYPE A

EOOT	LOCATION					REMARKS
	US 30					
37.5		LT	786+28.42	TO	786+65.92	
37.5		RT	786+68.23	TO	787+05.73	
TOTAL 75.0						

63500105 DELINEATORS

EACH	LOCATION					REMARKS
	US 30					
1		LT	788+65.90			GUARDRAIL TERMINAL END SECTION
1		RT	787+93.21			GUARDRAIL TERMINAL END SECTION
TOTAL 2						

66410400 CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED

EOOT	LOCATION					REMARKS
166.0	RT	803+81.00	TO	805+40.00		
TOTAL 166.0						

66600105 FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS

EACH	LOCATION		REMARKS
1	RT 61.28	794+38.28	METHOD A
1	RT 79.88	797+53.24	METHOD A
1	LT 55.00	869+00.00	METHOD A
1	RT 50.00	869+00.00	METHOD A
1	RT 40.15	870+00.00	METHOD A
1	LT 45.00	871+00.00	METHOD A
1	LT 45.00	873+00.00	METHOD A
1	LT 44.59	873+08.17	METHOD A
TOTAL 8			

66700305 PERMANENT SURVEY MARKERS, TYPE II

EACH	LOCATION			REMARKS
1	797+30.019	RT	55.000	CAST-IN-PLACE
1	805+44.538	LT	40.000	CAST-IN-PLACE
1	814+10.437	LT	24.620	CAST-IN-PLACE
1	842+40.267	RT	41.200	CAST-IN-PLACE
1	846+48.362	LT	29.040	CAST-IN-PLACE
1	852+74.858	RT	36.100	CAST-IN-PLACE
1	870+31.296	LT	36.650	CAST-IN-PLACE
TOTAL 7				

70300520 PAVEMENT MARKING TAPE, TYPE III, 4"

EOOT	LOCATION				REMARKS
	US 30				
	STAGE 2				
778	LT EDGE LINE	795+25.00	TO	803+03.00	
1,556	CENTERLINE	795+25.00	TO	803+03.00	DOUBLE 4" LINES
778	RT EDGE LINE	795+25.00	TO	803+03.00	
335	LT EDGE LINE	837+90.00	TO	841+25.00	
670	CENTERLINE	837+90.00	TO	841+25.00	DOUBLE 4" LINES
335	RT EDGE LINE	837+90.00	TO	841+25.00	
	STAGE 2A				
175	LT EDGE LINE	832+50.00	TO	834+25.00	
350	CENTERLINE	832+50.00	TO	834+25.00	
225	LT EDGE LINE	838+00.00	TO	840+25.00	
400	CENTERLINE	838+00.00	TO	840+00.00	
	STAGE 3				
800	LT EDGE LINE	795+00.00	TO	803+00.00	
1,600	CENTERLINE	795+00.00	TO	803+00.00	DOUBLE 4" LINES
800	RT EDGE LINE	795+00.00	TO	803+00.00	
350	LT EDGE LINE	838+00.00	TO	841+50.00	
700	CENTERLINE	838+00.00	TO	841+50.00	DOUBLE 4" LINES
350	RT EDGE LINE	838+00.00	TO	841+50.00	
	STAGE 5				
175	LT EDGE LINE	838+75.00	TO	840+50.00	
350	CENTERLINE	838+75.00	TO	840+50.00	DOUBLE 4" LINES
175	RT EDGE LINE	838+75.00	TO	840+50.00	
619	LT EDGE LINE	870+31.00	TO	876+50.00	
1,238	CENTERLINE	870+31.00	TO	876+50.00	DOUBLE 4" LINES
619	RT EDGE LINE	870+31.00	TO	876+50.00	
	STAGE 6				
100	LT EDGE LINE	836+75.00	TO	837+75.00	
200	CENTERLINE	836+75.00	TO	837+75.00	DOUBLE 4" LINES
100	RT EDGE LINE	836+75.00	TO	837+75.00	
600	LT EDGE LINE	870+25.00	TO	876+25.00	
1,200	CENTERLINE	870+25.00	TO	876+25.00	DOUBLE 4" LINES
600	RT EDGE LINE	870+25.00	TO	876+25.00	
TOTAL 16,178					

PLOT DATE = Fri Sep 02 09:12:25 2005
FILE NAME = P:\Dekalb\64517\01\sd01700cnr.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = jordanhd

SCHEDULE OF QUANTITIES